

SCIENTIFIC REPORTS



OPEN

Designing perfect linear polarization converters using perfect electric and magnetic conducting surfaces

Received: 25 August 2016
Accepted: 15 November 2016
Published: 13 December 2016

Gaochao Zhou, Xudong Tao, Ze Shen, Guanghao Zhu, Biaobing Jin, Lin Kang, Weiwei Xu, Jian Chen & Peiheng Wu

We propose a kind of general framework for the design of a perfect linear polarization converter that works in the transmission mode. Using an intuitive picture that is based on the method of bi-directional polarization mode decomposition, it is shown that when the device under consideration simultaneously possesses two complementary symmetry planes, with one being equivalent to a perfect electric conducting surface and the other being equivalent to a perfect magnetic conducting surface, linear polarization conversion can occur with an efficiency of 100% in the absence of absorptive losses. The proposed framework is validated by two design examples that operate near 10GHz, where the numerical, experimental and analytic results are in good agreements.

Polarization is an important characteristic of electromagnetic (EM) waves. In many related applications such as life science microscopy, fiber-optic communication and radar remote sensing, it is often required that the polarization states of the light must be controlled at will. To this end, conventional approaches are well-developed by taking advantage of birefringent crystals, Faraday rotations or Brewster angle effects¹. These approaches, although prevail in modern laboratories, are unfortunately bulky and heavy, and thus being not suitable for miniaturized integrations. Such a problem can be mitigated with the help of advanced designs based on metasurfaces, as witnessed in the past decade^{2–11}. The building elements of the metasurfaces are the so-called unit cells, of which the dimensions are much smaller comparing to the working wavelengths. By precisely tailoring the electromagnetic responses of the unit cells, various functional devices such as polarization converters^{12–22}, flat lenses^{8,11,23} and phase gradient mirrors^{24–26} have been realized with subwavelength scale sizes, thereby opening a new route to manipulating light properties in arbitrary manners^{9,21,27–30}.

Among various polarization manipulating devices, linear polarization converter is perhaps the most widely used one. A linear polarization converter rotates the polarization direction of a linearly polarized electromagnetic wave by 90 degree, making it perpendicular to the original one. Owing to its indispensable importance in many practical situations, linear polarization converter has attracted considerable amount of research efforts in recent years. Stimulated by these efforts, a variety of metasurface related linear polarization converters have been developed, such as those based on the chirality effect^{12,13,31–33}, polarization dependent resonance effect^{34–38} and stacked grating effect^{14,39,40}, just to name a few. These innovative polarization converting devices are expected to lead to significant technical advances in areas such as microwave and terahertz electronics^{12,40}, where unlike the case of optical electronics, advantages of broad bandwidth and compact sizes are difficult to be offered by their traditional counterparts.

In this article, we present a design framework for perfect linear polarization converters. In the Result section, we first provide an intuitively explanation of the underlying principle. It is shown that perfect linear polarization conversion can be achieved if the device under consideration simultaneously possesses two symmetric mirror planes, with one being equivalent to a perfect electric conducting surface and the other being equivalent to a perfect magnetic conducting surface, depending on the way that the device is virtually excited. Following that picture, we next utilize metasurfaces to physically construct the required dual perfect conducting surfaces. Two different realization examples operating near 10 GHz are given. Numerical, experimental and analytic works

School of Electronic Science and Engineering, Nanjing University, Nanjing, 210023, China. Correspondence and requests for materials should be addressed to G.Z. (email: gzhzhu@nju.edu.cn) or B.J. (email: bbjin@nju.edu.cn)




Figure 1. Principle of the design framework. (a) An x-polarized wave incident from the left side of a metasurface can be decomposed as a superposition of two virtual bi-directional excitations. (b) Illustration of the first type of virtual bi-directional excitation, which is referred as the E excitation. (c) Illustration of the second type of virtual bi-directional excitation, which is referred as the H excitation.

carried out on these two realization cases confirm the predicted perfect linear polarization conversions, thereby provide a solid validation of the proposed design framework for perfect linear polarization converters.

Result

Design framework. To illustrate the working principle of the proposed design framework, consider a lossless metasurface under illumination of an x-polarized electromagnetic wave incident from the left side. As shown by Fig. 1(a), such a one-directional excitation can be decomposed as a superposition of two virtual bi-directional excitations, where the two imaginary sources at the right side of the metasurface are polarized along the positive and negative directions of the y axis respectively. For clarity, the former virtual bi-directional excitation is referred as the E excitation while the latter virtual bi-directional excitation is referred as the H excitation. Without much effort, it is ready to see that at the plane of the metasurface, the electric field (and also the associated magnetic field) of the E excitation is polarized along the $\hat{x} + \hat{y}$ direction while the magnetic field (and also the associated electric field) of the H excitation is polarized along the $-\hat{x} + \hat{y}$ direction. Assuming that the metasurface has an electric type resonance if the driving electric field is polarized along the $\hat{x} + \hat{y}$ direction, for E excitation it will then behave as a perfect electric conducting surface at resonances. As a consequence, the two virtual waves incident from the left and right sides will be totally reflected, but with a π phase shift being imposed on the reflected electric field. Such a situation is illustrated in Fig. 1(b). On the other hand, assuming that the metasurface has a magnetic type resonance if the driving magnetic field is polarized along the $-\hat{x} + \hat{y}$ direction, for H excitation it will then behave as a perfect magnetic conducting surface. As illustrated in Fig. 1(c), a π phase shift will be imposed on the magnetic field of the two reflected virtual waves. When these two scenarios have a degenerate operating frequency, by taking a superposition of the reflected electromagnetic waves at that frequency, it follows that the overall reflected field is completely cancelled out at the left side of the metasurface and the electromagnetic field is 100% transmitted with the electric component being polarized along the y direction. In other words, perfect linear polarization conversion can be realized in this manner.

Device realizations. The theoretical framework outlined above suggests that in order to achieve perfect linear polarization conversion, the metasurface needs to possess two degenerate and complementary resonances, with one being electric and the other being magnetic. To validate the framework and elaborate more on its principle, we design two types of perfect linear polarization converters that operate near 10 GHz by using different methods to realize the required dual resonances.




Figure 2. Design case I. (a) Schematics of the proposed device. (b) The proposed device under E excitation, where the cut-wire is the only activated element. (c) The proposed device under H excitation, where the double-U is the only activated element. (d) Numerically simulated and experimentally measured power transmittances for the converted and unconverted polarization components. The inset shows the photograph of the fabricated device. Note that the cut-wire and the double-U are degenerate in term of resonant frequencies.

Design case I: a narrow band linear polarization converter. Figure 2(a) sketches the unit cell of the linear polarization converter of the first case, which consists of a double-U structure and a cut-wire embedded in a thin substrate layer. Note that the double-U structure and the cut-wire are parallel to each other and are geometrically oriented along the $\hat{x} + \hat{y}$ direction. Shown by Fig. 2(b), under case of E excitation, because the overall driving electric and magnetic fields are along the $\hat{x} + \hat{y}$ direction, the double-U structure is deactivated, leaving the cut-wire as the only active component. When properly tuned in resonance, the cut-wire behaves as a perfect electric conducting surface. On the other hand, as shown by Fig. 2(c), under case of H excitation, because the overall driving electric and magnetic fields are along the $-\hat{x} + \hat{y}$ direction, the cut-wire is deactivated, leaving the double-U structure as the only active component. In this case, if tuned properly, the double-U structure shall act as a perfect magnetic conducting surface. According to the proposed general design framework, when the double-U structure and the cut-wire have degenerate resonant frequencies, perfect linear polarization then can be achieved. It should be noted that the magnetic resonance of the double-U structure originates from the induced magnetic flux flowing across the section of the double-U structure and in principle can also be provided with single-U structures⁴¹. Here we choose to use the double-U structure because it enables a more compact device size when comparing to the single-U case.

We first use finite element method based numerical simulations to confirm the above theoretical prediction. Illustrated by the right part of Fig. 2(a), the parameters of the simulated unit cell are $l_1 = 4.65$ mm, $w_1 = 0.6$ mm, $g_1 = 0.4$ mm, $l_2 = 12.4$ mm, $w_2 = 0.4$ mm, $g_2 = 1$ mm and $p = 10$ mm respectively. Note that these parameters are determined in such a way that the double-U structure and the cut-wire have degenerate resonant frequencies

near 10 GHz. In our simulations, the double-U structure and cut-wire are assumed to be made of copper, whose conductivity is 5.8×10^7 S/m. The substrate is assumed to be made of a 1.0 mm thick F4BK slab, of which the permittivity is 2.25 and the loss tangent is 0.0009. The solid lines in Fig. 2(d) plot the numerically obtained power transmittances for the converted and unconverted polarization components (denoted by T_{xy} and T_{xx} respectively therein). It can be seen that due to the deliberately tuned resonance degeneracy, there exists a narrow peak standing upon a broad peak in the transmittance curve for the converted component. The narrow peak corresponds to the resonance of the double-U structure while the broad peak corresponds to the resonance of the cut-wire. A constructive interference of these two peaks therefore leads to an enhanced polarization conversion efficiency at ~ 10 GHz. We remark that the peak value of the polarization conversion efficiency is $\sim 80\%$ instead of 100%. Such a discrepancy is attributed to be primarily caused by the absorption of the unit cell. Methods for reducing the conversion loss will be presented in the Discussion section. Moreover, in order to provide further validations, experimental works have also been carried out. The inset of Fig. 2(d) shows the fabricated device, which has a small thickness of 1 mm and a lateral size of 15 cm. The experimental data taken from the fabricated sample for the transmittances of the polarization converted and unconverted components are plotted by the symbols in Fig. 2(d). A good agreement between the numerical and experimental results can be identified.

The perfect linear polarization conversion process can be analytically treated by adopting the wave scattering picture. In such a picture, the overall field is regarded as a superposition of the incident wave and the scattered wave. Relating to design case I, the incident wave is from the realistic excitation source placed at the left side of the metasurface and reads as

$$\mathbf{E}_i = \exp(-ikz + i\omega t)\hat{x}. \quad (1)$$

The scattered wave is from the electrical currents that flow on the metasurface and thus should be calculated in accordance to the way that the metasurface is excited. For the case of E excitation, only the cut-wire is activated. Since the electrical current flowing on the cut-wire is oscillating along the $\hat{x} + \hat{y}$ direction, the scattered field, or equivalently the field radiated by the cut-wire current, would also be polarized along the $\hat{x} + \hat{y}$ direction. Taking such a consideration into account, the scattered field then can be written as

$$\mathbf{E}_s|_E = \frac{1}{2} \frac{-i\omega\gamma_E^r}{\omega_E^2 - \omega^2 + i\omega(\gamma_E^a + \gamma_E^r)} \exp(-ikz + i\omega t) \cdot (\hat{x} + \hat{y}), \quad (2)$$

where the first factor of 1/2 describes the amplitude of the scattered field, and the second factor describes the electric resonance experienced by the current excited on the cut-wire, of which the resonant frequency is ω_E and the absorptive and radiative damping rates are γ_E^a and γ_E^r respectively³⁵. We emphasize that the coefficient of 1/2 is determined from the fact that when the cut-wire is in resonance, it should behave as a perfect electric conducting surface in the absence of absorptive losses. As a result, the electric field radiated by the cut-wire and that by the two virtual sources of the E excitation should be of the same amplitude but out of phase at the cut-wire plane position. Following a similar treatment, for the case of H excitation, the scattered field, or equivalently the field radiated by the electrical current flowing on the double-U structure, reads as

$$\mathbf{E}_s|_H = \frac{1}{2} \frac{-i\omega\gamma_H^r}{\omega_H^2 - \omega^2 + i\omega(\gamma_H^a + \gamma_H^r)} \exp(-ikz + i\omega t) \cdot (\hat{x} + \hat{y}), \quad (3)$$

where the second factor describes a magnetic resonance experienced by the current excited on the double-U structure, of which the resonant frequency is ω_H and the absorptive and radiative damping rates are γ_H^a and γ_H^r respectively. The overall field at the right side of the metasurface can be obtained by taking a summation over the field components given by Eqs (1–3), leading to the following expressions for the amplitude transmittances of the converted and unconverted polarization components

$$t_{yx} = \frac{1}{2} \frac{-i\omega\gamma_E^r}{\omega_E^2 - \omega^2 + i\omega(\gamma_E^a + \gamma_E^r)} + \frac{1}{2} \frac{-i\omega\gamma_H^r}{\omega_H^2 - \omega^2 + i\omega(\gamma_H^a + \gamma_H^r)}, \quad (4)$$

$$t_{xx} = 1 + \frac{1}{2} \frac{-i\omega\gamma_E^r}{\omega_E^2 - \omega^2 + i\omega(\gamma_E^a + \gamma_E^r)} + \frac{1}{2} \frac{-i\omega\gamma_H^r}{\omega_H^2 - \omega^2 + i\omega(\gamma_H^a + \gamma_H^r)}. \quad (5)$$

The analytic results obtained from Eqs (4 and 5) are plotted in Fig. 3 in together with the experimental data measured previously. In generating the analytic curves, fitting parameters with $\gamma_E^a = 0$, $\gamma_E^r = 2\pi \cdot 4.46$ GHz, $\omega_E = 2\pi \cdot 9.32$ GHz, $\gamma_H^a = 2\pi \cdot 0.08$ GHz, $\gamma_H^r = 2\pi \cdot 0.17$ GHz and $\omega_H = 2\pi \cdot 10.32$ GHz have been used. Again, a good agreement between the analytic and experimental results can be identified. We remark that the theoretical explanation could be also be made by first decomposing the incident fields along the $\hat{x} + \hat{y}$ and $-\hat{x} + \hat{y}$ polarization directions in a one-directional manner and then evaluating the transmitted fields respectively. Comparing to such a procedure that is widely used in the literatures, our bi-directional excitation treatment emphasizes the role played by the degenerate and complementary resonances, and thus helps to illustrate the proposed general mechanism for perfect linear polarization converters.

Design case II: a broadband linear polarization converter. Owing to the narrow magnetic resonance of the double-U structure, the polarization conversion efficiency achieved in design case I is limited within a small frequency band. To increase the conversion bandwidth, we take different approaches to realize the




Figure 3. Analytically calculated and experimentally measured power transmittances of the converted and unconverted polarization components for design case I.

required perfect electric and magnetic metasurfaces with broadened responses. The results are presented here as design case II.

Figure 4(a) sketches the unit cell of the linear polarization converter of the second case, which consists of a symmetric split ring and two wire gratings integrated in a dielectric substrate. The split ring is placed at the central plane of the substrate with openings aligned along the $\hat{x} + \hat{y}$ direction, and the two wire gratings are placed at the front and back ends of the substrate with grating wires aligned along the x and y directions respectively. It should be noted that such a device design falls into the category of the stacked gratings and has no fundamental difference from those studied previously by several other groups^{14,39,40}. Figure 4(b) and (c) sketch the complementary resonance picture of design case II, in accordance to the situations of E and H excitations respectively. Note that because the wire gratings located at the proximal ends of the virtual sources are perpendicular to the polarizations of the incident lights, the two virtual waves can pass through them and superpose at the split ring position. For the case of E excitation, since the superposed overall electric field is polarized along the direction formed by the openings of the split ring ($\hat{x} + \hat{y}$), when in resonance, the split ring will act as a perfect electric conducting surface. The two incident virtual waves are thus completely reflected and the roles of the wire gratings at the distal ends are disabled. In other words, the two wire gratings are deactivated at the resonant frequency of the split ring. On the other hand, for the case of H excitation, since the superposed overall electric field is polarized perpendicular to the opening direction of the split ring ($-\hat{x} + \hat{y}$), the split ring is deactivated. The two incident virtual waves thus can pass through the split ring and be reflected back by the wire gratings located at the distal ends of the virtual sources. The separation between the split ring and the distal end wire grating is set to be a quarter of the resonance wavelength of the split ring. This allows an equivalent perfect magnetic conducting surface to be created at the split ring position, provided that the operating frequency is in resonance with the split ring structure. We note that with such an arrangement, the degenerate condition for perfect electric and magnetic conducting surfaces is satisfied.

Numerical works are carried out to evaluate the performance of the device for design case II. Note that similar to design case I, here we have also assumed that the split ring and the wire gratings are made of copper and the substrate is made of F4BK. Referring to Fig. 4(a), parameters used for the numerical simulations are $w_1 = 0.8$ mm, $w_2 = 0.3$ mm, $r = 3.7$ mm, $\alpha = 45^\circ$, $\theta = 30^\circ$, $p = 8$ mm and $d = 10$ mm respectively. These values are determined in such a way that the electric and magnetic resonances drawn by Fig. 4(b) and (c) have degenerate resonant frequencies near 10 GHz. The solid lines in Fig. 4(d) plot the numerically obtained power transmittances of the polarization converted and unconverted components. From Fig. 4(d), it can be seen that within a broad bandwidth, the proposed device can efficiently convert the polarization of the incident wave from the x direction to the y direction. The numerical results are in good agreement with the experimental ones presented by the symbols in Fig. 4(d), which are taken from a fabricated sample shown by the right part of Fig. 4(a).

To theoretically analyze the polarization conversion process of design case II, we resort to the scattering matrix formalism. Owing to the polarization diversity, the linear polarization converter depicted in Fig. 4(a) is essentially a four-port device. The scattering matrix of such a kind four-port device reads as

$$S = \begin{bmatrix} r_{xx} & 0 & 0 & t_{yx} \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ t_{yx} & 0 & 0 & r_{xx} \end{bmatrix}, \quad (6)$$

where the column indexes of 1 and 2 correspond to the x and y polarized channels incident from the left side of the metasurface respectively, and the column indexes of 3 and 4 correspond to the x and y polarized channels incident from the right side of the metasurface respectively. The scattering matrix has the following eigen-vectors




Figure 4. Design case II. (a) Schematics of the proposed device and photograph of the fabricated sample. (b) The proposed device under E excitation. When in resonance, the split ring is the only activated element. (c) The proposed device under H excitation, where the wire grating is the only activated element. (d) Numerically simulated and experimentally measured power transmittances for the converted and unconverted polarization components. Note that the separation between the split ring and the wire gratings, i.e. $d/2$, is a quarter of the resonance wavelength of the split ring structure.

$$|\alpha\rangle = \begin{bmatrix} 0 \\ 0 \\ 1 \\ 0 \end{bmatrix}, \begin{bmatrix} 0 \\ 1 \\ 0 \\ 0 \end{bmatrix}, \begin{bmatrix} 1 \\ 0 \\ 0 \\ 1 \end{bmatrix}, \begin{bmatrix} 1 \\ 0 \\ 0 \\ -1 \end{bmatrix}, \quad (7)$$

of which the two latter ones are in accordance to the E and H excitations respectively. Note that the eigen-vectors of the E and H excitations satisfy the eigen-equation of

$$S|\alpha\rangle = e^{i\theta}|\alpha\rangle. \quad (8)$$

It indicates that the fields of the E and H excitations, when incident on the metasurface, will be totally reflected, in an analogy to the wave reflection phenomenon observed on a terminated transmission line. Inspired by such an analogy, we propose to use the transmission line model to analyze the reflection processes. Figure 5(a) depicts the transmission line model for the case of E excitation. The dielectric slab is modeled by a transmission line with a characteristic impedance of η , while the surrounding air background is modeled by a transmission line with a characteristic impedance of η_0 . The lumped circuit elements of R, L and C describe the resonance of the split ring, while the terminated short describes the wire grating placed at the distal end. Figure 5(b) depicts the transmission line model for the case of H excitation. In this case, since the split ring is deactivated, the lumped circuit elements of R, L and C are absent. Denoting the reflection coefficients for cases of E and H excitations as Γ_E and




Figure 5. Theoretical modeling for design case II. (a) Transmission line model for the case of E excitation. The dashed red line indicates the position of the perfect electric conducting surface. (b) Transmission line model for the case of H excitation. The dashed blue line indicates the position of the perfect magnetic conducting surface. (c) Analytically calculated and numerically simulated power transmittances for the converted polarization component.

Γ_H respectively, using the standard transmission line treatment and with some manipulations, it follows that the amplitude transmittance for the polarization converted component reads as

$$t_{yx} = \frac{1}{2}\Gamma_E + \left(-\frac{1}{2}\right)\Gamma_H = \frac{A}{-B + 2\gamma_a/\gamma_r + i2(\omega^2 - \omega_0^2)/(\omega\gamma_r)}, \tag{9}$$

where

$$A = \frac{n(1 - \cos \varphi)}{(n \cos \varphi + i \sin \varphi)^2}, \tag{10}$$

$$B = \frac{1 - \cos \varphi - in \sin \varphi}{n \cos \varphi + i \sin \varphi}, \tag{11}$$

where $\omega_0 = 1/\sqrt{LC}$, $\gamma_a = \omega_0^2 RC$, and $\gamma_r = \omega_0^2 \eta C$ denote the resonant frequency and the absorptive and radiative losses of the split ring respectively, $n = \eta_0/\eta$ denotes the normalized refractive index of the substrate and $\varphi = nd\omega/c$. The analytic result calculated from Eq. (9) is plotted in Fig. 5(c) in together with the simulated data obtained previously. In generating the analytic curve, fitting parameters with $n = 1.5$, $d = 10$ mm, $\gamma_a = 2\pi \cdot 0.06$ GHz, $\gamma_r = 2\pi \cdot 11.85$ GHz and $\omega_0 = 2\pi \cdot 9.95$ GHz have been used. The good agreement between the analytic and simulated results confirms the validity of our transmission line model based analysis. We remark that the theoretical analysis could also be carried out in a more general manner using the procedure based on multiple reflection interferences¹⁴. However, since the roles of the complementary perfect electric and magnetic conducting surfaces are not explicitly pointed out with such a kind of treatment, the major result presented in this article, i.e. the general framework for the perfect linear polarization converter, is therefore not revealed and the fundamental connection between design cases I and II is absent.

Comparing to case I, the device realized in case II has a much larger operating bandwidth. To explain such a difference, two mechanisms are suggested in accordance to the situations of H excitation and E excitation respectively. Note that for the situation of H excitation, instead of the double-U structure [Fig. 2(c)], we use a quarter-wavelength transformed short [Fig. 5(b)] to realize the perfect magnetic conducting surface. Because the quarter-wavelength transformed short is essentially a single-mirror open cavity of which the quality factor is low

(comparing to that of the double-U structure), the bandwidth of the magnetic resonance is therefore large. On the other hand, note that for the situation of E excitation, instead of the cut-wire [Fig. 2(b)], we use a split ring backed by a quarter-wavelength transformed wire grating [Fig. 5(a)] to realize the perfect electric conducting surface. Although the cut-wire and the split ring may have comparable bandwidths, however, by backing the split ring with a quarter-wavelength transformed wire grating, the bandwidth will be increased. The increase of the bandwidth can be intuitively explained by referring to Fig. 5(a) with loss effect being neglected for sake of simplicity. Note that the overall impedance at the position of the perfect electric conducting surface (marked by the dashed red line) is a parallel sum of a LC resonator and a quarter-wavelength transformed short. When the operating frequency is at the degenerate resonance, the LC resonator has a zero impedance and the quarter-wavelength transformed short has an infinite impedance. The overall impedance is thus zero and the perfect electric conducting surface condition is satisfied. When the operating frequency deviates from the degenerate resonance, the impedance of the LC resonator starts to increase from the null end to the infinity end. This renders the overall impedance also to increase away from zero and the perfect electric conducting surface condition is broken. The growing rate of the overall impedance is slow for design case II because it will be hindered by the accompanying decrease of the impedance of the quarter-wavelength transformed short from the infinity end to the null end. As a result, the response bandwidth is broadened. Note that such a mechanism has also been employed in the design of broadband linear polarization converters that operate in the reflective mode⁴².

Discussion

We emphasize that the presented design framework for the perfect linear polarization converter bears a close resemblance to that of the perfect channel drop filter discovered previously in photonic crystal systems⁴³. In essence, these two types of devices, although are functionally different, however, if viewing from a fundamental perspective, are both four-port systems, where the four ports refer to the input and output ports with x and y polarized states for the case of linear polarization converter, and to the input and output ports of the photonic crystal waveguides located at the upper and lower sides of the photonic crystal defects for the case of channel drop filter. Previous study on the photonic crystal drop filter has shown that if the involved photonic crystal defect has two degenerate resonances with odd and even symmetries, light then can perfectly tunnel from the lower side input port to the upper side output port. Taking an analogy between these two different physical systems, perfect linear polarization converter thus can be realized if the considered device possesses two perfect electric and magnetic conducting surfaces, which are in correspondence to the odd and even resonance modes of the photonic crystal defects. The above arguments illustrate that the proposed design framework for the perfect linear polarization converter is essentially a different functional application of the fundamental principle of the four-port system with appropriately arranged symmetries. It has features of being both generally applicable and physically intuitive.

Although our theoretical analysis based on Fig. 1 has predicted that a perfect linear polarization conversion is possible, however, both the numerical and the experimental investigations have shown that the conversion efficiencies are less than 100% due to the unavoidable absorptive loss and the imperfect realization of the designed devices. It should be noted that the loss related drawback, which has been encountered in many realistic design cases^{4,13,27,30}, might be mitigated with the help of gain medium⁴⁴ or superconducting material⁴⁵ at the cost of increased device complexities. Another more practical route to relieve the problem has been proposed recently. It is shown that by increasing the effective inductance to capacitance ratio, i.e. L/C , the absorptive loss can be reduced substantially⁴⁶. Note that by following this method, the reduction of the conversion loss for design case I has been confirmed numerically.

In conclusion, we have presented a framework for the design of perfect linear polarization converters. It is found that in order to achieve a 100% linear polarization conversion efficiency, the device under consideration should possess two degenerate and complementary resonances, with one being electric and the other being magnetic. We use two different design examples operating near 10 GHz to validate the proposed design framework. The obtained results show that a narrow band and a broadband linear polarization converter can be realized by following the proposed design framework, which has features of being both generally applicable and physically intuitive.

Methods

The numerical simulations were carried out by using the frequency domain solver of a commercially available software, i.e. CST microwave studio. In our simulations, the copper structures were treated as lossy metal while the F4BK substrate was treated as normal.

The experimental measurements were performed in an anechoic chamber. A pair of linearly polarized broadband horn antennas were placed in front of and behind a transmission window of a microwave absorbing screen, acting as the transmitter and receiver of the measurement system. Fabricated device samples were mounted on the transmission window of the microwave absorbing screen. A vector network analyzer (Agilent N5244) was utilized to measure the polarization related transmittances of the fabricated devices, with the free space case served as the normalization reference. Because the transmitting and receiving antennas are not impedance matched to the free space, residue reflections occur at their coupling planes. The residue reflections from the antennas and also from the samples form a Fabry-Perot like effect and manifest themselves as ripples in the measured transmittance curves. Note that the frequency of the measured ripple is in good agreement with that estimated from the separations between the antennas and the samples.

References

1. Hecht, E. *Optics* (Pearson Education, 2002).
2. Sun, S. *et al.* Gradient-index meta-surfaces as a bridge linking propagating waves and surface waves. *Nat. Mater.* **11**, 426–431 (2012).

3. Jung, H., In, C., Choi, H. & Lee, H. Anisotropy modeling of terahertz metamaterials: polarization dependent resonance manipulation by meta-atom cluster. *Sci. Rep.* **4**, 5217 (2014).
4. Pfeiffer, C., Zhang, C., Ray, V., Guo, L. J. & Grbic, A. High performance bianisotropic metasurfaces: asymmetric transmission of light. *Phys. Rev. Lett.* **113**, 023902 (2014).
5. Koenderink, A. F., Alù, A. & Polman, A. Nanophotonics: shrinking light-based technology. *Science* **348**, 516–521 (2015).
6. Li, Z., Liu, W., Cheng, H., Chen, S. & Tian, J. Realizing broadband and invertible linear-to-circular polarization converter with ultrathin single-layer metasurface. *Sci. Rep.* **5**, 18106 (2015).
7. Mueller, J. P. B., Leosson, K. & Capasso, F. Ultracompact metasurface in-line polarimeter. *Optica* **3**, 42 (2016).
8. Khorasaninejad, M. *et al.* Metalenses at visible wavelengths: diffraction-limited focusing and subwavelength resolution imaging. *Science* **352**, 1190–1194 (2016).
9. Klimov, V. V. *et al.* Manipulation of polarization and spatial properties of light beams with chiral metafilms. *Opt. Express* **24**, 6172–6185 (2016).
10. Verre, R. *et al.* Polarization conversion-based molecular sensing using anisotropic plasmonic metasurfaces. *Nanoscale* **8**, 10576–10581 (2016).
11. Wen, D., Yue, F., Ardron, M. & Chen, X. Multifunctional metasurface lens for imaging and Fourier transform. *Sci. Rep.* **6**, 27628 (2016).
12. Ye, Y. & He, S. 90° polarization rotator using a bilayered chiral metamaterial with giant optical activity. *Appl. Phys. Lett.* **96**, 203501 (2010).
13. Chiang, Y. J. & Yen, T. J. A composite-metamaterial-based terahertz-wave polarization rotator with an ultrathin thickness, an excellent conversion ratio, and enhanced transmission. *Appl. Phys. Lett.* **102**, 011129 (2013).
14. Grady, N. K. *et al.* Terahertz metamaterials for linear polarization conversion and anomalous refraction. *Science* **340**, 1304–1307 (2013).
15. Cong, L. *et al.* Highly flexible broadband terahertz metamaterial quarter-wave plate. *Laser Photonics Rev.* **8**, 626–632 (2014).
16. Pfeiffer, C. & Grbic, A. Bianisotropic metasurfaces for optimal polarization control: analysis and synthesis. *Phys. Rev. Appl.* **2**, 044011 (2014).
17. Wang, D. *et al.* An ultrathin terahertz quarter-wave plate using planar babinet-inverted metasurface. *Opt. Express* **23**, 11114–11122 (2015).
18. Shi, J. H. *et al.* Dual-polarity metamaterial circular polarizer based on giant extrinsic chirality. *Sci. Rep.* **5**, 16666 (2015).
19. Wang, D. *et al.* Switchable ultrathin quarter-wave plate in terahertz using active phase-change metasurface. *Sci. Rep.* **5**, 15020 (2015).
20. Xu, H. X. *et al.* Dynamical control on helicity of electromagnetic waves by tunable metasurfaces. *Sci. Rep.* **6**, 27503 (2016).
21. Zárate, Y. *et al.* Elastic metamaterials for tuning circular polarization of electromagnetic waves. *Sci. Rep.* **6**, 28273 (2016).
22. Zhao, J. *et al.* A Wide-angle multi-octave broadband waveplate based on field transformation approach. *Sci. Rep.* **5**, 17532 (2015).
23. Aieta, F. *et al.* Aberration-free ultrathin flat lenses and axicons at telecom wavelengths based on plasmonic metasurfaces. *Nano Lett.* **12**, 4932–4936 (2012).
24. Farmahini-Farahani, M. & Mosallaei, H. Birefringent reflectarray metasurface for beam engineering in infrared. *Opt. Lett.* **38**, 462–464 (2013).
25. Li, Y. *et al.* Wideband radar cross section reduction using two-dimensional phase gradient metasurfaces. *Appl. Phys. Lett.* **104**, 221110 (2014).
26. Luo, J., Yu, H., Song, M. & Zhang, Z. Highly efficient wavefront manipulation in terahertz based on plasmonic gradient metasurfaces. *Opt. Lett.* **39**, 2229–2231 (2014).
27. Pfeiffer, C. *et al.* Efficient light bending with isotropic metamaterial Huygens' surfaces. *Nano Lett.* **14**, 2491–2497 (2014).
28. Cao, T., Wei, C. & Mao, L. Numerical study of achiral phase-change metamaterials for ultrafast tuning of giant circular conversion dichroism. *Sci. Rep.* **5**, 14666 (2015).
29. Kim, T. T. *et al.* Optical activity enhanced by strong inter-molecular coupling in planar chiral metamaterials. *Sci. Rep.* **4**, 5864 (2014).
30. Pors, A., Nielsen, M. G. & Bozhevolnyi, S. I. Analog computing using reflective plasmonic metasurfaces. *Nano Lett.* **15**, 791–797 (2015).
31. Mutlu, M. & Ozbay, E. A transparent 90° polarization rotator by combining chirality and electromagnetic wave tunneling. *Appl. Phys. Lett.* **100**, 051909 (2012).
32. Song, K. *et al.* 90° polarization rotator with rotation angle independent of substrate permittivity and incident angles using a composite chiral metamaterial. *Opt. Express* **21**, 7439–7446 (2013).
33. Shi, H., Zhang, A., Zheng, S., Li, J. & Jiang, Y. Dual-band polarization angle independent 90° polarization rotator using twisted electric-field-coupled resonators. *Appl. Phys. Lett.* **104**, 034102 (2014).
34. Cheng, Y. Z. *et al.* Ultrabroadband reflective polarization converter for terahertz waves. *Appl. Phys. Lett.* **105**, 181111 (2014).
35. Jiang, S. C. *et al.* Controlling the polarization state of light with a dispersion-free metastructure. *Phys. Rev. X* **4**, 021026 (2014).
36. Jiang, Z. H. *et al.* Broadband and wide field-of-view plasmonic metasurface-enabled waveplates. *Sci. Rep.* **4**, 7511 (2014).
37. Guo, Y. *et al.* Dispersion management of anisotropic metamirror for super-octave bandwidth polarization conversion. *Sci. Rep.* **5**, 8434 (2015).
38. Lévesque, Q. *et al.* Plasmonic planar antenna for wideband and efficient linear polarization conversion. *Appl. Phys. Lett.* **104**, 111105 (2014).
39. Cong, L. *et al.* A perfect metamaterial polarization rotator. *Appl. Phys. Lett.* **103**, 171107 (2013).
40. Fan, R. H. *et al.* Freely tunable broadband polarization rotator for terahertz waves. *Adv. Mater.* **27**, 1201–1206 (2015).
41. Fan, K., Strikwerda, A. C., Tao, H., Zhang, X. & Averitt, R. D. Stand-up magnetic metamaterials at terahertz frequencies. *Opt. Express* **19**, 12619–12627 (2011).
42. Pu, M. *et al.* Anisotropic meta-mirror for achromatic electromagnetic polarization manipulation. *Appl. Phys. Lett.* **102**, 131906 (2013).
43. Fan, S., Villeneuve, P. R., Joannopoulos, J. D. & Haus, H. A. Channel drop filters in photonic crystals. *Opt. Express* **3**, 4–11 (1998).
44. Wuestner, S., Pusch, A., Tsakmakidis, K. L., Hamm, J. M. & Hess, O. Overcoming losses with gain in a negative refractive index metamaterial. *Phys. Rev. Lett.* **105**, 127401 (2010).
45. Wu, J. *et al.* Superconducting terahertz metamaterials mimicking electromagnetically induced transparency. *Appl. Phys. Lett.* **99**, 161113 (2011).
46. Zhou, J., Koschny, T. & Soukoulis, C. M. An efficient way to reduce losses of left-handed metamaterials. *Opt. Express* **16**, 11147–11152 (2008).

Acknowledgements

This work was supported by the MOST 973 program (Grant No. 2014CB339800), the National Instrumentation Program (Grant No. 2012YQ14005), the National Natural Science Foundation (Grant Nos 61571105, 61671234, 61371035, 11173015, 11227904, 61521001, 61501219, 61071009, and 61322508), and the Priority Academic Program Development of Jiangsu Higher Education Institutions. B.B. Jin and J. Chen also acknowledge support from the Cooperative Innovation Centre of Terahertz Science, University of Electronic Science and Technology, Chengdu, China.

Author Contributions

G.C.Z., X.D.T. and Z.S. performed the numerical simulations and the experimental measurements. G.C.Z. and G.H.Z. carried out the theoretical analysis. G.H.Z. and B.B.J. conceived the design concept. L.K., W.W.X. and J.C. provided helpful discussions. G.C.Z., G.H.Z. and B.B.J. wrote the manuscript. P.H.W. supervised the research.

Additional Information

Competing financial interests: The authors declare no competing financial interests.

How to cite this article: Zhou, G. *et al.* Designing perfect linear polarization converters using perfect electric and magnetic conducting surfaces. *Sci. Rep.* **6**, 38925; doi: 10.1038/srep38925 (2016).

Publisher's note: Springer Nature remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.



This work is licensed under a Creative Commons Attribution 4.0 International License. The images or other third party material in this article are included in the article's Creative Commons license, unless indicated otherwise in the credit line; if the material is not included under the Creative Commons license, users will need to obtain permission from the license holder to reproduce the material. To view a copy of this license, visit <http://creativecommons.org/licenses/by/4.0/>

© The Author(s) 2016