

OPEN

First flush of non-point source pollution and hydrological effects of LID in a Guangzhou community

Jiajun Zeng¹, Guoru Huang^{1,2,3}, Haiwan Luo¹, Yepeng Mai¹ & Haichun Wu¹

To study the first flush effect of nonpoint source pollution in the Guangzhou community unit, runoff from roads, roofs, and green spaces during three rainfall events was collected and analyzed for pollutants. Nine runoff pollution indices were considered. The dimensionless cumulative curve of pollutant mass vs. volume, the first flush coefficient (b) and the mass first flush ratio (MFF_n) were used to assess the first flush effect of different underlying surfaces. The assessment results pointed out that the roof was most prone to first flush effect. And ammonia nitrogen and phosphorus were the main pollutants in the first flush in the study area. For a quantitative analysis of the first flush, the Storm Water Management Model (SWMM) was used to simulate the hydrological effect of low impact development (LID) implementation in the community. The results showed that the first flush strength was reduced after setting LID. And LID measures, such as green roofs and sunken green spaces, contribute to flood control and rainwater purification. This research can be relevant regarding for constructing sponge cities and reducing the pollution caused by the first flush.

Urban nonpoint source pollution refers to pollutants that flow into rivers and lakes via the runoff formed by rainfall, which then pollute the receiving water in the city. The sponge city, with good resilience in adapting to environmental changes and responding to natural disasters caused by rainwater, is becoming more and more popular in China. The concept of sponge city was proposed in “Sponge City Construction Technology Guide”¹ to alleviate urban water environmental problems in modern cities such as urban waterlogging, rainwater runoff pollution and water shortage. As sponge city construction in China spreads, investigation of the first flush via rainfall runoff is an important basis for the study of characteristics control of urban nonpoint source pollution. The first flush is the phenomenon that a greater fraction of contaminant is washed out during the initial stage of a rainfall event^{2–4}. It is mainly caused by the quick wash off of pollutants accumulated on the watershed surfaces⁵. One of the purposes of sponge city construction is to reduce initial rainwater pollution. The research on first flush effect is an important part of sponge city construction. Bach *et al.*⁶ demonstrated an assessment method to detect the presence and characteristics of the first flush effect. The installation of a device to divert the first flush water away from the collection system may improve the quality of the harvested water⁷. Xiaoping *et al.*⁸ assessed the differences in first flush water quality by designing a rainfall harvesting system to monitor rainwater drained from roofs. Many factors affect the occurrence and intensity of the first flush. Park *et al.*⁹ estimated the probability of the mass first flush ratio (MFF_n) by using the Storm Water Management Model (SWMM) to analyze the characteristics of the first flush.

In all of these studies, the emphasis is on the analysis of the first flush characteristics without quantitative analysis on the first flush effect. And first flush effect of different underlying surfaces is rarely studied. Then in this research, the first flush of different underlying surfaces is discussed, and quantitative analysis is proposed. Moreover, some measures are proposed to mitigate the degree of contamination. To compare the difference in these methods, three kinds of methods were adopted to evaluate the first flush effect in the present study: The dimensionless cumulative curve called $M(V)$ curve, mass first flush ratio (MFF_n) and the first flush coefficient (b). The $M(V)$ curve is a qualitative method to evaluate the pollutants load distribution in storm runoff while MFF_n is used to quantitatively analyze the amount of pollutant load in runoff. And the value b can be used to analyze

¹South China University of Technology, School of Civil Engineering and Transportation, Guangdong, Guangzhou, 510640, China. ²South China University of Technology, State Key Laboratory of Subtropical Building Science, Guangdong, Guangzhou, 510640, China. ³Guangdong Engineering Technology Research Center of Safety and Greenization for Water Conservancy Project, Guangzhou, 510640, Guangdong, China. Correspondence and requests for materials should be addressed to G.H. (email: huanggr@scut.edu.cn)

Received: 6 March 2019

Accepted: 12 September 2019

Published online: 25 September 2019




Figure 1. Study area location

Date	T_r [min]	W [mm]	I_a [mm·h ⁻¹]	I_{max} [mm·h ⁻¹]
Sep 2 nd	37	6.3	8.1	24
Sep 7 th	90	10.1	3.4	18
Sep 10 th	66	8.1	1.0	13

Table 1. Rainfall characteristics of the three rainfall events.

the first flush strength. Comprehensive analysis of the results using the different methods can be propitious to quantitative analysis of the first flush in the study area and helpful for putting forward a strategy of pollution reduction. Low impact development (LID) system layout may affect the hydrological characteristics significantly, thus further study via SWMM on the efficiency of runoff and pollutant control is still needed¹⁰. LID system significantly reduced storm-water runoff and runoff quality. In the process of sponge city construction in Guangzhou, the principles and applications of LID have the potential to mitigate urban nonpoint source pollution and the impact of imperviousness in urban areas¹¹. Efforts to investigate the effectiveness of LID practices have largely been directed toward microscale evaluation of green roofs, green spaces, permeable pavement, and other LID practices¹². The reductions in runoff volume and pollutant loads after implementing LID practices have been simulated. The simulation results were compared with the observed impacts and showed the reductions in runoff volume and pollutant loads¹³. Therefore, the simulation results are capable of assisting decision-makers in evaluating the environmental impacts of LID.

In the present study, the authors characterized the first flush effect on roads, roofs, and green spaces in the community of Guangzhou. Different pollutants indices were tested to investigate the influencing factors on the first flush effect. The characteristics of first flush effect in Guangzhou is explored. Pollution caused by first flush is part of urban non-point source pollution. Attention should be paid to the pollution caused by first flush and quantitative analysis of the first flush in Guangzhou according to a comprehensive analysis of different methods. LID design plan is proposed to reduce the first flush pollution. A model of the community unit in Guangzhou was built using the SWMM to analyze the effect of LID. Based on the characteristics of the first flush and the simulation results from the SWMM, suggestions for construction of the sponge city are proposed. The research results provide an important scientific basis for reducing the level of pollutants in the first flush.

The study area is a community located in Guangzhou, China (Fig. 1). It is a housing estate that is an independent closed drainage system, was built in 2013, and covers 432 thousand square meters. The land use of the area is mainly composed of roads, public squares, residential areas, and green spaces.

Three typical underlying surfaces, i.e., roads, roofs, and green spaces, were selected for sampling. When a rainfall event occurred, rainfall runoff samples were collected manually every 10 minutes at different sampling sites and recording each sampling time. Three different bottles were filled at each sampling site. The samples were used to analyze different types of underlying stormwater runoff pollutant types five-day biochemical oxygen demand (BOD_5), chemical oxygen demand (COD_{Cr}), total suspended solids (TSS), ammonia nitrogen (NH_3-N), total nitrogen (TN), and total phosphorus (TP). As the properties of COD_{Cr} , NH_3-N , TN, and TP will change over time and the sampling sites are far from the laboratory, concentrated sulfuric acid was added to the samples immediately after collection to avoid changes in these indicators. The A and B bottles were used for the determination of BOD_5 and TSS, respectively, and the C bottles were used for determining the COD_{Cr} , NH_3-N , TN, and TP, thus concentrated sulfuric acid was added into the C bottles.

In this study, the authors collected samples during three rainfall events on September 2, 7, and 10 in 2016. The rainfall characteristics of rainfall duration (T_r), rainfall (W), average rainfall intensity (I_a), and maximum rainfall intensity (I_{max}) for the three events are shown in Table 1. There's no rain a week before September 2th and no other rain between the three rainfall events.

Test items	Test methods
BOD ₅	Dilution and inoculation HJ 505-2009
COD _{cr}	Dichromate method GB/T 11914-1989
TSS	Gravimetric method GB/T 11901-1989
NH ₃ -N	Sodium Reagent Spectrophotometry HJ 535-2009
TN	Alkaline potassium persulfate digestion UV Spectrophotometry HJ 636-2012
TP	Ammonium molybdate spectrophotometric method GB/T 11893-1989

Table 2. Test methods of each index.

Water quality index	BOD ₅	COD _{cr}	TSS	NH ₃ -N	TN	TP
C_{max} (mg/L)	84.20	393.00	132.00	2.27	3.96	0.26
C_{med} (mg/L)	3.75	16.50	8.50	0.62	2.46	0.05
C_{min} (mg/L)	1.40	5.00	1.00	0.11	1.35	0.02
\bar{C} (mg/L)	7.80	33.80	19.80	0.75	2.43	0.08
σ	13.40	63.20	30.10	0.56	0.68	0.06
C_v	1.72	1.87	1.52	0.74	0.28	0.73

Table 3. Summary statistics (N = 52) for the water quality indicators.

Samples (N = 52) were tested according to the methods listed in Table 2. The maximum concentration C_{max} , the median concentration C_{med} , the minimum concentration C_{min} , the average concentration \bar{C} , the standard deviation σ , and the coefficient of variation C_v of each pollution indicator in the samples are shown in Table 3. Statistics from the test results indicate that the greatest variation occurred for BOD₅, COD, and TSS, and the least variation occurred for TN.

Results

First flush analysis. The M(V) curves for pollutant indices were drawn based on the measured rainfall data and pollutant concentration data, as shown in Fig. 2. The M(V) curves were plotted to represent the normalized cumulated runoff volume for each storm event and each water quality index¹⁴. If the curve is close to the diagonal line, it indicates that the pollutant concentration changed little during the early stage of runoff or that the load distribution is comparatively uniform¹⁵.

As illustrated in Fig. 2, the M(V) curves of the pollutant indices all fluctuated in different degrees. Among them, the upward convex part of the curve of BOD₅, NH₃-N and TP is more obvious and that indicated that the first flush effect of these pollutant indices is more significant. The curves of TN are the closest to the diagonal line and the curves of TSS are concave, so the first flush effect of TN and TSS is weak. On the other hand, during the first rainfall (Sep/02/2016), the curves of pollutants indices such as BOD₅, COD_{cr}, TSS, TN, and TP showed that the first flush occurred on the roads. Whereas during the third rainfall (Sep/10/2016), the first flush effect was not obvious for the roads and roofs. The curves for the pollution on the road demonstrate large variability in the strength of the first flush effect. In addition, the M(V) curves of the multiple pollution indices showed the first flush effect of the roof occurred and the strength of first flush for roof is stronger than road and green space. From the above, the first flush effect is most pronounced on the roof and the strength of first flush is most uncertain on road. The main pollutions in first flush are BOD₅, NH₃-N and TP.

Using Eq. (3), the MFF₂₀ and MFF₃₀ of each pollutant index were calculated and the results are summarized as boxplots in Fig. 3. Figure 3 indicates that for all the contaminants the mean values were near 1.0. Variances for BOD₅ and COD were about three times the variances for NH₃-N and TN. The average of the MFF₂₀ values are all greater than 1.0, whereas the average of the MFF₃₀ values of TSS and COD_{cr} are less than 1.0. From the general trend, the MFF₂₀ values of different pollutants indices are greater than the MFF₃₀ values. The greater the value of MFF_n the more obvious the first flush effect is. And the MFF₂₀ values is average of fourteen points higher than MFF₃₀. According to the definition of MFF_n, the first flush effect is more likely to occur during the first 20% runoff than the first 30% runoff for the community unit in Guangzhou. According to the MFF₂₀ calculation results, 100% of the TN indices; 42.9% of the BOD₅, COD_{cr}, and TSS indices; and 57.1% of the NH₃-N and TP indices occurred first flush effect.

Based on Eq. (4), the water quality data were fitted using power function regression and the first flush coefficient (b) was calculated. The fitting correlation coefficients were all greater than 0.93, which indicated that the fitting effect was good and the results were suitable for first flush analysis. Figure 4 shows a comparison of pollutant indices on different underlying surfaces and a comparison of first flush effect for different pollutant indices. According to the definition of the value b , when $b < 1.0$, the first flush occurred, and the smaller the b value, the greater the first flush intensity. Figure 4 shows that 59.5% of the b values are less than 1.0. The change ranges of b values for NH₃-N, TN and TP are smaller than the other indices. The intensity of first flush for NH₃-N and TP are greater because the b values are smaller. It indicates that ammonia nitrogen and phosphorus are the main pollutants in the first flush effect of the community unit in Guangzhou. In addition, b values for the roof indicate




Figure 2. M (V) curves of different pollutions

the first flush effect is the most pronounced and b values for the road indicate the first flush strength is uncertain. The first flush strength of the green space is weakest. There consist with the result of M(V) curve.

Different methods were used to determine whether the first flush occurred. The results obtained from different methods were generally the same, but not completely consistent. The difference in results illustrates the complexity and uncertainty of the influence factors of the first flush effect.

In order to analyze the influence factors of the first flush effect, pollutants are analyzed in different rainfall events. MF_{20} and first flush coefficient (b) were calculated to compare the first flush effect during each rainfall event and some similar results can be found in Fig. 5 (I) and (II). Figure 5 (I) shows that the first flush effect occurred on a majority of the roads and roofs during the first rainfall (Sep 2nd) of which the intensity is the maximum of the three rainfall events. The number of first flushes occurring is less for the second rainfall (Sep 7th) whereas the intensity is weaker than the first rainfall event. Figure 5 (II) shows that the intensity of the first flush effect is the greatest during the first rainfall which indicated that the intensity of rainfall is an influence factor of the first flush. Besides, the first flush effects for roofs are more intensity than that for roads. In addition, the intensity and the occurrence frequency of the first flush of the green spaces during the second rainfall (Sep 7th) are




Figure 3. MFF₂₀ and MFF₃₀ of the different pollutants indices (The base of box denotes the first quartile (25%), the line in the central part of the box indicates the median (50%), and the roof marks the third quartile (75%). The mark in the middle of the box indicates the average. The upper and lower ends of the whiskers denote the Maximum and minimum values.)




Figure 4. The calculation results of *b* values




Figure 5. (I) MFF₂₀ for the different underlying surfaces. (II) The *b* values for the different rainfall events.

more than during the third rainfall (Sep 10th). This supported the previous conclusion that green spaces function as pollutant interceptors.

Hydrological effect analysis. There is great uncertainty about the first flush of roads according to the above analysis of the first flush. This may be because the sanitation department is washing the streets daily. Thus, the measures to cut pollution should be concentrated on the roofs and green spaces. The functions of the LID mainly are infiltration, stagnation, storage, purification, usage, and drainage, which can reduce the total amount of runoff discharge and treat the rainwater¹⁶. Referring to the Sponge City Development Technical Guide compiled by the Ministry of House and Urban-Rural Development of the People’s Republic of China¹, 50% of the roofs and green spaces were selected for transformation based on the corresponding LID measures. In other words, 50% of the roofs were




Figure 6. MFF_{20} during different rainfall recurrence period.

Recurrence period (a)	Water quantity	BOD_5	COD_{Cr}	TSS	NH_3-N	TN	TP
P = 0.5	46	38	33	33	37	40	50
P = 1	45	35	32	29	35	37	50
P = 2	44	30	29	23	32	34	49
P = 5	43	23	24	15	29	28	48

Table 4. Water quantity and pollutants reduction (%) effect of LID measure.

transformed into green roofs and 50% of the green spaces were transformed into sunken green spaces. Rainwater on the roads and roofs will flow into the sunken green spaces and then flow to the water outlets.

According to the flow process of drainage outlets in the simulation results, the MFF_n of different pollutants can be calculated. As the first flush effect is more prone to occur during the first 20% of runoff in the above research, the MFF_{20} values were calculated. The situation after the implementation of the LID measures is compared with the original situation in Fig. 6.

The results of the comparison show that the MFF_{20} values of the pollutant indices, decreased after the implementation of the LID measures. In other words, pollutants were reduced in the first 20% of the rainwater runoff. The reduction effect in different rainfall return periods is similar. LID measures such as green roofs and sunken green spaces have an interception effect on pollutants. The decline in MFF_{20} of TP is not obvious after the implementation of the LID measures, whereas, for the whole runoff process, the reduction in TP reached 48%. In general, green roofs and sunken green spaces can lower the degree of pollution caused by the first flush.

Discussion

The phenomenon of first flush is influenced by many factors. The first flush effects on different underlying surfaces are varied. The first flush strength of the roof and road is stronger than that of the green space. This conclusion is similar previous studies which concluded that the strength of first flush is stronger in the impervious areas¹⁷. The first flush occurs on the road showing uncertainty, probably because of the reduction of pollutants accumulation after street cleaning. Nitrogen and phosphorus are mainly pollutants in the first flush. The results of nonpoint source pollution studies in adjacent areas¹⁸ show that nitrogen and phosphorus pollutant load in first flush accounted for more than 50%. However, the factors affecting the first flush effect are various and the first flush strength varies greatly in different regions.

Table 4. shows the analysis results of water quantity and pollutant reduction. The reduction effect on water and pollutants decreases with the increase in rainfall recurrence period. The effect of LID measures is more significant for the low recurrence period rainfall. The reduction effect is positively related to the water storage capacity of LID measures. Because the water storage capacity of LID measures is limited, reduction effect decreased with greater rainfall. The results correctly reflected the objective law that the larger the rainfall, the smaller the reduction rate. According to the results, the reductions in water quantity are more than 43%, which indicated the LID measures had good water storage capacity and a positive effect on flood control. In addition, the LID measures can reduce pollutants in runoff. The reductions of TP are more than 48%, which is the most significant reduction effect among the pollutants. The results from the SWMM simulation show that LID measures contribute to flood control, treat rainwater, and reduce the level of pollutants in the first flush.

Some suggestions can be made for sponge city construction according to the study results. Firstly, rainwater from roofs and roads can be drawn into the green spaces and purification measures can be installed in the green spaces. Green spaces can reduce the direct discharge of polluted water into receiving waters. Secondly, treatment measures for nitrogen and phosphorus pollutants should be considered during sponge city construction. In future studies, the reduction of pollutants will be the focus and more collection of samples during more rainfall events will be the next step.

Methods

First flush effect. Early understanding of the first flush effect regarded as the concentration of pollution during initial rainfall. The view was that the concentration of pollutants in early rainfall runoff is higher than that in later stages of runoff. However, the influence of rainfall intensity and runoff cannot be neglected. On one hand, the greater the rainfall intensity, the greater the impact intensity on the surface and the more likely that pollutants are transferred from the underlying surface to the surface runoff¹⁹. On the other hand, on the premise of the same rainfall intensity and total amount of pollutants, when the runoff is large, the pollution concentration decreases. Because the definition of the first flush is controversial, the $M(V)$ curve, MFF_n , and first flush coefficient were used to analyze the first flush effect of the study area. The purpose is to conduct a comprehensive quantitative analysis of the first flush effect.

The $M(V)$ curve is commonly used for studying the first flush. The view is that when the accumulative transport rate of pollutants is larger than that of runoff accumulation in the early stage of rainfall, the first flush exists²⁰. In other words, a small proportion of total runoff transfers a large proportion of the pollution during a rainfall event. To compare the variation in pollutant loads during rainfall events, $M(V)$ curves can be obtained using Eq. (1) and Eq. (2):

$$M(t) = \int_0^t Q(t)C(t)dt / \int_0^T Q(t)C(t)dt \approx \sum_{i=0}^k \bar{Q}(t_i)\bar{C}(t_i)\Delta t / \sum_{i=0}^k \bar{Q}(t_i)\bar{C}(t_i)\Delta t \quad (1)$$

$$V(t) = \int_0^t Q(t)dt / \int_0^T Q(t)dt \approx \sum_{i=0}^k \bar{Q}(t_i)\Delta t / \sum_{i=0}^k \bar{Q}(t_i)\Delta t \quad (2)$$

where $M(t)$ is the ratio of cumulative runoff to total runoff during the rainfall at time t ; $V(t)$ is the ratio of cumulative pollutant load to total pollutant load during the rainfall at time t ; $Q(t)$ is the instantaneous flux at time t , [L/min]; $C(t)$ is the instantaneous pollutant concentration at time t , [mg/L]; T indicates the time from which rainfall runoff begins and ends at the end of the runoff, [min]; Δt is the time increment of the calculation, [min]; $\bar{Q}(t_i)$ is the average runoff during Δt at time t_i , [L/min]; and $\bar{C}(t_i)$ is the average value of the pollutant concentration during Δt at time t_i , [mg/(L·min)].

According to Code for Design of Outdoor Wastewater Engineering²¹, the fixed runoff coefficient method was used to calculate the runoff via the rainfall data. According to the code²¹, when the catchment areas are not exceeded 2 square kilometers, the runoff can be calculated by inference formula. Then, the average runoff can be calculated using Eq. (3) that the Code recommends:

$$\bar{Q}(t_i) = \bar{i}(t_i)\psi F \quad (3)$$

where $\bar{i}(t_i)$ is the average rainfall intensity during Δt at time t_i , [mm/min]; ψ is the runoff coefficient, and F is the catchment area, [hm²].

Taking the ratio of cumulative runoff to total runoff as the abscissa and the ratio of pollutant cumulative load to total pollutant load as the ordinate, the dimensionless $M(V)$ curve was plotted. The 45° angle bisector of the coordinate system was used as a standard indicator of the occurrence of the first flush effect. When the $M(V)$ curve lies above the 45° angle bisector, the first flush occurs. On the contrary, if the $M(V)$ curve lies below the 45° angle bisector, the first flush does not occur.

On the basis of $M(V)$ curve, for qualitatively describing the first flush effect, Saget *et al.*²² defined that when at least 80% of the pollutant mass is transported in the first 30% of the runoff volume, the first flush exists. Based on the dimensionless cumulative $M(V)$ curve, Ma *et al.*²³ suggested the MFF ratio, which can be used for quantitative analysis of the first flush effect. The MFF_n is the ratio of the percentage of cumulative pollution load to percentage of cumulative runoff when the cumulative transport runoff accounts for $n\%$ of the total runoff. The calculation formula is shown as Eq. (4):

$$MFF_n = \frac{\int_0^t Q(t)C(t)dt/M}{\int_0^t Q(t)dt/V} \approx \frac{\sum_{i=0}^k \bar{Q}(t_i)\bar{C}(t_i)\Delta t/M}{\sum_{i=0}^k \bar{Q}(t_i)\Delta t/V} \quad (4)$$

where n is the percentage of cumulative runoff to total runoff from the time of runoff generation to time t , ranging from 0 to 100%. M is the total amount of pollution load during the whole rainfall process, [mg]; and V is the total amount of runoff discharged during the whole rainfall process, [L]. The MFF ratio is a method derived from the $M(V)$ curve. According to the previously mentioned about the definition of MFF , 80% of the pollutant mass is transported in the first 30% of the runoff, which means $MFF_{30} = 2.67$. When the $M(V)$ curve lies above the 45° angle bisector, $MFF_n > 1.0$.

This method describes the occurrence conditions of the first flush effect. To analyze the first flush intensity quantitatively, Bertrand-Krajewski *et al.*²⁴ demonstrated that there is a power function relationship between the cumulative pollution load percentage and the cumulative runoff percentage, as follows:

$$G = L^b \quad (5)$$

where G is the proportion of cumulative pollution load and values range from 0 to 1, and L is the proportion of cumulative runoff. When $L = 0$, $G = 0$ and when $L = 1$, $G = 1$. The value b is the first flush coefficient, which reflects the intensity of the first flush according to the deviation between curve and diagonal. When the $M(V)$

Parameter	Physical meaning	The recommended parameter range ²⁶	The parameter of this model
N-Imperv	Manning coefficient of impervious area	0.010–0.015	0.015
N-Perv	Manning coefficient of permeable area	0.012–0.8	0.032
Destore-Imperv	Depth of water storage in impervious area (mm)	0.1–2	1
Destore-Perv	Depth of water storage in permeable area (mm)	2–15	10
% Zero-Imperv	Proportion of no depressions and impervious zones in impervious area	25–100	50
MaxRate	Maximum infiltration rate (mm·h ⁻¹)	45–120	103.81
MinRate	Minimum infiltration rate (mm·h ⁻¹)	0–25	11.44
Decay	Osmotic attenuation coefficient	2–7	2.75

Table 5. Water quantity parameters of the model.

Underlying surface types	Parameter	BOD ₅	COD _{Cr}	TSS	NH ₃ -N	TN	TP
Road	Maximum accumulation / (kg·hm ⁻²)	80	300	100	2	5	1
	Accumulation time of semi saturation /d	3~5	3~5	3~5	3~5	3~5	3~5
	Flushing coefficient	0.005	0.007	0.03	0.015	0.02	0.0045
	Flush index	1.8	1.5	1.2	1.8	1.6	1.1
Roof	Maximum accumulation / (kg·hm ⁻²)	10	8	10	2	7.5	0.3
	Accumulation time of semi saturation /d	3~7	3~7	3~7	3~7	3~7	3~7
	Flushing coefficient	0.0032	0.03	0.014	0.014	0.006	0.0022
	Flush index	1.4	1.2	1.2	1.8	1.2	1.05
Green space	Maximum accumulation / (kg·hm ⁻²)	20	40	80	4	8	2
	Accumulation time of semi saturation /d	3~20	3~20	3~20	3~20	3~20	3~20
	Flushing coefficient	0.006	0.03	0.024	0.008	0.011	0.0009
	Flush index	1.8	1.5	1.6	1.25	1.42	1.6

Table 6. Water quality parameters of the SWMM model.

curve lies above the 45° angle bisector, the value of b is less than 1.0; the smaller the b value, the greater the first flush intensity. A dilution effect was defined for when b is greater than 1.0²⁵.

Storm water management model. The SWMM is a widely used stormwater simulation model that was developed for the Environmental Protection Agency²⁶. The model can be used for a single event or long-term simulation of runoff quantity and quality from urban areas. LID measures have been implemented in SWMM to simulate the hydrologic performance. And sunken green spaces, green roofs, and permeable pavement have been chosen in this research. LID measures can be assigned within the selected subcatchments and defined the corresponding areal coverage. Basing on permeation theory, Horton infiltration model has been used, and different parameters of structural layers were set correspond to different measures²⁷.

In the current research, the drainage system subcatchments of the study area were divided using the equal angle line method. Then, the Tyson polygon rule was used to subdivide the subcatchments based on the locations of manholes. Finally, the study area was divided into 132 subcatchment areas. The water quantity parameters of the model (Table 5) were determined by referring to the model's manual²⁶ and the relevant research on the same study regions²⁸. The runoff from 20 rainfall events were monitored and Zhu *et al.*²⁸ used the Nash–Sutcliffe efficiency (NSE) index and Kling–Gupta efficiency (KGE) to evaluated the model and suggested that the parameter values were reasonable because the KGE and NSE between the observed runoff timeseries and the simulated data were up to 0.7. Simulated values can be regarded as satisfactory when NSE > 0.5. And simulated values could be regarded as satisfactory with a KGE value as low as 0.6.

The water quality parameters were calibrated using the rainfall event of September 10. Then, the observed data of the September 2 and 7 rainfall events were used to assess the model. Method of trial and error was used and the parameters were adjusted by one-at-a-time method. The correlation coefficient between the simulation results and the observed data was used to characterize the trends of concentration change for pollutants. The water quality model parameters were adjusted until the correlation coefficient is greater than 0.5 and simulated values could be regarded as satisfactory. The final determined water quality parameters are shown in Table 6.

The simulation of the transformation plan was completed in the SWMM, and the effect of LID measures under various rainfall recurrence periods was analyzed. The rainstorm intensity in each recurrence period was calculated by using the rainstorm intensity formula of Guangzhou and the design rainfall hydrograph using the Chicago rainfall pattern which is determined according to a rainfall pattern using the Chicago Hydrograph Model²⁹. The water quality parameters of the model were calibrated and assessed using the sample data of the three rainfall events.

References

1. MOHURD (Ministry of Housing and Urban-Rural Development of the People's Republic of China). Sponge City Sponge City Construction Technology Guide. Beijing (in Chinese) (2014).
2. Xichao, G. *et al.* Temperature Dependence of Hourly, Daily, and Event-based Precipitation Extremes Over China. *Scientific Reports* **8**(1), 17564 (2018).
3. Sansalone, J. J. & Buchberger, S. G. Partitioning and First Flush of Metals in Urban Roadway Storm Water. *Journal of Environmental Engineering*. **123**(2), 134–143 (1997).
4. Sansalone, J. J. & Cristina, C. M. First Flush Concepts for Suspended and Dissolved Solids in Small Impervious Watersheds. *Journal of Environmental Engineering*. **130**(11), 1301–1314 (2004).
5. Sharifi, S., Massoudieh, A. & Kayhanian, M. A stochastic stormwater quality volume-sizing method with first flush emphasis. *Water Environment Research. A Research Publication of the Water Environment Federation* **83**(11), 2025–2035 (2011).
6. Bach, P. M., Mccarthy, D. T. & Deletic, A. Redefining the stormwater first flush phenomenon. *Water Research* **44**(8), 2487–2498 (2010).
7. Mendez, C. B. *et al.* The effect of roofing material on the quality of harvested rainwater. *Water Research* **45**(5), 2049–2059 (2011).
8. Xiaoping, W. & Fei, Z. Effects of land use/cover on surface water pollution based on remote sensing and 3d-eem fluorescence data in the Jinghe Oasis. *Scientific Reports* **8**(1), 13099 (2018).
9. Park, I., Kim, H., Chae, S.-K. & Ha, S. Probability mass first flush evaluation for combined sewer discharges. *Journal of Environmental Sciences* **22**(6), 915–922 (2010).
10. Xing, W. *et al.* Layout effects and optimization of runoff storage and filtration facilities based on SWMM simulation in a demonstration area. *Water Science and Engineering* **9**(2), 115–124 (2016).
11. Liu, Y. *et al.* Optimal selection and placement of bmps and lid practices with a rainfall-runoff model. *Environmental Modelling & Software* **80**, 281–296 (2016).
12. Ahiablame, L. M., Engel, B. A. & Chaubey, I. Effectiveness of low impact development practices in two urbanized watersheds: retrofitting with rain barrel/cistern and porous pavement. *Journal of Environmental Management* **119**(119C), 151–161 (2013).
13. Liu, Y., Ahiablame, L. M., Bralts, V. F. & Engel, B. A. Enhancing a rainfall-runoff model to assess the impacts of bmps and lid practices on storm runoff. *Journal of Environmental Management* **147**(147), 12–23 (2015).
14. Inhyeok, P., Hongmyeong, K., Soo-Kwon, C. & Sungryong, H. Probability mass first flush evaluation for combined sewer discharges. *Journal of Environmental Sciences* **22**(6), 915–922 (2010).
15. Li, S., Wang, X., Qiao, B., Li, J. & Tu, J. First flush characteristics of rainfall runoff from a paddy field in the taihu lake watershed, china. *Environmental Science & Pollution Research* **24**(9), 8336–8351 (2017).
16. Beecham, S. & Razzaghmanesh, M. Water quality and quantity investigation of green roofs in a dry climate. *Water Research* **70**(C), 370–384 (2015).
17. Li, L. Q., Yin, C. Q., He, Q. C. & Kong, L. L. First flush of storm runoff pollution from an urban catchment in China. *Journal of Environmental Sciences* **19**(3), 295–299 (2007).
18. Li, D. *et al.* Stormwater runoff pollutant loading distributions and their correlation with rainfall and catchment characteristics in a rapidly industrialized city. *PLoS one* **10**(3), e0118776 (2015).
19. Zhang, Q. *et al.* The temporal changes in road stormwater runoff quality and the implications to first flush control in Chongqing, China. *Environmental Monitoring & Assessment* **185**(12), 9763–9775 (2013).
20. Hathaway, J. M. & Hunt, W. F. Evaluation of first flush for indicator bacteria and total suspended solids in urban stormwater runoff. *Water Air & Soil Pollution* **217**(1–4), 135–147 (2011).
21. MOHURD (Ministry of Housing and Urban-Rural Development of the People's Republic of China). Code for Design of Outdoor Wastewater Engineering, GB50014-2006. Beijing (in Chinese) (2016).
22. Saget, A., Chebbo, G. & Bertrand-Krajewski, J. L. The First Flush in Sewer Systems. *Water Science & Technology*. **33**(9), 101–108 (1996).
23. Ma, Z. B., Ni, H. G., Zeng, H. & Wei, J. B. Function formula for first flush analysis in mixed watersheds: a comparison of power and polynomial methods. *Journal of Hydrology* **402**(3–4), 333–339 (2011).
24. Bertrand-Krajewski, J. L., Chebbo, G. & Saget, A. Distribution of pollutant mass vs volume in stormwater discharges and the first flush phenomenon. *Water Research* **32**(8), 2341–2356 (1998).
25. Yang, L. E., Scheffran, J., Süsler, D., Dawson, R. & Chen, Y. D. Assessment of flood losses with household responses: Agent-based simulation in an urban catchment area. *Environmental Modelling & Assessment* **23**, 369–388 (2018).
26. Rossman, L.A. Storm Water Management Model User's Manual, Version 5.0. National Risk Management Research Laboratory, Office of Research and Development, US Environmental Protection Agency, (2010).
27. Ahiablame, L. & Shakya, R. Modeling flood reduction effects of low impact development at a watershed scale. *Journal of Environmental Management* **171**, 81–91 (2016).
28. Zhu, Z., Chen, Z., Chen, X. & He, P. Approach for evaluating inundation risks in urban drainage systems. *Science of the Total Environment* **553**, 1–12 (2016).
29. Keifer, C. J. & Chu, H. H. Synthetic storm pattern for drainage design. *Journal of the Hydraulics Division*. **83**(4), 1–25 (1957).

Acknowledgements

This study was financially supported by the National Natural Science Foundation of China (51739011, 51741903), Science and Technology Program of Guangzhou, China (201707020020), Guangdong water resources scientific and technological innovation project (2016-32), and Innovation Fund Project of excellent master graduate students of South China University of Technology (2017SJ10).

Author Contributions

J.J.Z. and H.W.L. designed the project and wrote the paper. G.R.H. revised the project. Y.P.M. and H.C.W. collected and sample data and made statistic. All the authors commented on the manuscript.

Additional Information

Competing Interests: The authors declare no competing interests.

Publisher's note Springer Nature remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.



Open Access This article is licensed under a Creative Commons Attribution 4.0 International License, which permits use, sharing, adaptation, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons license, and indicate if changes were made. The images or other third party material in this article are included in the article's Creative Commons license, unless indicated otherwise in a credit line to the material. If material is not included in the article's Creative Commons license and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder. To view a copy of this license, visit <http://creativecommons.org/licenses/by/4.0/>.

© The Author(s) 2019