

Arginase II Downregulates Nitric Oxide (NO) Production and Prevents NO-mediated Apoptosis in Murine Macrophage-derived RAW 264.7 Cells

Tomomi Gotoh and Masataka Mori

Department of Molecular Genetics, Kumamoto University School of Medicine, Kumamoto 862-0976, Japan

Abstract. Excess nitric oxide (NO) induces apoptosis of some cell types, including macrophages. As NO is synthesized by NO synthase (NOS) from arginine, a common substrate of arginase, these two enzymes compete for arginine. There are two known isoforms of arginase, types I and II. Using murine macrophage-like RAW 264.7 cells, we asked if the induction of arginase II would downregulate NO production and hence prevent apoptosis. When cells were exposed to lipopolysaccharide (LPS) and interferon- γ (IFN- γ), the inducible form of NOS (iNOS) was induced, production of NO was elevated, and apoptosis followed. When dexamethasone and cAMP were further added, both iNOS and arginase II were induced, NO production

was much decreased, and apoptosis was prevented. When the cells were transfected with an arginase II expression plasmid and treated with LPS/IFN- γ , some cells were rescued from apoptosis. An arginase I expression plasmid was also effective. On the other hand, transfection with the arginase II plasmid did not prevent apoptosis when a NO donor SNAP or a high concentration (12 mM) of arginine was added. These results indicate that arginase II prevents NO-dependent apoptosis of RAW 264.7 cells by depleting intracellular arginine and by decreasing NO production.

Key words: arginase • NO • NO synthase • apoptosis • arginine

NITRIC oxide (NO)¹ is an important multifunctional biomolecule involved in a variety of physiological and pathological processes, including regulation of blood vessel dilatation and immune response, and functions as a neurotransmitter (Christopherson and Bredt, 1997; Harrison, 1997; Mayer and Hemmens, 1997; Nathan, 1997). In pathologic processes, NO functions as a bactericidal or tumoricidal agent; however, excess NO production is thought to be the cause of several diseases, such as septic shock (Stuehr and Marletta, 1985), autoimmune disease (Farrell et al., 1992), cerebral infarction (Dawson et al., 1996), and diabetes mellitus (Corbett and McDaniel, 1992). NO-mediated apoptosis is often observed in such cases (Kröncke et al., 1997). NO has several cytotoxic effects, including reactions with proteins and nucleic acids. The main targets of NO in proteins are the SH group (Molina y Vedia et al., 1992) and Fe of active sites (Hibbs et al., 1988),

especially Fe²⁺ (Kim et al., 1995) in heme. In the nucleus, NO has been shown to cause mutations of genes (Routledge et al., 1994; Juedes and Wogan, 1996), and inhibition of DNA repair enzymes (Kwon et al., 1991; Lepoivre et al., 1991), and to mediate DNA strand breaks (Nguyen et al., 1992; Fehsel et al., 1993). In several types of cells including macrophages (Albina et al., 1993; Sarih et al., 1993), chondrocytes (Blanco et al., 1995), neurons (Bonfoco et al., 1995), and islet β cells (Kaneto et al., 1995), NO has been shown to mediate apoptosis (Dimmeler and Zeiher, 1997).

Morphologically, chromatin condensation, nuclear fragmentation, and formation of apoptotic body are characteristic changes of apoptosis (Kerr, 1995). In the cascade of inducing these morphological changes, IL-1 β -converting enzyme (ICE)-like proteases or caspases play a key role (Miura et al., 1993; Nicholson et al., 1995). Activation of caspases leads to activation of a specific endonuclease (Enari et al., 1998). Digestion of DNA at the linker portions of nucleosomes by endonuclease causes fragmentation of DNA (Gaido and Cidlowski, 1991; Peitsch et al., 1993; Shiokawa et al., 1994). Many agents including NO synthase (NOS)-inducing agents have been shown to induce activation of caspases, and apoptosis follows (Hale et al., 1996).

NO is synthesized from arginine by NOS, generating citrulline. The availability of arginine is one of the rate limit-

Address correspondence to Dr. Masataka Mori, Department of Molecular Genetics, Kumamoto University School of Medicine, Kuhonji 4-24-1, Kumamoto 862-0976, Japan. Tel.: 81-96-373-5140. Fax: 81-96-373-5145. E-mail: masa@gpo.kumamoto-u.ac.jp

1. *Abbreviations used in this paper:* carboxy-PTIO, 2-(4-carboxyphenyl)-4,4,5,5-tetramethylimidazole-1-oxyl 3-oxide; Dex, dexamethasone; IFN- γ , interferon- γ ; iNOS, inducible NO synthase; LPS, lipopolysaccharide; NO, nitric oxide; NOS, NO synthase; SNAP, S-nitroso-N-acetyl-DL-penicillamine.

ing factors of cellular NO production. When the inducible type NOS (iNOS) is induced, the activity is so high that the supply of arginine is important. This amino acid can be obtained from blood circulation, intracellular protein degradation, or by regeneration from citrulline through the "citrulline-NO cycle" (Hecker et al., 1990; Hattori et al., 1994; Nussler et al., 1994; Nagasaki et al., 1996). As arginine is a common substrate for NOS and arginase, arginase may compete with NOS for arginine, and downregulate production of NO. Arginase exists in two known isoforms. Liver-type arginase (arginase I) is expressed almost exclusively in the liver and catalyzes the last step of urea synthesis. However, we found that arginase I is highly induced in rat macrophages activated with bacterial lipopolysaccharide (LPS; Sonoki et al., 1997). On the other hand, nonhepatic type (arginase II) is expressed in some extrahepatic tissues (Grody et al., 1989). Recently, we (Gotoh et al., 1996) and others (Vockley et al., 1996; Morris et al., 1997) cloned human arginase II cDNA and localized the arginase II gene to chromosome 14q24.1-24.3 (Gotoh et al., 1997). Activity (Wang et al., 1995) and mRNA (Gotoh et al., 1996) of arginase II, as well as those of iNOS, are induced by LPS in murine macrophage-like RAW 264.7 cells. On the other hand, treatment of RAW cells with LPS and interferon- γ (IFN- γ) induces apoptosis (Messmer et al., 1996).

Here, we report that the LPS/IFN- γ -dependent apoptosis of RAW cells is prevented by dexamethasone (Dex) and cAMP, and that this antiapoptotic effect depends on induction of arginase II that leads to suppression of iNOS-dependent production of NO in these cells.

Materials and Methods

Plasmids

pCAGGS-rAI, a mammalian expression plasmid for rat arginase I, was constructed by inserting the EcoRI-PstI fragment of pARGr-2 (Kawamoto et al., 1987) into the EcoRI site of the plasmid pCAGGS (Niwa et al., 1991) after linker attachment. The rat arginase II cDNA clone was isolated by PCR, using mRNA from the small intestine of a male Wistar rat. PCR was carried out using rat arginase II primers corresponding to nucleotides 86–1211 (GenBank, accession number U90887). The obtained product was inserted into the HincII site of pGEM-3Zf(+) (Promega Corp.), yielding pGEM-rAII-2.

Materials

Antiserum against human arginase II was raised in a rabbit by injecting *Escherichia coli*-expressed and the purified mature portion of human arginase II (residues 25–354). A monoclonal antibody against mouse iNOS was obtained from Transduction Laboratories.

Cell Culture and DNA Transfection

Mouse macrophage-like RAW 264.7 cells were grown in Eagle's minimal essential medium supplemented with 10% fetal calf serum. Transfection of RAW cells with plasmids was carried out using TransIT-LT1 Polyamine (PanVera Corp.) according to the protocol provided by the manufacturer.

Treatment of RAW Cells

RAW cells were cultured in medium with or without 1 μ M Dex and/or 1 mM dibutyryl cAMP for 24 h, and then treated with various combinations of *E. coli* LPS (serotype 0127:B8, Sigma Chem. Co., 150 μ g/ml) and mouse IFN- γ (100 U/ml) for indicated periods. A NO scavenger carboxy-PTIO [2-(4-carboxyphenyl)-4,4,5,5-tetramethylimidazole-1-oxyl 3-oxide, 300

μ M] or a NO donor SNAP (*S*-nitroso-*N*-acetyl-DL-penicillamine, 1 mM) was added to the medium concomitantly with the addition of LPS and/or IFN- γ .

RNA Blot Analysis

Total RNA from RAW cells was prepared by the guanidium thiocyanate-phenol-chloroform extraction procedure (Chomczynski and Sacchi, 1987). After electrophoresis in formaldehyde-containing agarose gels, RNAs were transferred to nylon membranes. Hybridization was performed using digoxigenin-labeled antisense RNAs as probes for rat iNOS, or rat arginase II. The antisense RNAs were synthesized using as templates pCDNAII-riNOS (Nagasaki et al., 1996), or pGEM-rAII-2, digested by appropriate restriction enzymes. Chemiluminescence signals derived from hybridized probes were detected on x-ray films using DIG luminescence detection kits (Boehringer Mannheim GmbH), and were quantified using a MacBAS bio-image analyzer (Fuji Photo Film Co.).

Immunoblot Analysis

RAW cells were homogenized in 20 mM Hepes-KOH (pH 7.5) containing 1% Triton X-100, 20% glycerol, and 1 mM dithiothreitol. After centrifugation, the supernatants were used as cell extracts for immunoblot analysis. The cell extracts were subjected to SDS-polyacrylamide gel electrophoresis, and proteins were electrotransferred to nitrocellulose membranes. Immunodetection was performed using ECL kits (Nycomed Amersham), according to the protocol provided by the manufacturer. The results were quantified using a MacBAS bio-image analyzer.

Immunocytochemical Staining

RAW cells were cultured on coverslips and transfected with the human arginase II expression plasmid or stimulated with LPS (150 μ g/ml), Dex (1 μ M), and dibutyryl cAMP (1 mM), as described above. The cells were fixed with 4% paraformaldehyde for 40 min at room temperature and treated with phosphate-buffered saline containing 1% Triton X-100. The cells were then incubated with antiserum against human arginase II and then with goat anti-rabbit IgG conjugated with FITC (Vector Laboratories) as the second antibody. The stained cells were observed under a fluorescence microscope.

Detection of Apoptosis

RAW cells were treated as described above. To analyze morphological changes of nuclei, the cells were fixed, stained with 8 μ g/ml of the Hoechst dye 33258 for 5 min, and washed with phosphate-buffered saline. The stained cells were observed under a fluorescence microscope. DNA fragmentation was detected by the terminal transferase-mediated dUTP-biotin nick end labeling method (TUNEL method), using in situ apoptosis detection kits (Takara) according to the protocol provided by the manufacturer. To detect DNA ladder formation, we used apoptosis ladder detection kits (Wako Pure Chemical Industries) according to the protocol provided by the manufacturer. DNA was isolated from the cells, resolved on agarose gels, stained with SYBR Green I, and visualized by UV transillumination.

Other Methods

Arginase activity was measured as described in Schimke (1962). Concentration of NO₂⁻ plus NO₃⁻ in culture supernatants was measured using the Griess reagent with the NO₂/NO₃ assay kit-C (Dojindo Labs) after reduction of NO₃⁻ to NO₂⁻ according to the protocol provided by the manufacturer.

Results

LPS/IFN- γ Induces NO-mediated Apoptosis of RAW Cells

When mouse macrophage-like RAW 264.7 cells were treated with LPS/IFN- γ for 24 h, morphological changes characteristic of apoptosis occurred (Fig. 1 A). Round-shaped cells and apoptotic bodies were observed in phase-




Figure 1. Induction of NO-mediated apoptosis of RAW cells by treatment with LPS and IFN- γ . (A) RAW cells were cultured for 24 h with (d-f) or without (a-c) 150 μ g/ml LPS and 100 U/ml IFN- γ . After fixation, the cells were analyzed for apoptosis by the TUNEL method (b and e) or stained with a DNA-specific fluorochrome Hoechst dye 33258 (c and f). Phase-contrast images (a and d) and fluorescence images (b and e) of the same fields are shown. Original magnifications: a, b, d, and e, \times 400; c and f, \times 1,000. Bars, 10 μ m. When the cells were treated with

contrast images, and chromatin condensation and nucleus fragmentation were seen in the case of Hoechst dye 33258 staining. Most cells were positive for TUNEL staining. These apoptotic changes were strongly prevented by adding a NO scavenger carboxy-PTIO (Akaike et al., 1993; Fig. 1 B). These results show that LPS/IFN- γ induces apoptosis of RAW cells, and this apoptosis is mediated by NO. LPS alone was much less effective in inducing apoptosis (data not shown).

Induction of Arginase II Prevents iNOS-dependent Apoptosis of RAW Cells

NO is synthesized from arginine, a common substrate for NOS and arginase. We reported that iNOS and arginase II mRNAs are coinduced in RAW cells by LPS (Gotoh et al., 1996). On the other hand, when these cells were treated with LPS plus IFN- γ , the induction of iNOS mRNA was augmented, whereas the induction of arginase II was strongly suppressed (Gotoh et al., 1996).

We then asked whether LPS/IFN- γ -induced apoptosis would be prevented by arginase II induction. RAW cells were cultured in the presence or absence of Dex/cAMP for 24 h, and then treated with LPS or IFN- γ , or their combination for 6 or 12 h (Fig. 2 A). Fig. 2, B and C, shows effects of various combinations of reagents on iNOS and arginase II mRNAs. iNOS mRNA of \sim 4.5 kb was not evident in the untreated cells but was induced by LPS, and this induction was enhanced by IFN- γ or Dex/cAMP, and even more strongly by their combination. Dex/cAMP was without effect. Arginase II mRNA of \sim 1.8 kb that was low in untreated cells was induced by LPS or Dex/cAMP and even more so by their combination. IFN- γ strongly prevented the induction of arginase II by LPS, whereas it had little effect on the induction by LPS plus Dex/cAMP. In other words, inhibition of LPS induction of arginase II mRNA by IFN- γ was alleviated by Dex/cAMP. cAMP alone had some effect in such cases, whereas Dex alone was ineffective (Fig. 2 D).

Fig. 2, E and F, shows immunoblot analysis of arginase II protein in RAW cells treated with Dex/cAMP for 24 h and then with LPS and/or IFN- γ for 12 h. Arginase II protein was induced by LPS and this induction was prevented by IFN- γ . It was also induced by Dex/cAMP, and LPS plus Dex/cAMP appeared to have an additive effect. The induction of arginase II protein by LPS plus Dex/cAMP was somewhat reduced by the further addition of IFN- γ . The results of arginase II protein were in accord with those of arginase II mRNA (Fig. 2, B and C).

We then examined the effect of Dex and cAMP on LPS/IFN- γ -induced apoptosis of RAW cells (Fig. 2 G). When

LPS/IFN- γ , a portion of the cells was apparently dead and detached from coverslips and the number of attached cells decreased. (B) RAW cells were cultured for 24 h with 150 μ g/ml LPS and 100 U/ml IFN- γ . At the same time of the addition of LPS/IFN- γ , a NO scavenger carboxy-PTIO (300 μ M) was added to the medium where indicated. After fixation, the cells were analyzed for apoptosis by the TUNEL method. Phase-contrast images (a and c) and fluorescence images (b and d) of the same fields are shown. Original magnifications: \times 400. Bars, 10 μ m.




Figure 2. Effect of induction of arginase II on apoptosis of RAW cells. (A) Time course of treatment of RAW cells is shown. RAW cells were cultured in the medium with or without 1 μ M Dex and/or 1 mM dibutyryl cAMP (cAMP) for 24 h, and then treated with various combinations of LPS (150 μ g/ml) and IFN- γ (100 U/ml) for 6 h for RNA blot analysis (B–D) or 12 h for immunoblot analysis and apoptosis assays (E–H). (B) RAW cells were treated with reagents as indicated and total RNAs (2 μ g) were subjected to blot analysis for iNOS and arginase II (AII) mRNAs. The positions of 18S and 28S rRNAs are shown on the right. The bottom panels in B show ethidium bromide staining of 18S and 28S rRNAs. (C) The results in B were quantitated and are shown by means \pm ranges ($n = 2$). Maximal values are set at 100%. (D) Experiments were performed as in B and the results for arginase II (AII) mRNA were quantitated and are shown by means \pm SE ($n = 3$). Maximal value is set at 100%. (E) RAW cells were treated with reagents as indicated on the top and the cell extracts (30 μ g) were subjected to immunoblot analysis for the arginase II (AII) protein. The molecular mass marker on the right

was ovalbumin (46 kD). (F) The results in E ($n = 2$) and a parallel experiment ($n = 2$) were quantitated and are shown by means \pm SE ($n = 4$). Maximal value is set at 100%. (G) RAW cells were cultured in the medium with or without 1 μ M Dex and/or 1 mM dibutyryl cAMP for 24 h, and then treated with LPS (150 μ g/ml) and IFN- γ (100 U/ml) for 12 h. After fixation, the cells were stained with Hoechst dye 33258. Phase-contrast images (a, c, e, and g) and fluorescence images (b, d, f, and h) of the same fields are shown. Original magnifications: $\times 400$. Bars, 10 μ m. The percentage of total cells which were determined to be apoptotic is shown on the bottom of each panel. (H) RAW cells were treated with reagents as indicated on the top. DNAs were isolated, resolved on an agarose gel, stained with SYBR Green I, and visualized for DNA fragmentation by UV transillumination.

cells were treated with LPS/IFN- γ , iNOS but not arginase II was induced. Under these conditions, apoptotic changes were observed. These changes were effectively prevented by Dex/cAMP; under these conditions both iNOS and ar-

ginase II were induced. Dex or cAMP alone was much less effective than their combination in arginase II induction in the presence of LPS/IFN- γ (Fig. 2 D), and was not effective in preventing apoptosis.

Fig. 2 H shows results of agarose gel electrophoresis of DNA. The formation of a DNA ladder, characteristic of apoptotic cells, was observed when the cells were treated with LPS/IFN- γ . This ladder formation was prevented by Dex/cAMP. Dex or cAMP had little effect in preventing ladder formation. All these results suggest strongly that apoptosis is prevented by the induction of arginase II.

Transfection of Arginase Expression Plasmids Prevents iNOS-dependent Apoptosis of RAW Cells

To examine the effect of arginase on apoptosis even more directly, transfection experiments were done. In a control experiment, RAW cells were treated with LPS plus Dex/cAMP to induce arginase II. After fixation, the cells were immunostained with an antibody against arginase II (Fig. 3). Little immunoreactivity was observed in untreated cells. On the other hand, when the cells were treated with LPS plus Dex/cAMP, the cells became positive for arginase II immunoreactivity. Thread-like structures were stained, results reflecting localization of arginase II in the mitochondria (Gotoh et al., 1996). When the cells were transiently transfected with the arginase II plasmid, some cells that were apparently transfected with the plasmid were strongly immunostained. Thread-like mitochondrial structures were visible in most of the positive cells, whereas whole cells were stained in some positive cells, probably due to a high overexpression of the enzyme.

Fig. 4 shows the effect of arginase II expression on apoptosis of RAW cells. Apoptotic changes were observed by




Figure 3. Immunocytochemical staining of arginase II in RAW cells. RAW cells were treated with LPS (150 μ g/ml), 1 μ M Dex, and 1 mM dibutyryl cAMP for 24 h to induce arginase II (B and C), or transfected with human arginase II expression plasmid pCAGGS-hAII and cultured for 36 h (D and E). The cells were then fixed and immunostained with rabbit antiserum against arginase II, as described in Materials and Methods. A is an untreated control. Original magnifications: A, B, and D, \times 400; C and E, \times 1000. Bars, 10 μ m.

the addition of LPS/IFN- γ . When the arginase II plasmid was transfected, some cells were protected from apoptotic change. Transfection of an expression plasmid for arginase I, a cytosolic enzyme, was also effective in protecting cells from LPS/IFN- γ -dependent apoptosis. Transfection of the insertless plasmid was without effect. These results support our hypothesis that arginase prevents apoptosis by depleting intracellular arginine and thus decreasing production of NO. Both mitochondrial arginase II and cytosolic arginase I were effective.

To gain support for this hypothesis, we examined the effect of a NO donor SNAP on apoptosis of RAW cells. SNAP alone induced apoptosis of the cells. SNAP also canceled the antiapoptotic effects of Dex/cAMP or arginase II plasmid (data not shown). Therefore, the antiapoptotic effect of arginase relates to downregulation of NO production by the enzyme. In fact, when a high concentration of arginine (12 mM) was added to the culture medium, antiapoptotic effects of the arginase II plasmid were not observed, and all the cells underwent apoptosis (data not shown). 12 mM arginine alone induced no apoptotic change of the cells.

Arginase II Suppresses NO Production in RAW Cells

We next examined the effect of arginase II induction on NO production in RAW cells (Fig. 5). NO production measured by NO₂ plus NO₃ in the culture medium was not detected in untreated cells. When the cells were treated with LPS/IFN- γ , iNOS protein was induced and NO production was markedly increased. On the other hand, when Dex plus cAMP were included with LPS/IFN- γ , iNOS protein was further induced, whereas arginase activity was highly induced, and NO production was markedly decreased. These results suggest strongly that the induced arginase II competes with iNOS for arginine and suppresses NO production.

Discussion

Arginine is a common substrate for NOS and arginase. In RAW cells, LPS/IFN- γ treatment induces iNOS and NO-mediated apoptosis. We obtained evidence that the induced arginase downregulates NO production by depleting arginine and hence preventing apoptosis. First, when arginase II was induced by Dex/cAMP in activated cells, iNOS induction was not suppressed, but apoptosis was prevented. Second, when the expression plasmid for arginase I or II was transiently transfected, some cells were prevented from apoptosis. Third, a NO donor or a high concentration of arginine canceled out this antiapoptotic effect of arginase. Fourth, NO production was suppressed under conditions where the iNOS expression remained high and arginase II was induced.

In cases of septic shock, iNOS is strongly induced and a large amount of NO is produced. This high-output production of NO is thought to lead to various symptoms, especially hypotension (Moncada and Higgs, 1993). Glucocorticoids and epinephrine are prescribed in cases of shock state. There are reports that glucocorticoids inhibit NF- κ B activity through the induction of I κ B synthesis (Auphan et al., 1995; Scheinman et al., 1995) and suppress expres-




Figure 4. Effect of transfection of arginase expression plasmids. RAW cells were transfected with insertless pCAGGS (e and f), human arginase II expression plasmid pCAGGS-hAII (g–j), or rat arginase I expression plasmid pCAGGS-rAI (k and l). 24 h after transfection, LPS (150 μ g/ml) and IFN- γ (100 U/ml) were added to the medium and cultured for 12 h. The cells were then fixed and stained with Hoechst dye 33258 except i and j that were analyzed for apoptosis by the TUNEL method after fixation. Phase-contrast images (a, c, e, g, i, and k) and fluorescence images (b, d, f, h, j, and l) of the same fields are shown. Original magnifications: $\times 400$. Bars, 10 μ m. A portion of the cells was detached from coverslips by treatment with LPS/IFN- γ (c–l). Arrows indicate cells rescued from apoptosis. The percentage of total cells which were determined to be apoptotic is shown on the bottom of each panel.

sion of inflammatory genes, including the iNOS gene. Our present results suggest that the combination of Dex, a synthetic glucocorticoid, and cAMP, a second messenger of epinephrine, may also contribute to the antishock effect by inducing arginase II and downregulating NO production. If such is the case, arginase would be a good target for therapy of septic shock and other conditions due to the overexpression of NO. NOS inhibitors usually inhibit all types of NOS and inhibition of constitutive types of NOS may cause side effects. On the other hand, the demand of iNOS for its substrate arginine is much higher than those of constitutive NOSs because of its very high activity. The induction of arginase may lead to selective inhibition of the high output NO production by iNOS.

We reported that iNOS and arginase I, not arginase II, are coinduced by LPS in cultured rat peritoneal macrophages and in the lung and spleen in vivo (Sonoki et al., 1997). The induction of arginase I is slower than that of iNOS. Based on these findings, we suggested that iNOS is first induced, NO is produced, and then arginase is induced and the sustained overproduction of NO that is

toxic to surrounding cells is prevented. In rat aortic endothelial cells, both constitutive and LPS-inducible arginase activity were reported to be present (Buga et al., 1996). The constitutive presence of arginase I and induction of arginase II by LPS were evident, as determined using immunoprecipitation experiments. iNOS is known to be highly induced in rat hepatocytes by the combination of tumor necrosis factor, IL-1, IFN- γ , and LPS (Geller et al., 1993). Treatment of rats with glucocorticoids and cAMP induces arginase I in hepatocytes (Morris et al., 1987). It remains to be seen whether expression of arginase I is affected by treatment with LPS in combination with glucocorticoids and cAMP.

Induction of arginase I and II differs between rats and mice. As reported previously (Sonoki et al., 1997) and as mentioned above, only arginase I is induced by LPS in rat peritoneal macrophages and in the lung and spleen in vivo. On the other hand, only arginase II is induced in mouse macrophage-like RAW cells (Wang et al., 1995; Gotoh et al., 1996). Thus, there appears to be a differential regulation of expression of these two isoforms in various cell types in




Figure 5. Effect of various reagents on iNOS protein (A), arginase activity (B), and NO₂/NO₃ production (C) in RAW cells. The cells were treated with or without 1 μ M Dex and 1 mM dibutyryl cAMP for 24 h and then with LPS (150 μ g/ml) and IFN- γ (100 U/ml) as indicated at the bottom for 12 h (A and B) or 18 h (C). (A) Cell extracts (30 μ g protein) were subjected to immunoblot analysis for iNOS protein and the immunoblots were quantitated and are shown by means \pm SE ($n = 3$). Maximal value is set at 100%. (B) Arginase activity of the cell extracts was measured and the results are shown by means \pm SE ($n = 3$). (C) NO₂ plus NO₃ in the medium was measured and the results are shown by means \pm SE ($n = 3$).

various species. Despite this, our results show both forms are effective in preventing NO-mediated apoptosis.

We thank M. Yano for technical advice and other colleagues for suggestions and discussion. We also thank M. Ohara for comments on the manuscript.

This work was supported in part by Grants-in-Aid (08457040 to M. Mori and 09770099 to T. Gotoh) from the Ministry of Education, Science, Sports, and Culture of Japan, and a grant (to M. Mori) from Taisho Pharmaceutical Company.

Received for publication 23 March 1998 and in revised form 23 December 1998.

References

Akaike, T., M. Yoshida, Y. Miyamoto, K. Sato, M. Kohno, K. Sasamoto, K. Miyazaki, S. Ueda, and H. Maeda. 1993. Antagonistic action of imidazole-oxyl N-oxides against endothelium-derived relaxing factor/NO through a radical reaction. *Biochemistry*. 32:827-832.

Albina, J.E., S. Cui, R.B. Mateo, and J.S. Reichner. 1993. Nitric oxide-mediated apoptosis in murine peritoneal macrophages. *J. Immunol.* 150:5080-5085.

Auphan, N., J.A. DiDonato, C. Rosette, A. Helmsberg, and M. Karin. 1995. Immunosuppression by glucocorticoids: inhibition of NF- κ B activity through induction of I κ B synthesis. *Science*. 270:286-290.

Blanco, F.J., R.L. Ochs, H. Schwarz, and M. Lotz. 1995. Chondrocyte apoptosis induced by nitric oxide. *Am. J. Pathol.* 146:75-85.

Bonfoco, E., D. Krainc, M. Ankarcrona, P. Nicotera, and S.A. Lipton. 1995. Apoptosis and necrosis: two distinct events induced, respectively, by mild and intense insults with N-methyl-D-aspartate or nitric oxide/superoxide in cortical cell cultures. *Proc. Natl. Acad. Sci. USA*. 92:7162-7166.

Buga, G.M., R. Singh, S. Pervin, N.E. Rogers, D.A. Schmitz, C.P. Jenkinson, S.D. Cederbaum, and L.J. Ignarro. 1996. Arginase activity in endothelial cells: inhibition by NG-hydroxy-L-arginine during high-output NO production. *Am. J. Physiol.* 271:H1988-H1998.

Chomczynski, P., and N. Sacchi. 1987. Single-step method of RNA isolation

by acid guanidinium thiocyanate-phenol-chloroform extraction. *Anal. Biochem.* 162:156-159.

Christopherson, K.S., and D.S. Bredt. 1997. Nitric oxide in excitable tissues: physiological roles and disease. *J. Clin. Invest.* 100:2424-2429.

Corbett, J.A., and M.L. McDaniel. 1992. Does nitric oxide mediate autoimmune destruction of β -cells? Possible therapeutic interventions in IDDM. *Diabetes*. 41:897-903.

Dawson, V.L., V.M. Kizushi, P.L. Huang, S.H. Snyder, and T.M. Dawson. 1996. Resistance to neurotoxicity in cortical cultures from neuronal nitric oxide synthase-deficient mice. *J. Neurosci.* 16:2479-2487.

Dimmeler, S., and A.M. Zeiher. 1997. Nitric oxide and apoptosis: another paradigm for the double-edged role of nitric oxide. *Nitric Oxide*. 1:275-281.

Enari, M., H. Sakahira, H. Yokoyama, K. Okawa, A. Iwamoto, and S. Nagata. 1998. A caspase-activated DNase that degrades DNA during apoptosis, and its inhibitor ICAD. *Nature*. 391:43-50.

Farrell, A.J., D.R. Blake, R.M. Palmer, and S. Moncada. 1992. Increased concentrations of nitrite in synovial fluid and serum samples suggest increased nitric oxide synthesis in rheumatic diseases. *Ann. Rheum. Dis.* 51:1219-1222.

Fehsel, K., A. Jalowy, S. Qi, V. Burkart, B. Hartmann, and H. Kolb. 1993. Islet cell DNA is a target of inflammatory attack by nitric oxide. *Diabetes*. 42: 496-500.

Gaido, M.L., and J.A. Cidlowski. 1991. Identification, purification, and characterization of a calcium-dependent endonuclease (NUC18) from apoptotic rat thymocytes. NUC18 is not histone H2B. *J. Biol. Chem.* 266:18580-18585.

Geller, D.A., A.K. Nussler, M. Di Silvio, C.J. Lowenstein, R.A. Shapiro, S.C. Wang, R.L. Simmons, and T.R. Billiar. 1993. Cytokines, endotoxin, and glucocorticoids regulate the expression of inducible nitric oxide synthase in hepatocytes. *Proc. Natl. Acad. Sci. USA*. 90:522-526.

Gotoh, T., T. Sonoki, A. Nagasaki, K. Terada, M. Takiguchi, and M. Mori. 1996. Molecular cloning of cDNA for nonhepatic mitochondrial arginase (arginase II) and comparison of its induction with nitric oxide synthase in a murine macrophage-like cell line. *FEBS Lett.* 395:119-122.

Gotoh, T., M. Araki, and M. Mori. 1997. Chromosomal localization of the human arginase II gene and tissue distribution of its mRNA. *Biochem. Biophys. Res. Commun.* 233:487-491.

Grody, W.W., C. Argyle, R.M. Kern, G.J. Dizikes, E.B. Spector, A.D. Strickland, D. Klein, and S.D. Cederbaum. 1989. Differential expression of the two human arginase genes in hyperargininemia. Enzymatic, pathologic, and molecular analysis. *J. Clin. Invest.* 83:602-609.

Hale, A.J., C.A. Smith, L.C. Sutherland, V.E. Stoneman, V.L. Longthorne, A.C. Culhane, and G.T. Williams. 1996. Apoptosis: molecular regulation of cell death. *Eur. J. Biochem.* 236:1-26.

Harrison, D.G. 1997. Cellular and molecular mechanisms of endothelial cell dysfunction. *J. Clin. Invest.* 100:2153-2157.

Hattori, Y., E.B. Campbell, and S.S. Gross. 1994. Argininosuccinate synthetase mRNA and activity are induced by immunostimulants in vascular smooth muscle. Role in the regeneration or arginine for nitric oxide synthesis. *J. Biol. Chem.* 269:9405-9408.

Hecker, M., W.C. Sessa, H.J. Harris, E.E. Anggard, and J.R. Vane. 1990. The metabolism of L-arginine and its significance for the biosynthesis of endothelium-derived relaxing factor: cultured endothelial cells recycle L-citrulline to L-arginine. *Proc. Natl. Acad. Sci. USA*. 87:8612-8616.

Hibbs, J.J., R.R. Taintor, Z. Vavrin, and E.M. Rachlin. 1988. Nitric oxide: a cytotoxic activated macrophage effector molecule. *Biochem. Biophys. Res. Commun.* 157:87-94.

Juedes, M.J., and G.N. Wogan. 1996. Peroxynitrite-induced mutation spectra of pSP189 following replication in bacteria and in human cells. *Mutat. Res.* 349: 51-61.

Kaneto, H., J. Fujii, H.G. Seo, K. Suzuki, T. Matsuoka, M. Nakamura, H. Tsumi, Y. Yamasaki, T. Kamada, and N. Taniguchi. 1995. Apoptotic cell death triggered by nitric oxide in pancreatic β -cells. *Diabetes*. 44:733-738.

Kawamoto, S., Y. Amaya, K. Murakami, F. Tokunaga, S. Iwanaga, K. Kobayashi, T. Saheki, S. Kimura, and M. Mori. 1987. Complete nucleotide sequence of cDNA and deduced amino acid sequence of rat liver arginase. *J. Biol. Chem.* 262:6280-6283.

Kerr, J.F.R. 1995. Neglected opportunities in apoptosis research. *Trends Cell Biol.* 5:55-57.

Kim, Y.M., H.A. Bergonia, C. Muller, B.R. Pitt, W.D. Watkins, and J.J. Lancaster. 1995. Loss and degradation of enzyme-bound heme induced by cellular nitric oxide synthesis. *J. Biol. Chem.* 270:5710-5713.

Kröncke, K.D., K. Fehsel, and V. Kolb-Bachofen. 1997. Nitric oxide: Cytotoxicity versus cytoprotection-how, why, when, and where? *Nitric Oxide*. 1:107-120.

Kwon, N.S., D.J. Stuehr, and C.F. Nathan. 1991. Inhibition of tumor cell ribonucleotide reductase by macrophage-derived nitric oxide. *J. Exp. Med.* 174: 761-767.

Lepoivre, M., F. Fieschi, J. Coves, L. Thelander and M. Fontecave. 1991. Inactivation of ribonucleotide reductase by nitric oxide. *Biochem. Biophys. Res. Commun.* 179:442-448.

Mayer, B., and B. Hemmens. 1997. Biosynthesis and action of nitric oxide in mammalian cells. *Trends Biochem. Sci.* 22:477-481.

Messmer, U.K., U.K. Reed, and B. Brune. 1996. Bcl-2 protects macrophages from nitric oxide-induced apoptosis. *J. Biol. Chem.* 271:20192-20197.

Miura, M., H. Zhu, R. Rotello, E.A. Hartwig, and J. Yuan. 1993. Induction of apoptosis in fibroblasts by IL-1 β -converting enzyme, a mammalian homolog of the *C. elegans* cell death gene *ced-3*. *Cell*. 75:653-660.

- Molina y Vedia, L., B. McDonald, B. Reep, B. Brüne, M. Di Silvio, T.R. Billiar, and E.G. Lapetina. 1992. Nitric oxide-induced S-nitrosylation of glyceraldehyde-3-phosphate dehydrogenase inhibits enzymatic activity and increases endogenous ADP-ribosylation. *J. Biol. Chem.* 267:24929–24932.
- Moncada, S., and A. Higgs. 1993. The L-arginine-nitric oxide pathway. *N. Engl. J. Med.* 329:2002–2012.
- Morris, S.J., C.L. Moncman, K.D. Rand, G.J. Dizikes, S.D. Cederbaum, and W.E. O'Brien. 1987. Regulation of mRNA levels for five urea cycle enzymes in rat liver by diet, cyclic AMP, and glucocorticoids. *Arch. Biochem. Biophys.* 256:343–353.
- Morris, S.J., D. Bhamidipati, and D. Kepka-Lenhart. 1997. Human type II arginase: sequence analysis and tissue-specific expression. *Gene.* 193:157–161.
- Nagasaki, A., T. Gotoh, M. Takeya, Y. Yu, M. Takiguchi, H. Matsuzaki, K. Takatsuki, and M. Mori. 1996. Coinduction of nitric oxide synthase, argininosuccinate synthetase, and argininosuccinate lyase in lipopolysaccharide-treated rats. RNA blot, immunoblot, and immunohistochemical analyses. *J. Biol. Chem.* 271:2658–2662.
- Nathan, C. 1997. Inducible nitric oxide synthase: what difference does it make? *J. Clin. Invest.* 100:2417–2423.
- Nguyen, T., D. Brunson, C.L. Crespi, B.W. Penman, J.S. Wishnok, and S.R. Tannenbaum. 1992. DNA damage and mutation in human cells exposed to nitric oxide *in vitro*. *Proc. Natl. Acad. Sci. USA.* 89:3030–3034.
- Nicholson, D.W., A. Ali, N.A. Thornberry, J.P. Vaillancourt, C.K. Ding, M. Gallant, Y. Gareau, P.R. Griffin, M. Labelle, Y.A. Lazebnik, et al. 1995. Identification and inhibition of the ICE/CED-3 protease necessary for mammalian apoptosis. *Nature.* 376:37–43.
- Niwa, H., K. Yamamura, and J. Miyazaki. 1991. Efficient selection for high-expression transfectants with a novel eukaryotic vector. *Gene.* 108:193–199.
- Nussler, A.K., T.R. Billiar, Z.Z. Liu, and S.J. Morris. 1994. Coinduction of nitric oxide synthase and argininosuccinate synthetase in a murine macrophage cell line. Implications for regulation of nitric oxide production. *J. Biol. Chem.* 269:1257–1261.
- Peitsch, M.C., B. Polzar, H. Stephan, T. Crompton, H.R. MacDonald, H.G. Mannherz, and J. Tschopp. 1993. Characterization of the endogenous deoxyribonuclease involved in nuclear DNA degradation during apoptosis (programmed cell death). *EMBO (Eur. Mol. Biol. Organ.) J.* 12:371–377.
- Routledge, M.N., F.J. Mirsky, D.A. Wink, L.K. Keefer, and A. Dipple. 1994. Nitrite-induced mutations in a forward mutation assay: influence of nitrite concentration and pH. *Mutat. Res.* 322:341–346.
- Sarih, M., V. Souvannavong, and A. Adam. 1993. Nitric oxide synthase induces macrophage death by apoptosis. *Biochem. Biophys. Res. Commun.* 191:503–508.
- Scheinman, R.I., P.C. Cogswell, A.K. Lofquist, and A.J. Baldwin. 1995. Role of transcriptional activation of I κ B α in mediation of immunosuppression by glucocorticoids. *Science.* 270:283–286.
- Schimke, R.T. 1962. Adaptive characteristics of urea cycle enzymes in the rat. *J. Biol. Chem.* 237:459–468.
- Shiokawa, D., H. Ohyama, T. Yamada, K. Takahashi, and S. Tanuma. 1994. Identification of an endonuclease responsible for apoptosis in rat thymocytes. *Eur. J. Biochem.* 226:23–30.
- Sonoki, T., A. Nagasaki, T. Gotoh, M. Takiguchi, M. Takeya, H. Matsuzaki, and M. Mori. 1997. Coinduction of nitric-oxide synthase and arginase I in cultured rat peritoneal macrophages and rat tissues *in vivo* by lipopolysaccharide. *J. Biol. Chem.* 272:3689–3693.
- Stuehr, D.J., and M.A. Marletta. 1985. Mammalian nitrate biosynthesis: mouse macrophages produce nitrite and nitrate in response to *Escherichia coli* lipopolysaccharide. *Proc. Natl. Acad. Sci. USA.* 82:7738–7742.
- Vockley, J.G., C.P. Jenkinson, H. Shukla, R.M. Kern, W.W. Grody, and S.D. Cederbaum. 1996. Cloning and characterization of the human type II arginase gene. *Genomics.* 38:118–123.
- Wang, W.W., C.P. Jenkinson, J.M. Griscavage, R.M. Kern, N.S. Arabolos, R.E. Byrns, S.D. Cederbaum, and L.J. Ignarro. 1995. Co-induction of arginase and nitric oxide synthase in murine macrophages activated by lipopolysaccharide. *Biochem. Biophys. Res. Commun.* 210:1009–1016.