

Integrative Systems

Integrative Neuroscience of *Paramecium*, a “Swimming Neuron”

 Romain Brette<https://doi.org/10.1523/ENEURO.0018-21.2021>

Sorbonne Université, Institut National de la Santé et de la Recherche Médicale, Centre National de la Recherche Scientifique, Institut de la Vision, Paris 75012, France

Abstract

Paramecium is a unicellular organism that swims in fresh water by beating thousands of cilia. When it is stimulated (mechanically, chemically, optically, thermally...), it often swims backward then turns and swims forward again. This “avoiding reaction” is triggered by a calcium-based action potential. For this reason, some authors have called *Paramecium* a “swimming neuron.” This review summarizes current knowledge about the physiological basis of behavior of *Paramecium*.

Key words: ciliates; excitability; *Paramecium*; sensorimotor

Significance Statement

Paramecium is a unicellular organism that swims in fresh water by beating thousands of cilia. When it is stimulated (mechanically, chemically, optically, thermally...), it often swims backward then turns and swims forward again. This “avoiding reaction” is triggered by a calcium-based action potential. For this reason, some authors have called *Paramecium* a “swimming neuron.” This review summarizes current knowledge about the physiological basis of behavior of *Paramecium*.

Introduction

Even the simplest behavior must engage at least a sensory organ, a large part of the nervous system, the body (muscles, skeleton), and the environment. Thus, understanding the biological basis of behavior requires an integrative approach, which remains highly challenging given

the complexity of both the nervous and musculoskeletal systems of vertebrates. A fruitful research strategy is to study model organisms that are structurally simpler and have experimental advantages. For example, the biophysical basis of excitability was studied in the giant axon of the squid (Hodgkin, 1964), the molecular basis of learning and memory was studied in *Aplysia* (Kandel, 2009). A recent model organism to develop integrative approaches to behavior is *Caenorhabditis elegans*, with its 302 neurons and a known connectome (Schafer, 2018). In *C. Elegans*, modeling the entire organism and its interaction with the body and environment seems more feasible in principle (Cohen and Sanders, 2014; Cohen and Denham, 2019). Nevertheless, even in this more favorable situation, developing functional and empirically valid neuromechanical models of *C. elegans* remains very challenging. Two other recently introduced model organisms for this type of integrative work are *Hydra*, which has a few thousand neurons and the advantage of being transparent (Dupre and Yuste, 2017; Wang et al., 2020), and jellyfish *Aurelia aurita* (Pallasdies et al., 2019). Here, I will present a model organism that is significantly simpler as it consists of a single “neuron.”

Received January 15, 2021; accepted March 18, 2021; First published May 5, 2021.

The author declares no competing financial interests.

Author contributions: R.B. designed research; R.B. performed research; R.B. wrote the paper.

This work was supported by the Agence Nationale de la Recherche Grant ANR-20-CE30-0025-01, the Programme Investissements d’Avenir IHU FOReSIGHT Grant ANR-18-IAHU-01, the Sorbonne Université Programme Emergence Grant NEUROSIM, and the Fondation Pour l’Audition Grant FPA RD-2017-2.

Correspondence should be addressed to Romain Brette at romain.brette@inserm.fr.

<https://doi.org/10.1523/ENEURO.0018-21.2021>

Copyright © 2021 Brette

This is an open-access article distributed under the terms of the Creative Commons Attribution 4.0 International license, which permits unrestricted use, distribution and reproduction in any medium provided that the original work is properly attributed.




Figure 1. *Paramecium* morphology. **A**, Scanning electron microscopy image of *P. tetraurelia*; scale bar: 10 μ m (Valentine et al., 2012). **B**, *Paramecium caudatum* (Jennings, 1899a), a large species (~200 μ m) with a pointed posterior end. a, anterior end; p, posterior end; g, oral groove; m, mouth; o, oral side; ab, aboral side; cv, contractile vacuole. The drawing also shows food vacuoles and cilia.

Paramecium is a single-cell eukaryote, 100–300 μ m long depending on species (Fokin, 2010; Fig. 1), which has long been a model organism for many aspects of eukaryotic biology (Wichterman, 1986; Görtz, 1988). It is a ciliate that has been living in ponds and lakes all over the world for hundreds of millions of years (Parfrey et al., 2011), a fossil has been discovered in a 200 million-year-old piece of amber (Schönborn et al., 1999). Its abundance and large size made it a popular subject of behavioral study in the late 19th century; Jennings described his culture method as follows (Jennings, 1897): “A handful of hay or grass is placed in a jar and covered with hydrant water. In a few weeks the solution of decaying vegetable matter swarms with paramecia.”

Paramecium swims in fresh water by beating its thousands of cilia, and feeds on smaller microorganisms such as bacteria and algae. It is a prey for other microorganisms such as *Didinium*. As beautifully described by Jennings more than a century ago (1906), *Paramecium* lives in a rich sensory environment: it finds food by detecting and following chemicals produced by decaying plants and fellow paramecia; it moves toward the water surface

by gravitaxis; it avoids obstacles thanks to its mechanosensitivity; it resists water currents by rheotaxis; it avoids bright light; it avoids hot and cold waters; it even communicates chemically. It typically swims in helicoidal paths interrupted by abrupt changes in direction called avoiding reactions, which form the “trial-and-error” basis of its behavior. When an unfavorable condition is met (obstacle, unwanted chemical), the avoiding reaction is triggered (Fig. 2A): *Paramecium* swims backward for a brief time, then turns and swims forward in a new direction. By this simple mechanism, *Paramecium* can navigate in crowded multisensory environments.

This avoiding reaction is triggered by an action potential produced by voltage-gated calcium channels located in the cilia (Fig. 2B; Eckert, 1972). These are L-type calcium channels related to the Ca_v1 family found in neurons, heart and muscles of mammals (Lodh et al., 2016). A number of other ionic currents have been identified (Eckert and Brehm, 1979), and genes for many more ionic channels have been found in the genome, often homologs of mammalian channels (Martinac et al., 2008). Sensitivity to various sensory signals is provided by transduction into ionic currents, which may then trigger action potentials. Piezo channels, which convey mechanosensitivity in many species including mammals (Coste et al., 2010) have been identified in the genome. A rhodopsin-like protein has been identified in *Paramecium bursaria*, a photosensitive species (Nakaoka et al., 1991). In fact, many signaling pathways of neurons have been found in *Paramecium*, in particular calcium signaling pathways (Plattner and Verkhatsky, 2018), calcium release channels, pumps, calmodulin, centrin, calcineurin, SNARE proteins, cAMP and cGMP-dependent kinases, etc. For this reason, some authors have called *Paramecium* a “swimming neuron” (Kung and Saimi, 1985).

Many other motile unicellular organisms have rich behavior (Wan and Jékely, 2020) and produce action potentials, including microalgae (Eckert and Sibaoka, 1968; Harz and Hegemann, 1991; Taylor, 2009), other ciliates such as *Stentor* (Wood, 1991), other protists such as *Actinocoryne contractilis* (Febvre-Chevalier et al., 1986) and even bacteria (Kralj et al., 2011; Masi et al., 2015). One advantage of *Paramecium* is its large size, allowing relatively simple electrophysiological recordings (Naitoh and Eckert, 1972; Kulkarni et al., 2020). For this reason,




Figure 2. The avoiding reaction triggered by an action potential. **A**, Avoiding reaction against an obstacle, as illustrated by Jennings (1906). **B**, Action potential in response to a 2-ms current pulse (top), recorded with the hanging droplet method (bottom; from Naitoh et al., 1972 with permission).




Figure 3. Swimming, feeding and reproducing. **A**, Spiral swimming, with the oral groove facing the spiral axis (Jennings, 1899a). **B**, Thigmotactic *Paramecium* resting against a fiber (Jennings, 1897). Arrows show water currents produced by oral cilia. **C**, Two paramecia in conjugation (sexual reproduction; Jennings, 1904).

there is a rich literature on *Paramecium* electrophysiology, mostly from the 1960–1980s (Eckert, 1972; Eckert and Brehm, 1979). In addition, *Paramecium* is still an active model organism in genetics, and benefits from many tools such as RNA interference (Galvani and Sperling, 2002); its genome has also been sequenced (Aury et al., 2006; McGrath et al., 2014).

I will first give an overview of the behavior of *Paramecium*, then I will explain how it moves with its body and cilia, and finally I will describe the physiological basis of behavior, with a special focus on the avoiding reaction. Most studies cited in this review were done on two species, *P. caudatum* and *P. aurelia*.

The Life of *Paramecium*

Swimming, feeding, reproducing

Behavior has been described in detail in articles and books by Jennings and a few contemporary scientists, in the late 19th and early 20th century (Jensen, 1893; Ludloff, 1895; Mendelssohn, 1895; Jennings, 1897, 1906); these observations would benefit from precise and systematic measurements with modern techniques. *Paramecium* lives in fresh water in various kinds of habitats, differing in temperature and composition. It swims in spiral paths at ~ 1 mm/s by beating its thousands of cilia, revolving around its long axis at about one cycle per second, the oral groove facing the spiral axis (Fig. 3A; Jennings, 1899a; Bullington, 1930). These paths are occasionally interrupted by abrupt changes in direction, which can be preceded by a short period of backward swimming.

It is often found near the water surface, as it tends to swim against gravity (Jensen, 1893; p. 18). When it hits a solid surface such as glass or wood, it gives the avoiding reaction (Fig. 2A). But when it encounters some fibrous material such as a decaying plant or a piece of cloth, it may stall (Jennings, 1897). This behavior has been termed contact reaction or thigmotaxis (Fig. 3B). It can also occur on properly coated glass (Iwatsuki et al., 1996). The cilia in contact with the object are immobilized, and all the other cilia are quiet or quivering except the oral cilia, which beat strongly. In this situation, *Paramecium* may feed, for example on bacteria, yeast or algae. Food is brought into its oral groove by powerful cilia, which have different properties from locomotor cilia (Jung et al., 2014; Aubusson-Fleury et al., 2015).

A well-fed *Paramecium* can reproduce by fission every 6 h (Beisson et al., 2010a), depending on temperature (Krenek et al., 2011). Without food, *Paramecium* can survive for several weeks (Jackson and Berger, 1984). Starvation triggers sexual reproduction, where two individuals of opposite mating types attach to each other by the oral side and exchange genetic material (Fig. 3C). In *P. aurelia*, sexual reproduction can also occur by autogamy (with itself; Beisson et al., 2010b).

Navigating

When *Paramecium* encounters a solid obstacle, it swims backward for a fraction of second, still revolving around its long axis, then the anterior end turns while the posterior end is still (Fig. 2A). This is called the avoiding reaction; it forms the basis of much of its behavior. According to Jennings, the organism always turns toward the same structurally defined side, the “aboral” side (away from the oral groove; Jennings, 1899a), although systematic measurements are lacking. But since it also revolves along its long axis, from a fixed viewpoint the change in direction may alternate between left and right. Thus, the change in direction may be considered as pseudo-random.

The avoiding reaction is graded (Fig. 4). A weak stimulus may only trigger a gentle reorientation with no backward swimming (Fig. 4A), while a stronger stimulus induces backward swimming and reorientation (Fig. 4B). A very strong stimulus may trigger long backward swimming followed by turning a complete circle (Fig. 4C). This graded reaction parallels the graded action potential: the duration of backward swimming correlates with the stimulus-induced depolarization (Machemer and Eckert, 1973).

Paramecium also reacts when the rear is touched, but in a different way (Fig. 5A): it swims forward faster, by beating its cilia up to twice faster (Machemer, 1974). This speed increase is accompanied by a contraction along the longitudinal axis (Nakaoka and Machemer, 1990). This is called the escape reaction, first described by Roesle in 1903 (Roesle, 1903), then by Jennings (Jennings, 1904). Non-localized mechanical stimulation, as when shaking a tube of *Paramecium* culture, also induces an increase in swimming speed that can last for several minutes.

When stimulated by a strong heat using a laser (5–10°C increase), *Paramecium* can jump away from the stimulus




Figure 4. The avoiding reaction is graded (Jennings, 1904): swinging of the anterior end in a weak reaction (A), a strong reaction (B) and a very strong reaction (C).

(possibly sideways) within just 5 ms, at ~ 10 mm/s (Hamel et al., 2011; Fig. 5B). To perform this feat, *Paramecium* throws trichocysts, which are sorts of needles docked near the membrane, thereby projecting itself in the opposite direction. The same behavior occurs in reaction to an appropriate chemical stimulus and in encounters with the predator *Dileptus* (Knoll et al., 1991).

When *Paramecium* swims in a narrow channel that does not allow it to turn, it may be trapped into a dead end, where it will give the avoiding reaction repeatedly, alternatively moving backward and forward against the wall

(Kunita et al., 2014). But after a minute, the avoiding reaction suddenly becomes much longer (several millimeters), potentially allowing the organism to escape (Fig. 5C). When the channel is very narrow, *Paramecium* may also bend itself to move forward (Jana et al., 2015; Smith, 1908; Fig. 5D). The posterior end anchors onto the wall, presumably because tail cilia do not beat (Machemer and Machemer-Röhnisch, 1984; Ishikawa and Hota, 2006), while the anterior end slides along the other wall, causing the cell to bend until it can swim freely. Under some conditions, *Paramecium* can also slide along surfaces (Li and Ardekani, 2014; Nishigami et al., 2018; Ohmura et al., 2018). Some of this behavior is due not to physiological responses but to hydrodynamic interactions with surfaces (Berke et al., 2008; Lauga and Powers, 2009; Li and Ardekani, 2014; Ohmura et al., 2018).

Finally, in a water current, *Paramecium* orients itself with its anterior end directed up stream, a behavior called rheotaxis. According to Jennings (1906), rheotaxis derives from the avoiding reaction. When *Paramecium* swims along the water current, its cilia beat backwards and the water current opposes that movement. This acts as a mechanical stimulus which triggers the avoidance reaction. By trial and error, *Paramecium* turns until it faces the current. However, this remains an untested hypothesis. In a few other microorganisms, rheotaxis has been attributed to hydrodynamic effects (Bretherton and Rothschild, 1961; Marcos et al., 2012).

Chemical sensing and social behavior

Paramecium is sensitive to a variety of chemical compounds (Jennings, 1899b; Nakatani, 1968; Dryl, 1973; Valentine et al., 2008). It is attracted by some substances, in particular bacterial metabolites (folate, acetate, glutamate, cAMP, biotin, ammonium, etc.), weak acids, carbon dioxide, colloidal solutions. These substances may indicate the distal presence of food, possibly components of the “phycosphere,” the rich interface between phytoplankton and bacteria (Seymour et al., 2017).

Other substances are repellent (e.g., alkaline solutions, quinine, ATP, GTP, GDP, NBT, Alcian Blue, Cibacron blue, Cytochrome c; Francis and Hennessey, 1995).




Figure 5. *Paramecium* navigation. **A**, Escape reaction triggered by a heat stimulus (laser) near the posterior end (star; Hamel et al., 2011). **B**, Sideways jumping from a strong heat stimulus (star) by throwing trichocysts (Hamel et al., 2011). **C**, Trajectory of *Paramecium* in a 5-mm capillary, showing an increase in backward swimming after 1 min, corresponding to ~ 40 avoiding reactions (Kunita et al., 2014). **D**, Bending of *P. caudatum* in a 160- μ m channel (Jana et al., 2015).




Figure 6. Chemotaxis and social behavior. **A**, Gathering of paramecia in a drop of weakly acid solution (Jennings, 1899a). **B**, Path followed by *Paramecium* in a drop of acid (Jennings, 1906). **C**, paramecia avoiding a drop of sodium carbonate (Jennings, 1899a). **D**, paramecia gathering in a cloud of carbon dioxide generated by their respiration (Jennings, 1899a).

Some of these molecules may signal the distal presence of a noxious condition. For example, Hennessey speculated that ATP and GTP are strong repellents because they are “blood-in-the-water signals” (Hennessey, 2005); these molecules are present at high concentrations in cells, and so their presence signals cell lysis, and whatever dangerous condition might have caused it.

Some substances only produce a reaction when *Paramecium* is subject to toxic doses (cane sugar, dextrose, urea), effectively killing it (Jennings, 1899b). For example, after some time, cane sugar induces plasmolysis, and then *Paramecium* begins to swim backward and forward repeatedly, possibly because of the induced depolarization. But many substances are toxic at doses much larger than the sensitivity threshold. In a number of cases, this sensitivity is conferred by specific membrane receptors, which can depolarize or hyperpolarize the cell (Van Houten, 1998) and possibly modulate ionic channels (Oami, 1996a,b).

In the 19th century, Jennings described the behavior of paramecia gathering in a drop of weak acid (Fig. 6A). He linked this behavior to the avoiding reaction. When *Paramecium* enters a drop of acid, its course is unchanged; but when it reaches the border of the drop, it gives the avoiding reaction and therefore remains in the drop (Fig. 6B). On the contrary, alkaline solutions are repellent: an avoiding reaction is triggered as soon as the alkaline solution is reached (Fig. 6C). More recently, various substances have been characterized as attractant or repellent based on the accumulation of paramecia in a test solution relative to a control solution, using different behavioral assays (Van Houten et al., 1975; Leick and Helle, 1983; Levandowsky et al., 1984; Nakazato and Naitoh, 1993; Valentine and Van Houten, 2016).

As previously mentioned, when stimulated, *Paramecium* turns to a structurally defined side (the aboral side, away from the mouth). Therefore, *Paramecium* is not attracted to a

substance because it turns toward it. Rather, its behavior seems to result from trial and error: if attractant concentration increases, then *Paramecium* keeps on swimming in the same direction; if it decreases, then *Paramecium* changes direction. Jennings reported that the reaction of the organism is independent of where the chemical substance is applied; however, this may well depend on the compound because some chemoreceptors are spatially organized (Preston and Van Houten, 1987; Oami, 1996b).

For this reason, this behavior is sometimes named chemokinesis (changes in motility with chemical signals), which is more general than chemotaxis (movements toward a chemical stimulus; Houten, 1979). In particular, chemokinesis can result not only from modulation of the avoiding reaction (named klinokinesis), but also of swimming speed (named orthokinesis; Houten, 1978). Nonetheless, the chemical modulation of this apparently random motion can lead to motion toward the chemical source, and presumably to a preferred orientation of the body in the direction of the source (since the organism spends more time in the favored direction). There is some similarity with run-and-tumble chemotaxis in bacteria for which there is a dense literature (Berg, 2008; Sourjik and Wingreen, 2012), including theoretical (Berg and Purcell, 1977; Kollmann et al., 2005; Tu et al., 2008; Celani and Vergassola, 2010; Tu, 2013), and with pirouettes in *C. elegans* (Pierce-Shimomura et al., 1999).

A consequence of *Paramecium* attraction to weak acids is social behavior, as observed by Jennings (Jennings, 1897). By their respiration, *Paramecium* produces CO₂, which is acid in solutions. At low concentration, *Paramecium* is attracted to CO₂. It follows that paramecia tend to attract each other (Fig. 6D). This explains why gatherings can be observed at the bottom of a watch glass or at random positions in a tube. This may play an important role in feeding behavior, as it allows paramecia to collectively search for food.

Finally, *Paramecium* also has GABA_A and GABA_B receptors that can influence its behavior (Bucci et al., 2005; Ramoino et al., 2003, 2004). For example, the activation of GABA_B receptors inhibits the avoiding reaction. In addition, *Paramecium* releases GABA on stimulation. This release might act as a signal for other paramecia, or perhaps as an externalized spatial memory for exploration (as observed in slime mold; Reid et al., 2012), making the organism take a different action when it comes back to the same location. NMDA-like receptors have also been identified (Ramoino et al., 2014).

The logic of *Paramecium* behavior

Many aspects of *Paramecium* behavior can be described as trial and error (1906). If its path is blocked by an obstacle, *Paramecium* withdraws then tries a new direction. If it encounters an undesirable chemical signal, it changes direction. If it leaves a desirable region, it withdraws and tries a new direction. This logic also applies to other sensory modalities. For example, when placed in a gradient of temperature, *Paramecium* accumulates in regions with temperature close to their culture temperature (Mendelssohn, 1895; Jennings, 1906). Again, this occurs by temperature-triggered avoiding reactions. When temperature changes away from culture temperature (whether this corresponds to a decrease or an increase), the avoiding reaction rate transiently increases; conversely, the avoiding reaction rate decreases when temperature gets closer to culture temperature (Nakaoka and Oosawa, 1977). This behavior is mediated by membrane potential changes (Tominaga and Naitoh, 1992) produced by cold-sensitive and heat-sensitive thermoreceptors (Tominaga and Naitoh, 1994; Kuriu et al., 1996, 1998).

Paramecium also shows photophobic responses to large changes in the intensity of visible light (mainly green, and red; Iwatsuki and Naitoh, 1982, 1983a,b; Hinrichsen and Peters, 2013). When *Paramecium* is kept in the dark and a bright light is turned on, it displays the avoiding reaction with a latency of around a second, then adapts over ~15 s. As a result, *Paramecium* tends to accumulate in shaded regions. A related species, *P. bursaria*, is naturally highly sensitive to light and accumulates in lighted regions (Saji and Oosawa, 1974). This species harbors a symbiotic green alga named *Chlorella*: the alga provides photosynthetic products to its host while the host brings the alga in suitable light conditions. A moderate decrease in light intensity triggers an avoiding reaction, which makes *P. bursaria* seek light.

This trial-and-error behavior shares some similarity with the run-and-tumble behavior of bacteria (Berg, 1975). Macroscopically, trajectories of *Escherichia coli* resemble *Paramecium* trajectories, with helicoidal “runs” interrupted by “tumbles” where the cell changes direction randomly. Bacterial chemotaxis is enabled by concentration-dependent modulation of the tumbling rate: the tumbling rate decreases when concentration increases, while it is unchanged when concentration decreases. Thus, tumbling is not an avoiding reaction (it is not triggered by a concentration decrease). In *Paramecium*, the new direction is somewhat (pseudo-)random, but the turning event seems

more deterministically related to environmental conditions than in bacteria. In other words, the avoiding reaction of *Paramecium* is more akin to a decision based on sensory inputs, than to a modulation of the spontaneous turning rate. This difference with bacteria may be because of a difference in scale: compared with bacteria, the membrane surface of *Paramecium* is at least two orders of magnitude larger, so that the signal-to-noise ratio is at least one order of magnitude larger; membrane potential fluctuations are ~1–3 mV (Moolenaar et al., 1976; Nakaoka et al., 2009).

This simple logic of behavior calls for a couple of remarks in the context of neuroscience. First, it is somewhat surprising that a single spiking “neuron” can control relatively complex navigation in crowded multisensory environments, social behavior, and perhaps spatial memory. In terms of connectionism (Seung, 2012), *Paramecium* is a zero-connectome organism, and yet it can accomplish a variety of ecologically relevant tasks. This arises not from the complexity of the cell, which is electrically much simpler than a single pyramidal cortical neuron (it is isopotential), but rather from the interaction between this spiking cell and the environment, together with the exploratory properties conferred by the pseudo-random nature of the effect of a spike. This highlights the importance of embodiment and coupling with the environment, which are increasingly appreciated in cognitive science and philosophy of mind (Maturana and Varela, 1973; Powers, 1973; Gibson, 1979; Brooks, 1991; Bickhard and Terveen, 1996; Hurley, 2001; O’Regan and Noë, 2001; Ahissar and Assa, 2016; Pezzulo and Cisek, 2016; Brette, 2019).

Second, “control” may not be the right term to describe the relation between spiking and behavior. Motor control is classically described as feedforward or feedback (Wolpert and Ghahramani, 2000). In feedforward control, internal models are used to plan movements, and specific sets of neurons are recruited to trigger the appropriate movements. In *Paramecium*, spiking produces a single type of movement, regardless of the goal or stimulus: it does not move by planning specific movements. In feedback control, actions are taken that reduce the difference between the observed state and a desired state. In *Paramecium*, an action is also taken when the observed state is undesirable, but that action is not directed toward the goal, rather, it is (pseudo-)random. Thus, *Paramecium* movements are based neither on feedforward nor on feedback control, but rather on exploration and selection (trial and error). This is reminiscent of the Darwinian insight that an apparently goal-directed process can occur through random exploration and elimination of unsuccessful choices, rather than by either planning or steering.

Adaptation

Paramecium lives in habitats of diverse ionic composition. Changes in ionic composition directly affect ionic currents and reversal potentials, and therefore can potentially interfere with behavior. For example, moderate changes in cation concentration can alter swimming velocity (Machemer, 1989; Nakaoka et al., 1983). More critically, an increase in potassium concentration can inhibit the avoiding reaction through depolarization-induced




Figure 7. Adaptation. **A**, Change in swimming velocity when *Paramecium* adapted to a solution of 0.25 mM CaCl_2 and 4 mM KCl is transferred to a solution of 0.25 mM CaCl_2 and 1 mM (open circles), 2 mM (closed circles), 4 mM (squares), or 16 mM (triangles) KCl (from Oka et al., 1986). **B**, Resting potential versus KCl concentration for cells adapted to 2 mM, 4 mM, 8 mM, and 16 mM KCl (top to bottom; Oka et al., 1986, with permission). Arrows indicate the adapted state. **C**, Accumulation of *Paramecium* in a warm region (Jennings, 1899a). The top of the slide is placed on a 40°C bath while the bottom rests on ice. **D**, Change in avoiding reaction rate after paramecia cultured at 25°C are transferred to 30°C (from Nakaoka et al., 1982, with permission). Note the change in time scale.

inactivation of the ciliary calcium channels (Oka and Nakaoka, 1989), making the organism unresponsive to stimulation. Remarkably, after a couple of hours, behavior returns to its normal state before the medium changed (Oka et al., 1986; Fig. 7A). In parallel, the resting potential changes after a medium change then decays back to its original value (Fig. 7B). This homeostatic regulation appears to be mediated by changes in channel permeability. With a more prolonged (48 h) exposure to a high potassium solution, more complex changes in excitability can occur, with enhanced responses to Mg^{2+} and Na^+ (Preston and Hammond, 1998).

Temperature also affects ionic channel properties and the entire metabolism of the organism, as well as hydrodynamic properties (viscosity of water). For example, when temperature is lowered, the ciliary calcium current is smaller and slower, action potentials are smaller and broader, cilia reverse with longer latency and for a longer time (Machemer, 1974). As previously discussed, *Paramecium* has a thermoregulation mechanism based on movement: using the avoiding reaction, it navigates toward waters of a preferred temperature (Fig. 7C). However, this mechanism is insufficient if the medium changes temperature globally. Remarkably, in this case, *Paramecium* adapts over a couple of hours: behavior returns to normal and the new temperature

becomes the preferred temperature (Nakaoka et al., 1982; Fig. 7D). This behavioral adaptation correlates with changes in electrophysiological properties, in particular of the ciliary calcium conductance (Martinac and Machemer, 1984).

Learning

Beyond adaptation, there is an important literature on learning in *Paramecium* and other ciliates. Unfortunately, as reviewed by Applewhite (1979), many of those studies are difficult to interpret as they lack appropriate controls or observations. In a series of papers (Gelber, 1952, 1956, 1957, 1958, 1962a,b), Gelber showed an apparent reinforcement of behavior with a food reward (see (Gershman et al., 2021) for a recent commentary). A platinum wire is lowered repeatedly into a depression slide with paramecia. If the wire is intermittently baited with bacteria, then more and more paramecia cling to the wire, even when a clean wire is finally lowered into the slide. What might be the stimulus? Gelber (1956) noted that the behavior was not observed when paramecia, with permission developed an attraction to a reflection or shadow cast by the wire.

These observations were controversial, because it was objected that lowering the baited wire introduces bacteria

in the fluid, to which paramecia are then attracted even when the wire is removed or cleaned (Jensen, 1957). In support of this interpretation, Katz and Deterline (1958) replicated Gelber's main findings but found that stirring before the final test destroyed the observed behavior. Naturally, this could be interpreted as an erasure of learning because of the mechanical disturbance, but perhaps more crucially, they found that Gelber's observations could be reproduced when the entire experiment (not just the test) was done in the dark, effectively removing any distal sensory stimulus by which paramecia may be able to recognize the wire. A plausible explanation, in line with informal observations reported in this set of studies, is that feeding reduces the activity of paramecia so that they tend to stay near the wire, and promotes thigmotaxis so that they tend to adhere more easily to the wire. In this case, the procedure would indeed reinforce a behavior, namely the feeding behavior, but not a stimulus-specific behavior. More detailed observations seem necessary to understand the phenomenon.

Another phenomenon that has attracted some attention is tube escape learning, first described by French in 1940 (French, 1940). A single *Paramecium* is placed in a drop and a thin tube is lowered into it. The organism is drawn into the tube by capillarity. It then escapes from the bottom after ~30 s. When the experiment is repeated, escape time decreases to around 15 s after a few trials. French states that after the initial trials, paramecia go and back and forth in the tube only a few times then take "one long dive to the bottom." The faster escape persists for at least 2 h (Huber et al., 1974), which seems to rule out the possibility that *Paramecium* simply adapts to the mechanical stimulus of capillary suction. This phenomenon has been robustly reproduced by several authors (Hanzel and Rucker, 1972; Applewhite and Gardner, 1973), but its basis is unclear. Applewhite and Gardner (1973) proposed that *Paramecium* released some substance in the tube that then influences future behavior, but this hypothesis contradicts earlier results by Hanzel and Rucker (1972) showing the same performance improvement in multiple paramecia with the same tube. Studies of tube escape learning in *Stentor*, another ciliate, suggest that the phenomenon is related to gravitaxis (Bennett and Francis, 1972; Hinkle and Wood, 1994). Performance improvement is seen only when the tube is vertical, not when it is horizontal, where escape is fast from the first trial. This suggests the following (speculative) explanation: in a vertical tube, paramecia are trapped near the top because of negative gravitaxis, then prolonged confinement (perhaps signaled by frequent avoiding reactions) inhibits the normal gravitactic behavior, so that the organism can escape to the bottom.

Finally, Hennessey et al. (1979) managed to train *Paramecium* to react to sounds. When a tone is played by a speaker below the slide, *Paramecium* shows no reaction. However, when the tone is paired with electrical stimulation triggered in the middle of the tone, *Paramecium* reacts to the stimulus with an avoiding reaction, then after a few trials gives an avoiding reaction at the onset of the tone, in anticipation of the electrical

stimulus. The authors demonstrate extinction (reaction disappears when sound is presented alone), retention and specificity (reacting specifically to a 300-Hz tone or to a 500-Hz tone). The physiological basis is not known.

Armus and colleagues (Armus et al., 2006a,b; Mingee and Armus, 2009) trained paramecia to go to a lighted region. The bath is split into two compartments, one in the dark, the other one in light. Initially, *Paramecium* spends more time in the dark compartment, because of photophobia. Training consists in electrically stimulating the cell when it enters the compartment of the cathode. After training, *Paramecium* spends more time than before in the cathodal half, which now only differs by its lighting. However, if stimulation is triggered in the anodal half, then after training *Paramecium* spends less time in that half. Therefore, the phenomenon does not seem to be based on an association between the electrical stimulus and the light stimulus. A plausible interpretation is the following. As is known from studies of galvanotaxis (Ludloff, 1895; Dale, 1901), electrical stimulation makes *Paramecium* move toward the cathode. Stimulation in the lighted cathodal compartment then makes *Paramecium* spend more time in light, which results in adaptation of the photophobic behavior. Thus, after training, *Paramecium* spends more time than before in the lighted compartment. This interpretation is supported by the observation that the "trained" behavior only occurs when the cathodal compartment is lighted during training (Alipour et al., 2018), and by the absence of retention (Mingee, 2013).

In summary, although the existing literature is complex, there is clear evidence of behavioral plasticity in *Paramecium*. Some can be categorized as adaptation, and there is at least one documented case of learning (Hennessey et al., 1979), understood as a persistent stimulus-specific change in behavior.

The Motor System of *Paramecium*

How *Paramecium* swims

In the absence of any stimulus, *Paramecium* swims in spirals. *Paramecium* is covered by several thousand cilia (Fig. 8A; ~4000 cilia in *Paramecium tetraurelia*; Aubusson-Fleury et al., 2015; for precise counts and spatial pattern, see Iftode et al., 1989), each ~10 μm long and 0.2 μm thick (Eckert and Naitoh, 1970), similar to other motile cilia of eukaryotes, including mammals (Ishikawa, 2017). In forward swimming, each cilium beats at 10–20 Hz (Fig. 8B), with a power stroke toward the right and rear on the visible surface (Fig. 8C). Thus, on the hidden surface (further from the observer), cilia beat toward the left and rear. This results in a forward movement with a rotation around the longitudinal axis, as in unscrewing (over to the left; Fig. 8D). The typical velocity is ~1 mm/s (Machemer et al., 1991).

The spiral is wider than the cell's width, as first described by Jennings (1901) and later by Bullington (1930). A possible reason is that cilia in the oral groove beat in a specific direction, toward the mouth, which counters the movement produced by the other cilia. A recent study has




Figure 8. Spiral swimming. **A**, Organization of ciliary basal bodies on the oral (ventral) and aboral (dorsal) side (from Iftode et al., 1989, with permission). **B**, Ciliary beat cycle: power stroke (or effective stroke) and recovery stroke (Omori et al., 2020). **C**, Water currents produced by cilia for different orientations of *Paramecium* (Jennings, 1904). In the oral groove, currents are oriented toward the mouth. **D**, Metachronal waves represented by parallel lines, progressing transversally, with cilia's power stroke oriented toward the right and rear (from Machemer, 1972, with permission). Cilia on parallel lines are at the same phase of the beat cycle. The curved arrow shows the direction of movement.

shown indeed that properties of oral cilia differ from other cilia (Jung et al., 2014). This may explain why the trajectory describes a wide spiral, with the oral side always facing its axis (Fig. 3A; Párducz, 1967).

Properties of spiral swimming can vary, in particular its speed and width. *Paramecium* can also swim backward, with an effective stroke toward the front and slightly to the right. Thus, in backward swimming, the movement is not the symmetrical of forward swimming: the cell still rotates in the same direction.

Cilia beating is coordinated over the cell in the form of *metachronal waves*, which progress over the surface at $\sim 1 \mu\text{m/ms}$ (Párducz, 1967; Fig. 8D). These waves encircle the body in spirals (Párducz, 1967; Machemer, 1969). Cilia beat against the direction of the wave, but not at 180° , a pattern called “dextro-antiplectic.” This particular kind of motor coordination is functionally important. A key characteristic of swimming microorganisms is they live at low Reynolds number ($R \approx 0.1$ for *Paramecium*; Purcell, 1977), that is, inertial forces are small compared with viscous forces (as if a human were trying to swim in honey). As a consequence, the swimmer stops as soon as cilia stop beating. Therefore, if cilia beating were synchronized over the entire body, then the swimmer would move forward in regular discontinuous steps. In fact, this can happen in the escape reaction: a strong heat stimulus near the posterior end induces a synchronous power stroke of the cilia (as in the butterfly stroke; Hamel et al., 2011), which results in a transient speed increase immediately

followed by an almost complete stop, before the metachronal pattern is reestablished. If on the contrary cilia beating were completely disorganized (which can happen transiently in the avoiding reaction), then neighboring cilia might beat in inconsistent directions and this is not an efficient way of swimming. In fact, it has been shown that the metachronal pattern optimizes the energetic efficiency of swimming (Gueron and Levit-Gurevich, 1999; Osterman and Vilfan, 2011).

It was once postulated that ciliary coordination might be electrically controlled by the cell, but *Paramecium* is essentially isopotential (Eckert and Naitoh, 1970). Instead, cilia coordination is mediated by hydrodynamic interactions (Machemer, 1972; Guirao and Joanny, 2007) and mechanical coupling through the compliant body (Narematsu et al., 2015), in the absence of any central agency. This illustrates the concept of embodiment in motor neuroscience: part of the problem of efficient coordination is solved not by manipulating body representations, but by direct physical interaction of the body with its immediate environment (Tytell et al., 2011). In the case of microorganisms such as *Paramecium*, the results of this physical interaction can be understood precisely, thanks to an abundant literature on the mechanics of cilia and flagella (Blake and Sleight, 1974; Sartori et al., 2016; Wan, 2018) including mathematical models (Dillon et al., 2007; Yang et al., 2008), as well as on the hydrodynamics of swimming microorganisms (Keller and Wu, 1977; Lauga and Powers, 2009; Jung et al., 2014).




Figure 9. Gravitactic behavior of *Paramecium*. **A**, Upwardly curved trajectories of *Paramecium* in a vertical chamber (from Roberts, 2010, with permission). **B**, Velocity change (corrected for sedimentation) as a function of cell orientation (from Nagel and Machemer, 2000, with permission), open circles correspond to a morphologic mutant. **C**, Avoiding reaction frequency as a function of acceleration in a centrifuge microscope, after 4 h of equilibration (from Nagel and Machemer, 2000, with permission). Triangles indicate cell direction.

How *Paramecium* moves upward

As many other microorganisms (Häder and Hemmersbach, 2018), *Paramecium* tends to aggregate near the water surface, despite the fact that it is slightly heavier than water ($\sim 4\%$), a puzzling phenomenon which has attracted an abundant literature, first described in detail by Jensen in 1893 (Jensen, 1893). When observed in a vertical plane, trajectories are curved upward (Roberts, 2010; Fig. 9A). The earliest explanation, the gravity-buoyancy model, postulates a mismatch between the buoyancy center and the gravity center (Verworn, 1889): this could generate a torque making the body align with gravity. Roberts (Roberts, 1970, 2010) argued that density inhomogeneities are unlikely to be sufficient to account for the observations, and instead proposed a drag-gravity model: as the posterior end is larger than the anterior end, the viscous drag differs and the posterior end falls more rapidly than the anterior end; thus, the cell turns upward. However, Jensen (1893) and later Kuznicki (1968) observed that dead or immobilized cells fall with no preferred orientation, although this is questioned by Roberts (Roberts, 1970). This would discard both passive orientation mechanisms. The propulsion-gravity model (Winet and Jahn, 1974) is a more complex proposition, which links gravitaxis with ciliary beating: sedimentation introduces viscous resistance to beating that is stronger in the up phase of the helicoidal cycle than in the down phase, resulting in velocity-dependent reorientation.

In addition to these hydrodynamic mechanisms, physiological mechanisms have been postulated. It has been observed that *Paramecium* swims slightly faster upwards than downwards, once sedimentation has been subtracted (Machemer et al., 1991; Ooya et al., 1992; Fig. 8B), and the avoiding reaction is triggered more often when it swims backwards than upwards, although this bias tends to disappear after some time (Nagel and Machemer, 2000; Fig. 8C). Although spurious correlations should be ruled out (e.g., cells that swim more slowly may

tend to fall), Machemer and colleagues have proposed that this is because of pressure differences between the top and bottom ends of the cell, which are sensed by mechanoreceptors. As there is a spatial gradient of mechanosensitivity between the front and rear, the transduced current would be hyperpolarizing when the anterior end is upward (increased pressure on the rear end) and depolarizing when the anterior end is downward. In support of this hypothesis, a cell vertically immobilized between two horizontal electrodes can spontaneously turn upward or downward, and small membrane potential changes with the expected sign are observed, although with long latency (on the order of 20 s; Gebauer et al., 1999). These physiologically induced changes in mean velocity and avoiding reaction rate likely represent a small contribution to gravitaxis, compared with the reorientation of the cell (Roberts, 2010), but it is conceivable that reorientation itself occurs by physiological modulation of velocity within the helicoidal cycle (Mogami and Baba, 1998).

How *Paramecium* turns

In the avoiding reaction, *Paramecium* swims backward (if the reaction is strong) then turns before it swims forward again. Backward swimming occurs because cilia orient, with the power stroke oriented toward the anterior end instead of the posterior end, but how can *Paramecium* turn? Turning requires some inhomogeneity in the ciliary beating pattern.

First, anterior and posterior cilia do not revert synchronously during the avoiding reaction (Fig. 10A; Párducz, 1967; Machemer, 1969). When the avoiding reaction is initiated, all cilia simultaneously strike forward, which moves the cell backward (2). The beating pattern then progressively reorganizes into the metachronal pattern as the cell swims backward (3–5). Reorientation of the cell starts when the anterior end reverts to the forward metachronal pattern (6–8). Thus, anterior and posterior ends show different metachronal patterns, respectively, of forward and backward swimming.




Figure 10. Details of the avoiding reaction. **A**, Reorganization of the ciliary beating pattern during the avoiding reaction (after Machemer, 1969). **B**, Cross-section of *Paramecium* seen from the anterior end, during forward swimming (**a**, corresponding to step 1) and during reorientation (**b**, corresponding to step 6), according to Jennings (1904). The arrows correspond to the induced movement of the body (opposite to the beating direction).

It is not obvious, however, how this asynchronous pattern would make the cell turn. If the beating pattern were axisymmetric, then the net force produced by either group of cilia (anterior or posterior) should be directed along the main axis. Jennings claims that cilia in the oral groove may also reverse, i.e., they expel fluid from the mouth (Jennings, 1899a; Fig. 8C). This could make *Paramecium* turn toward its aboral (dorsal) side, as observed, but Jennings and Jamieson observed that when *Paramecium* was cut in two pieces below the oral groove, both pieces could turn in a similar way (Jennings and Jamieson, 1902). Jennings also mentions that cilia of the anterior end do not all strike to the right; instead, they strike toward the oral groove (Jennings, 1904; Fig. 10B). As a result, the cell turns toward the aboral side. This is supported by more recent observations in a flattened ciliary sheet from *Paramecium* (Noguchi et al., 1991). Thus, turning likely results from inhomogeneity in the response of different groups of cilia, but details are still lacking.

The Physiologic Basis of Behavior

The action potential

When *Paramecium* touches an obstacle, mechanosensitive channels open, depolarize the membrane and trigger a calcium-based action potential (Eckert, 1972). The entry of calcium then triggers the reorientation of cilia, so that *Paramecium* swims backwards. Then calcium is buffered or pumped out (Plattner et al., 2006; Yano et al., 2015) and the cilia reorient in the original direction.

Historically, *Paramecium* electrophysiology has been studied by placing the cell in a tiny droplet, letting the fluid evaporate until the cell is captured by surface tension, then inserting sharp microelectrodes and covering with extracellular medium (Naitoh and Eckert, 1972). A recent method immobilizes the cell by suction against a filter (Kulkarni et al., 2020).

Paramecium is an isopotential cell, as demonstrated with two-electrode measurements (Eckert and Naitoh, 1970; Dunlap, 1977; Satow and Kung, 1979), which is a

particularly favorable situation for electrophysiological modeling. This can be sensed from an estimation of the electrotonic length $\lambda = \sqrt{\frac{d r_m}{4 R_i}}$, where d is diameter, r_m is specific membrane resistance, and R_i is intracellular resistivity. For *P. tetraurelia*, cell width is $34 \mu\text{m}$ (Nagel and Machemer, 2000), with $r_m = 64,000 \Omega \cdot \text{cm}^2$ (Dunlap, 1977) and $R_i = 500 \Omega \cdot \text{cm}$ (conservative estimate based on the ~ 5 lower intracellular ionic content compared with mammals), we obtain $\lambda \approx 330 \text{ mm}$, much larger than the cell's length ($115 \mu\text{m}$). In the same way, for a 200 nm wide cilium, we obtain $\lambda \approx 260 \mu\text{m}$, much larger than its $10\text{-}\mu\text{m}$ length.

Paramecium has a resting potential of about -30 to -20 mV (more depolarized than neurons), depending on the extracellular medium (Naitoh and Eckert, 1968a). *P. caudatum* has a capacitance of $\sim 700 \text{ pF}$, half of which is due to the cilia (Machemer and Ogura, 1979), and a resistance of $\sim 65 \text{ M}\Omega$ (again depending on the extracellular medium), giving a membrane time constant of $\sim 45 \text{ ms}$. *P. tetraurelia*, which is smaller, has a resistance of $\sim 45\text{--}60 \text{ M}\Omega$ (Satow and Kung, 1976; Nagel and Machemer, 2000). Capacitance is not documented, but a simple scaling based on membrane area (Machemer and Ogura, 1979; Nagel and Machemer, 2000) gives $\sim 300 \text{ pF}$. These values are consistent with the surfacic capacitance of other cells including neurons ($\sim 1 \mu\text{F}/\text{cm}^2$).

The negative resting potential is due to a high intracellular concentration of K^+ ions ($18\text{--}34 \text{ mM}$ depending on studies; Naitoh and Eckert, 1969, 1973; Hansma, 1974; Oertel et al., 1978; Ogura and Machemer, 1980; Oka et al., 1986), much larger than the extracellular concentration (typically $\sim 1\text{--}4 \text{ mM}$ KCl in experiments; Machemer and Ogura, 1979; Machemer, 1998). Conversely, there is a low intracellular concentration of Ca^{2+} ions at rest ($50\text{--}200 \text{ nM}$; Klauke and Plattner, 1997; Iwadate, 2003), while the extracellular concentration is orders of magnitude higher (the minimal viable concentration is $\sim 0.1 \text{ mM}$; Naitoh and Eckert, 1968a). At rest, the membrane is permeable to many cations (Naitoh and Eckert, 1968a). Thus, the ionic content of the cytosol is approximately five times lower than metazoan cells (where intracellular K^+ concentration is $\sim 150 \text{ mM}$). One reason might be that the extracellular medium (fresh water) typically has very low ionic content, so that the cytosolic ions exert a large osmotic pressure on the membrane. In *Paramecium* and other protozoa, this osmotic imbalance is regulated by specialized organelles, the contractile vacuoles, which expel water that invades the cell by osmosis (Allen and Naitoh, 2002).

When *Paramecium* is mechanically stimulated on the front, or a current is injected, the membrane is depolarized (Fig. 11). If the stimulus is strong enough, this depolarization triggers a graded action potential, with a stimulus-dependent amplitude (all-or-none spikes can occur if extracellular calcium is partially replaced by barium; Naitoh and Eckert, 1968b). This action potential is due to calcium voltage-gated channels distributed over the cilia and delayed rectifier potassium channels located in the somatic membrane; this can be demonstrated by removing the cilia with ethanol and shaking (Machemer and Ogura, 1979). In response to a voltage step, the cell produces a current consisting of two phases: a fast inward current




Figure 11. Membrane potential responses to mechanical stimulation with a glass stylus on the front (**A**) and on the rear (**B**; from Naitoh and Eckert, 1969, with permission; top traces: voltage command to the piezoelectric actuator).

carried by Ca^{2+} , and a slower outward current carried by K^+ (Fig. 12), which have been separated using behavioral mutants (Saimi and Kung, 1987).

The Ca^{2+} current inactivates quickly (a few milliseconds) by a calcium-dependent mechanism: the entry of calcium (rather than voltage) inactivates the channels (Eckert and Brehm, 1979; Brehm et al., 1980; Eckert and Chad, 1984), there is also a slower voltage-gated inactivation acting over tens of seconds (Hennessey and Kung, 1985). Recovery from inactivation takes a few tens to a hundred of milliseconds (Naitoh et al., 1972; Brehm et al., 1980). This is a common form of inactivation of calcium channels in neurons, which has been discovered first in *Paramecium* (Brehm and Eckert, 1978a). It involves calmodulin, a highly conserved calcium sensor that is found across all species (Ben-Johny and Yue, 2014). Genetically, three related α units have been identified

in the cilia (Lodh et al., 2016), which are similar to the Ca_v1 mammalian family (L-type).

The voltage-gated K^+ current is a delayed rectifier current, which activates quickly (a few milliseconds; Eckert and Brehm, 1979) and inactivates slowly (a few seconds; Satow and Kung, 1980; Saimi et al., 1983). There is also a calcium-activated current, which develops more slowly (Satow and Kung, 1980). It is involved in repolarization after sustained stimulation (Saimi et al., 1983). Genetic analysis has identified in particular SK channels located in the cilia (Valentine et al., 2012; Yano et al., 2013). All these channels have homologs in mammalian neurons.

Currents selective for Na^+ (Saimi, 1986; Saimi and Ling, 1990) and Mg^{2+} (Preston, 1990, 1998) have also been identified.




Figure 12. Action potential currents in *P. caudatum* (from Brehm and Eckert, 1978a, with permission). **A**, Current recorded in voltage-clamp with different depolarization steps above resting potential. The first and last peaks are capacitive transients. The early negative transient is mediated by calcium; the late positive current is mediated by potassium. **B**, Early and late currents versus membrane potential (relative to rest).




Figure 13. Electromotor coupling. **A**, Calcium uncaging in cilia (circle) triggers local ciliary reversal (from Iwadate, 2003, with permission). **B**, Beating frequency (filled: positive; open: negative) as a function of membrane potential in voltage clamp (from Machemer, 1976, with permission). Reversal is indicated by dots. **C**, Beating frequency versus pCa ($-\log_{10} [\text{Ca}^{2+}]$) in a permeabilized cell (from Nakaoka et al., 1984, with permission). Squares and circles are two different permeabilized models, circles being more physiological. Cilia reverse at the minimum beating frequency. **D**, Cell length versus pCa in a permeabilized cell (from Nakaoka et al., 1984, with permission).

Electromotor coupling

Cilia are highly conserved structures. Motile cilia are found not only in swimming microorganisms but also in multicellular organisms including humans, where they are involved in moving fluids, for example the cerebrospinal fluid (Faubel et al., 2016). The cilium contains a cytoskeleton called the axoneme, composed of nine microtubule doublets arranged in a ring around a central pair of microtubules (Porter and Sale, 2000). Dynein motors make microtubule doublets slide on each other, which bends the cilium (Walczak and Nelson, 1994). The activity of these motors is regulated by second messengers, in particular calcium and cyclic nucleotides (cAMP and cGMP).

In the absence of stimulation, cilia beat at ~ 10 – 20 Hz with a power stroke toward the right and rear of the cell. Ciliary reversal is triggered by calcium entering the cell through voltage-gated calcium channels distributed over the cilia: this has been shown by direct intracellular exposure of cilia to $[\text{Ca}]_i > 1 \mu\text{M}$ (Naitoh and Kaneko, 1972; by making the membrane permeable with a detergent) and calcium uncaging in the cilia (Iwadate, 2003; Fig. 13A). In *P. tetraurelia*, Oertel et al. (1977) estimated that the largest calcium current triggered by a short voltage step increases the ciliary calcium concentration by $\sim 20 \mu\text{M}$, which then decays because of buffering and pumping.

Thus, stronger current pulses trigger larger and faster spikes, resulting in larger calcium increase and therefore longer reversed beating (Machemer and Eckert, 1973). Cyclic nucleotides (cAMP and cGMP) antagonize ciliary reorientation, i.e., an increased cAMP concentration raises the voltage threshold for ciliary reorientation (Nakaoka and Machemer, 1990).

Beating frequency also changes with voltage (Machemer and Eckert, 1975; Fig. 13B). In particular, cilia beat faster when the command voltage is increased above resting potential. Early work in permeabilized cells indicated that calcium controls ciliary reorientation but not beating frequency (Naitoh and Kaneko, 1972), but this was later argued to be because of unphysiological aspects of the permeable models (Nakaoka et al., 1984). In more physiological permeabilized cells, an increase in ciliary calcium concentration above the resting level triggers ciliary reorientation and an increase in beating frequency, matching the effect of depolarization (Fig. 13C). Note that swimming velocity does not exactly follow this frequency increase, because it also depends on the coordination of cilia, which is disrupted when cilia reorient. For small depolarizations, not all cilia reorient (Machemer and Eckert, 1975), which may explain how the organism turns. The cell also contracts when calcium concentration increases (Fig. 13D).




Figure 14. Mechanosensitive responses measured as a function of stimulation position (A: anterior; P: posterior) in a *P. aurelia* mutant with no action potential (from Satow et al., 1983, with permission). Below, K^+ currents are blocked with TEA.

Mechanotransduction

Mechanoreception in *Paramecium* and other ciliates has been the object of several reviews (Naitoh, 1984; Machemer, 1985; Machemer and Deitmer, 1985; Deitmer, 1992). Touching the anterior part of *Paramecium* results in membrane depolarization, while touching the posterior part results in membrane hyperpolarization (Naitoh and Eckert, 1969). Six genes of the Piezo family (Coste et al., 2010) have been identified in the genome, similar to those mediating mechanosensitivity in many species including mammals. Ionic channels mediating mechanosensitivity are located on the basal membrane; a deciliated cell is still mechanosensitive (Ogura and Machemer, 1980). Cilia are not directly involved in transduction, but they are involved in the mechanical transfer and filtering of stimuli. For example, the tail has long immobile cilia, which may enhance mechanical sensitivity (in particular to current flows) by spreading the mechanical stimulation over a larger membrane area (Machemer and Machemer-Röhnisch, 1984; Machemer-Röhnisch and Machemer, 1984).

Mechanosensitive currents change gradually from the posterior to anterior part because of overlapping spatial gradients of K^+ and Ca^{2+} mechanosensitive channels (Ogura and Machemer, 1980; Satow et al., 1983). Currents in the posterior part are mostly carried by fast K^+ currents (time constant in the 10-ms range), whereas currents in the anterior part are carried mainly by Ca^{2+} (and possibly other divalent cations; Satow et al., 1983) and are slower (in the 20-ms range; Fig. 14). In the middle region, a mixed current can be observed, with an outward then inward component, indicative of a superposition of two ionic channel responses. There are also graded changes in mechanosensitivity along the oral-aboral (dorsoventral) axis.

Mechanical responses have been studied mainly by deflecting a thin glass stylus onto the membrane with a piezo-electric actuator. In another ciliate, *Stylonichia*, the transduced current increases linearly with the deflection

amplitude of the probe; the resulting potential may saturate for strong stimuli, near the reversal potential. Faster deflections reduce response latency without changing the amplitude. When a mutant with defective ciliary calcium channels is mechanically stimulated, ciliary reversal is observed only at the site of stimulation on the anterior membrane (Takahashi and Naitoh, 1978): this indicates that mechanical stimulation only recruits local mechanoreceptors (these can trigger ciliary reversal because the transduced current is carried by calcium). Stimulations integrate both spatially and temporally, with no sign of refractoriness. Finally, the duration of the deflection has no effect on the response. The termination of the current may be due to an adaptation process and/or to the membrane passively retreating from the probe.

Thus, the integration of mechanical stimuli is analog to synaptic integration in a neuron: stimulation at a site produces a transient current through ionic channels, transduced currents are integrated both spatially and temporally, and the resulting potential response may trigger an action potential if it is large enough.

Electrophysiology of the escape reaction

When *Paramecium* is mechanically stimulated on the rear, the membrane is hyperpolarized (Fig. 14), which then triggers the escape reaction: swimming velocity increases. The electrophysiological response is shaped by several hyperpolarization-activated channels.

A fast inward rectifier K^+ current is activated by hyperpolarization, most strongly below E_K (Oertel et al., 1978), and partially inactivates over a few hundred milliseconds (Preston et al., 1990). Thus, the activation voltage depends on extracellular K^+ concentration. If that concentration is very low, a regenerative hyperpolarization can be obtained (Satow and Kung, 1977). This current is similar to inward rectifiers found in other species (Doupnik et al., 1995). Another K^+ current activates with calcium (Preston et al., 1990).

A calcium current activates with hyperpolarization, and the entry of calcium then mediates an increase in beating frequency (Nakaoka and Iwatsuki, 1992; Preston et al., 1992a,b). This current actually activates within a few tens of ms, and decays more slowly through calcium-dependent inactivation (Preston et al., 1992b). It actually consists of two pharmacologically distinct currents located in the somatic membrane, one of which is sustained (Nakaoka and Iwatsuki, 1992). The magnitude of the hyperpolarization-activated calcium current is directly related to the increase in beating frequency, and blocking this current also blocks the frequency increase (Nakaoka and Iwatsuki, 1992). Thus, it appears that beating frequency is controlled by calcium concentration in the somatic membrane, presumably at the base of cilia, in line with studies in other ciliary systems (Tamm, 1994). This contradicts several earlier hypotheses: that beating frequency increases with a hyperpolarization-induced decrease in ciliary calcium concentration (Machemer, 1974), by an iontophoretic mechanism in the cilia (Brehm and Eckert, 1978b), or by regulation by cyclic nucleotides (Satir et al., 1993; Pech, 1995). The latter hypothesis did receive some support (Bonini et al., 1986; Hamasaki et al., 1991; Schultz et al., 1992), as raising cAMP concentration makes cilia beat faster, but it has been disproven by the demonstration that, when the cell's voltage is maintained constant, injecting high levels of cAMP has no effect on beating frequency (Hennessey et al., 1985; Nakaoka and Machemer, 1990). Thus, the effect of cAMP was likely indirectly due to the hyperpolarization induced by cAMP (Bonini et al., 1986).

Discussion

Gomez-Marin and Ghazanfar described three fundamental biological principles of behavior that highlight the need for integrated approaches in neuroscience: materiality, agency and historicity (Gomez-Marin and Ghazanfar, 2019). Materiality refers to the role of body and environment in behavior. That is, the relation between neural activity and behavior is not just a case of correspondence (the coding view; Brette, 2019), but also of physical causality: spikes cause particular physiological effects, the results of which are determined by the structure of the body and the environment it interacts with (Tytell et al., 2011). For example, in *Paramecium*, cilia are under electrical control but efficient motor coordination is partly achieved by hydrodynamic interactions between cilia. Agency refers to the fact that action and perception form a closed loop in the service of goals, rather than a linear stimulus-reaction chain. For example, when *Paramecium* meets an obstacle, the mechanosensory signal is determined not just by the object but also by the motor response that the signal causes, in a closed loop. This concept is increasingly appreciated in cognitive science, philosophy of mind and more recently neuroscience (Maturana and Varela, 1973; Powers, 1973; Gibson, 1979; Brooks, 1991; Bickhard and Terveen, 1996; Hurley, 2001; O'Regan and Noë, 2001; Ahissar and Assa, 2016; Pezzulo and Cisek, 2016; Brette, 2019). Historicity refers to the fact that organisms are individuals: variability is best

understood not as a noisy deviation around a norm but as a functional result of their history. In *Paramecium*, this is evident for example in long-term adaptation to new environments, but also in some exploratory behaviors (such as tube escape).

Addressing these three principles requires studying an entire organism in an environment, rather than isolated subsystems. Computational neuroethology is a subfield of computational neuroscience focusing on the modeling of autonomous behavior (Beer, 1990), which has been investigated in particular artificial organisms (Beer and Gallagher, 1992) and robots (Webb, 2001). More recently, integrated models of *C. elegans* (Izquierdo and Beer, 2016; Cohen and Denham, 2019), *Hydra* (Dupre and Yuste, 2017; Wang et al., 2020), and jellyfish *Aurelia aurita* (Pallasdies et al., 2019) have been developed. Those model organisms have certain obvious advantages over *Paramecium*, namely the fact that they have a nervous system, with interacting neurons. But *Paramecium* has great assets for integrative modeling of a whole organism, relating physiology and behavior.

First, there is an extensive literature on *Paramecium*, covering detailed aspects of behavior, genetics, electrophysiology, cell and molecular biology. This literature has highlighted similarities with metazoans, in particular nervous systems, not only functionally but also at genetic and molecular levels (Connolly and Kerkut, 1983; Hinrichsen and Schultz, 1988; Beisson et al., 2010b; Yano et al., 2015; Plattner and Verkhatsky, 2018), with similar ionic channels, pumps, signaling pathways (calcium, cyclic nucleotides), sensory receptors, even GABA receptors. Second, it benefits from various tools, for example genetic tools such as RNA interference (Galvani and Sperling, 2002), proteomics (Yano et al., 2013), and whole genome sequencing (Aury et al., 2006; Arnaiz et al., 2010; Arnaiz and Sperling, 2011; McGrath et al., 2014), behavioral monitoring (Drescher et al., 2009), immobilization for electrophysiology (Kulkarni et al., 2020). Finally, it is easy to culture (Beisson et al., 2010a), it has a rich behavior that can be easily observed and quantified, and it allows intracellular electrophysiology in an intact organism, while monitoring its behavior.

As outlined in this review, a number of neuroscientific themes can be addressed and revisited in *Paramecium*. One such theme is the physiological basis of behavior and the relation between perception and action. A classical way to frame this problem is what Susan Hurley called the "classical sandwich" (Hurley, 2001): at the periphery, a perceptual system transforms stimuli into representations and a motor system transforms motor representations into actions; sandwiched between perception and action, cognition manipulates representations. As noted by many authors, the classical sandwich has many conceptual issues (Gibson, 1979; Brooks, 1991; O'Regan and Noë, 2001; Pezzulo and Cisek, 2016; Brette, 2019). Cisek, for example, noted that it leaves the cartesian dualistic view essentially unchanged, replacing the non-physical mind by "cognition" while preserving problematic homuncular concepts (Cisek, 1999). Another key issue is that framing neural activity as responses to stimuli denies any

autonomy to the organism. As Dewey pointed out (Dewey, 1896), sensory signals are as much causes as consequences of the organism's activity, because the relation between organism and environment is one of coupling rather than command. By its relative simplicity, *Paramecium* offers the possibility to study the physiological basis of autonomous behavior outside the frame of the classical sandwich, because it seems feasible to develop closed-loop dynamical systems models of the organism behaving autonomously in an environment, where spikes are not symbols but actions (Brette, 2019).

Motor control is a related theme where *Paramecium* may provide some insights. Embodiment is the idea that the body can contribute to motor control, beyond the mere execution of central commands. In *Paramecium*, cilia beat in a coordinated fashion in the absence of central command, by hydrodynamic and mechanical interactions, yielding efficient swimming. More generally, the mechanical properties of its body contribute to its navigation abilities, as when navigating in confined spaces, and more generally when interacting with surfaces. As it turns out, *Paramecium* appears to use neither of the two mainstream concepts in motor control, planning (or feedforward control; Wolpert and Ghahramani, 2000) and feedback control (Powers, 1973). Instead, it uses another way to produce goal-directed behavior, based on the Darwinian insight that random exploration and elimination of unsuccessful attempts can produce adapted behavior. This simple principle allows *Paramecium* to perform non-trivial sensorimotor tasks with a single "neuron".

While the physiological basis of learning is classically framed in terms of stimulus association, *Paramecium* may offer the possibility to address it in a more ecological context, that is, autonomous learning of a task. Tube escape might be such a task; however, the learning capabilities of *Paramecium* are still somewhat unclear.

As *Paramecium* is both an organism and a cell, it also offers the opportunity to investigate the relation between cellular plasticity and behavioral plasticity. Intrinsic plasticity is well documented in neurons (Daoudal and Debanne, 2003), but it remains very challenging to understand its functional implications for the organism. Thus, it is classically interpreted in terms of homeostasis of cellular properties (e.g., firing rate), or of abstract information-theoretical properties. In *Paramecium*, since the relation between cellular physiology and behavior is more direct than in brains, it becomes possible to relate intrinsic plasticity with behavioral plasticity. For example, ionic channel properties adapt to changes in temperature in such a way as to preserve normal motor behavior (Nakaoka et al., 1982; Martinac and Machemer, 1984). Similarly, developmental plasticity can be addressed by investigating the physiological and behavioral changes after fission (Iftode et al., 1989). Indeed, as ionic channels are spatially organized (for example depolarizing mechanoreceptors at the front), this organization is disrupted by fission and must be somehow restored.

This opens exciting perspectives for the development of integrated models of a "swimming neuron".

References

- Ahissar E, Assa E (2016) Perception as a closed-loop convergence process. *Elife* 5:e12830.
- Alipour A, Dorvash M, Yeganeh Y, Hatam G (2018) *Paramecium* learning: new insights. *J Protozool Res* 28:22–32.
- Allen RD, Naitoh Y (2002) Osmoregulation and contractile vacuoles of protozoa. *Int Rev Cytol* 215:351–394.
- Applewhite PB (1979) Learning in protozoa. In: *Biochemistry and physiology of protozoa*, pp 341–355. Amsterdam: Elsevier.
- Applewhite PB, Gardner FT (1973) Tube-escape behavior of *paramecia*. *Behav Biol* 9:245–250.
- Armus HL, Montgomery AR, Gurney RL (2006a) Discrimination learning and extinction in *paramecia* (*P. caudatum*). *Psychol Rep* 98:705–711.
- Armus HL, Montgomery AR, Jellison JL (2006b) Discrimination learning in *paramecia* (*P. caudatum*). *Psychol Rec* 56:489–498.
- Arnaiz O, Sperling L (2011) *Paramecium* DB in 2011: new tools and new data for functional and comparative genomics of the model ciliate *Paramecium tetraurelia*. *Nucleic Acids Res* 39:D632–D636.
- Arnaiz O, Gout JF, Bétermier M, Bouhouche K, Cohen J, Duret L, Kapusta A, Meyer E, Sperling L (2010) Gene expression in a paleopolyploid: a transcriptome resource for the ciliate *Paramecium tetraurelia*. *BMC Genomics* 11:547.
- Aubusson-Fleury A, Cohen J, Lemullois M (2015) Ciliary heterogeneity within a single cell: the *Paramecium* model. *Methods Cell Biol* 127:457–485.
- Aury JM, Jaillon O, Duret L, Noel B, Jubin C, Porcel BM, Ségurens B, Daubin V, Anthouard V, Aiach N, Arnaiz O, Billaut A, Beisson J, Blanc I, Bouhouche K, Câmara F, Duharcourt S, Guigo R, Gogendeau D, Katinka M, et al. (2006) Global trends of whole-genome duplications revealed by the ciliate *Paramecium tetraurelia*. *Nature* 444:171–178.
- Beer RD (1990) Intelligence as adaptive behaviour: an experiment in computational neuroethology, Ed 1. Boston: Academic Press.
- Beer RD, Gallagher JC (1992) Evolving dynamical neural networks for adaptive behavior. *Adapt Behav* 1:91–122.
- Beisson J, Bétermier M, Bré M-H, Cohen J, Duharcourt S, Duret L, Kung C, Malinsky S, Meyer E, Preer JR, Sperling L (2010a) Mass culture of *Paramecium tetraurelia*. *Cold Spring Harb Protoc* 2010: pdb.prot5362.
- Beisson J, Bétermier M, Bré M-H, Cohen J, Duharcourt S, Duret L, Kung C, Malinsky S, Meyer E, Preer JR, Sperling L (2010b) *Paramecium tetraurelia*: the renaissance of an early unicellular model. *Cold Spring Harb Protoc* 2010: pdb.emo140.
- Ben-Johny M, Yue DT (2014) Calmodulin regulation (calmodulation) of voltage-gated calcium channels. *J Gen Physiol* 143:679–692.
- Bennett DA, Francis D (1972) Learning in stentor. *J Protozool* 19:484–487.
- Berg HC (1975) Bacterial behaviour. *Nature* 254:389–392.
- Berg HC (2008) *E. coli* in motion. New York: Springer Science and Business Media.
- Berg HC, Purcell EM (1977) Physics of chemoreception. *Biophys J* 20:193–219.
- Berke AP, Turner L, Berg HC, Lauga E (2008) Hydrodynamic attraction of swimming microorganisms by surfaces. *Phys Rev Lett* 101: e038102.
- Bickhard MH, Terveen L (1996) Foundational issues in artificial intelligence and cognitive science: impasse and solution. San Diego: Elsevier.
- Blake JR, Sleight MA (1974) Mechanics of ciliary locomotion. *Biol Rev Camb Philos Soc* 49:85–125.
- Bonini NM, Gustin MC, Nelson DL (1986) Regulation of ciliary motility by membrane potential in *Paramecium*: a role for cyclic AMP. *Cell Motil* 6:256–272.
- Brehm P, Eckert R (1978a) Calcium entry leads to inactivation of calcium channel in *Paramecium*. *Science* 202:1203–1206.
- Brehm P, Eckert R (1978b) An electrophysiological study of the regulation of ciliary beating frequency in *Paramecium*. *J Physiol* 283:557–568.

- Brehm P, Eckert R, Tillotson D (1980) Calcium-mediated inactivation of calcium current in *Paramecium*. *J Physiol* 306:193–203.
- Bretherton FP, Rothschild MA (1961) Rheotaxis of spermatozoa. *Proc R Soc Lond B Biol Sci* 153:490–502.
- Brette R (2019) Is coding a relevant metaphor for the brain? *Behav Brain Sci* 42:e215.
- Brooks RA (1991) Intelligence without representation. *Artif Intell* 47:139–159.
- Bucci G, Ramoino P, Diaspro A, Usai C (2005) A role for GABAA receptors in the modulation of *Paramecium* swimming behavior. *Neurosci Lett* 386:179–183.
- Bullington WE (1930) A further study of spiraling in the ciliate *Paramecium*, with a note on morphology and taxonomy. *J Exp Zool* 56:423–449.
- Celani A, Vergassola M (2010) Bacterial strategies for chemotaxis response. *Proc Natl Acad Sci USA* 107:1391–1396.
- Cisek P (1999) Beyond the computer metaphor: behaviour as interaction. *J Conscious Stud* 6:125–142.
- Cohen N, Sanders T (2014) Nematode locomotion: dissecting the neuronal–environmental loop. *Curr Opin Neurobiol* 25:99–106.
- Cohen N, Denham JE (2019) Whole animal modeling: piecing together nematode locomotion. *Curr Opin Syst Biol* 13:150–160.
- Connolly JG, Kerkut GA (1983) Ion regulation and membrane potential in *Tetrahymena* and *Paramecium*. *Comp Biochem Physiol A Physiol* 76:1–16.
- Coste B, Mathur J, Schmidt M, Earley TJ, Ranade S, Petrus MJ, Dubin AE, Patapoutian A (2010) Piezo1 and Piezo2 are essential components of distinct mechanically-activated cation channels. *Science* 330:55–60.
- Dale HH (1901) Galvanotaxis and chemotaxis of ciliate infusoria. *J Physiol* 26:291–361.
- Daoudal G, Debanne D (2003) Long-term plasticity of intrinsic excitability: learning rules and mechanisms. *Learn Mem* 10:456–465.
- Deitmer JW (1992) Mechanosensory transduction in ciliates (protozoa). In: *Comparative aspects of mechanoreceptor systems. Advances in comparative and environmental physiology* (Ito F, ed), pp 39–54. Berlin; Heidelberg: Springer Berlin Heidelberg.
- Dewey J (1896) The reflex arc concept in psychology. *Psychol Rev* 3:357–370.
- Dillon RH, Fauci LJ, Omoto C, Yang X (2007) Fluid dynamic models of flagellar and ciliary beating. *Ann NY Acad Sci* 1101:494–505.
- Doupnik CA, Davidson N, Lester HA (1995) The inward rectifier potassium channel family. *Curr Opin Neurobiol* 5:268–277.
- Drescher K, Leptos KC, Goldstein RE (2009) How to track protists in three dimensions. *Rev Sci Instrum* 80:e014301.
- Dryl S (1973) Chemotaxis in ciliate protozoa. In: *Behaviour of microorganisms*, pp 16–30. New York: Springer.
- Dunlap K (1977) Localization of calcium channels in *Paramecium caudatum*. *J Physiol* 271:119–133.
- Dupre C, Yuste R (2017) Non-overlapping neural networks in *Hydra vulgaris*. *Curr Biol* 27:1085–1097.
- Eckert R (1972) Bioelectric control of ciliary activity. *Science* 176:473–481.
- Eckert R, Naitoh Y (1970) Passive electrical properties of *Paramecium* and problems of ciliary coordination. *J Gen Physiol* 55:467–483.
- Eckert R, Brehm P (1979) Ionic mechanisms of excitation in *Paramecium*. *Annu Rev Biophys Bioeng* 8:353–383.
- Eckert R, Chad JE (1984) Inactivation of Ca channels. *Prog Biophys Mol Biol* 44:215–267.
- Eckert R, Sibaoka T (1968) The flash-triggering action potential of the luminescent dinoflagellate noctiluca. *J Gen Physiol* 52:258–282.
- Faubel R, Westendorf C, Bodenschatz E, Eichele G (2016) Cilia-based flow network in the brain ventricles. *Science* 353:176–178.
- Febvre-Chevalier C, Bilbaut A, Bone Q, Febvre J (1986) Sodium-calcium action potential associated with contraction in the heliozoan *Actinocyrcyne contractilis*. *J Exp Biol* 122:177–192.
- Fokin SI (2010) *Paramecium* genus: biodiversity, some morphological features and the key to the main morphospecies discrimination. *Protistology* 6:227–235.
- Francis JT, Hennessey TM (1995) Chemorepellents in *Paramecium* and *Tetrahymena*. *J Eukaryot Microbiol* 42:78–83.
- French JW (1940) Trial and error learning in *Paramecium*. *J Exp Psychol* 26:609–613.
- Galvani A, Sperling L (2002) RNA interference by feeding in *Paramecium*. *Trends Genet* 18:11–12.
- Gebauer M, Watzke D, Macheimer H (1999) The gravikinetic response of *Paramecium* is based on orientation-dependent mechanotransduction. *Naturwissenschaften* 86:352–356.
- Gelber B (1952) Investigations of the behavior of *Paramecium aurelia*. I. Modification of behavior after training with reinforcement. *J Comp Physiol Psychol* 45:58–65.
- Gelber B (1956) Investigations of the behavior of *Paramecium aurelia*. III. The effect of the presence and absence of light on the occurrence of a response. *J Genet Psychol* 88:31–36.
- Gelber B (1957) Food or training in *Paramecium*? *Science* 126:1340–1341.
- Gelber B (1958) Retention in *Paramecium aurelia*. *J Comp Physiol Psychol* 51:110–115.
- Gelber B (1962a) Acquisition in *Paramecium aurelia* during spaced training. *Psychol Rec* 12:165–177.
- Gelber B (1962b) Reminiscence and the trend of retention in *Paramecium aurelia*. *Psychol Rec* 12:179–192.
- Gershman SJ, Balbi PE, Gallistel CR, Gunawardena J (2021) Reconsidering the evidence for learning in single cells. *Elife* 10:e61907.
- Gibson JJ (1979) *The ecological approach to visual perception*. London: Routledge.
- Gomez-Marin A, Ghazanfar AA (2019) The life of behavior. *Neuron* 104:25–36.
- Görtz HD (1988) *Paramecium*. Berlin; Heidelberg: Springer.
- Gueron S, Levit-Gurevich K (1999) Energetic considerations of ciliary beating and the advantage of metachronal coordination. *Proc Natl Acad Sci USA* 96:12240–12245.
- Guirao B, Joanny JF (2007) Spontaneous creation of macroscopic flow and metachronal waves in an array of cilia. *Biophys J* 92:1900–1917.
- Häder D-P, Hemmersbach R (2018) Gravitaxis in flagellates and ciliates. In: *Gravitational biology I: gravity sensing and graviorientation in microorganisms and plants*, SpringerBriefs in space life sciences (Braun M, Böhmer M, Häder DP, Hemmersbach R, Palme K, eds), pp 27–45. Cham: Springer International Publishing.
- Hamasaki T, Barkalow K, Richmond J, Satir P (1991) cAMP-stimulated phosphorylation of an axonemal polypeptide that copurifies with the 22S dynein arm regulates microtubule translocation velocity and swimming speed in *Paramecium*. *Proc Natl Acad Sci USA* 88:7918–7922.
- Hamel A, Fisch C, Combettes L, Dupuis-Williams P, Baroud CN (2011) Transitions between three swimming gaits in *Paramecium* escape. *Proc Natl Acad Sci USA* 108:7290–7295.
- Hansma HG (1974) Biochemical studies on the behavioral mutants of *Paramecium aurelia*: ion fluxes and ciliary membrane proteins. PhD Thesis, University of California.
- Hanzel TE, Rucker WB (1972) Trial and error learning in *Paramecium*: a replication. *Behav Biol* 7:873–880.
- Harz H, Hegemann P (1991) Rhodopsin-regulated calcium currents in *Chlamydomonas*. *Nature* 351:489–491.
- Hennessey TM (2005) Responses of the ciliates *Tetrahymena* and *Paramecium* to external ATP and GTP. *Purinergic Signal* 1:101.
- Hennessey TM, Kung C (1985) Slow inactivation of the calcium current of *Paramecium* is dependent on voltage and not internal calcium. *J Physiol* 365:165–179.
- Hennessey TM, Rucker WB, McDiarmid CG (1979) Classical conditioning in *paramecia*. *Anim Learn Behav* 7:417–423.
- Hennessey T, Macheimer H, Nelson DL (1985) Injected cyclic AMP increases ciliary beat frequency in conjunction with membrane hyperpolarization. *Eur J Cell Biol* 36:153–156.
- Hinkle DJ, Wood DC (1994) Is tube-escape learning by protozoa associative learning? *Behav Neurosci* 108:94–99.

- Hinrichsen RD, Schultz JE (1988) *Paramecium*: a model system for the study of excitable cells. *Trends Neurosci* 11:27–32.
- Hinrichsen R, Peters C (2013) A genetic dissection of the photophobic response of *Paramecium tetraurelia*. *Protist* 164:313–322.
- Hodgkin AL (1964) The conduction of the nervous impulse. Springfield: C. C. Thomas.
- Houten JV (1978) Two mechanisms of chemotaxis in *Paramecium*. *J Comp Physiol* 127:167–174.
- Houten JV (1979) Membrane potential changes during chemokinesis in *Paramecium*. *Science* 204:1100–1103.
- Huber JC, Rucker WB, McDiarmid CG (1974) Retention of escape training and activity changes in single *paramecia*. *J Comp Physiol Psychol* 86:258–266.
- Hurlay S (2001) Perception and action: alternative views. *Synthese* 129:3–40.
- Iftode F, Cohen J, Ruiz F, Rueda AT, Chen-Shan L, Adoutte A, Beisson J (1989) Development of surface pattern during division in *Paramecium*. I. Mapping of duplication and reorganization of cortical cytoskeletal structures in the wild type. *Development* 105:191–211.
- Ishikawa T (2017) Axoneme structure from motile cilia. *Cold Spring Harb Perspect Biol* 9:a028076.
- Ishikawa T, Hota M (2006) Interaction of two swimming *paramecia*. *J Exp Biol* 209:4452–4463.
- Iwade Y (2003) Photolysis of caged calcium in cilia induces ciliary reversal in *Paramecium caudatum*. *J Exp Biol* 206:1163–1170.
- Iwatsuki K, Naitoh Y (1982) Photoresponses in colorless *Paramecium*. *Experientia* 38:1453–1454.
- Iwatsuki K, Naitoh Y (1983a) Photobehavior in a colorless *Paramecium*. *BioScience* 33:714–715.
- Iwatsuki K, Naitoh Y (1983b) Behavioral responses in *Paramecium multimicronucleatum* to visible light. *Photochem Photobiol* 37:415–419.
- Iwatsuki K, Hirano T, Kawase M, Chiba H, Michibayashi N, Yamada C, Sumiyoshi N, Yagi K, Mizoguchi T (1996) Thigmotaxis in *Paramecium caudatum* is induced by hydrophobic or polyaniline-coated glass surface to which liver cells from rat adhere with forming multicellular spheroids. *Eur J Protistol* 32:58–61.
- Izquierdo EJ, Beer RD (2016) The whole worm: brain–body–environment models of *C. elegans*. *Curr Opin Neurobiol* 40:23–30.
- Jackson KM, Berger J (1984) Survival of ciliate protozoa under starvation conditions and at low bacterial levels. *Microb Ecol* 10:47–59.
- Jana S, Eddins A, Spoon C, Jung S (2015) Somersault of *Paramecium* in extremely confined environments. *Sci Rep* 5:13148.
- Jennings HS (1897) Studies on reactions to stimuli in unicellular organisms. *J Physiol* 21:258–322.
- Jennings HS (1899a) Studies on reactions to stimuli in unicellular organisms. ii.—the mechanism of the motor reactions of *Paramecium*. *Am J Physiol* 2:311–341.
- Jennings HS (1899b) Studies on reactions to stimuli in unicellular organisms. iv.—laws of chemotaxis in *Paramecium*. *Am J Physiol* 2:355–379.
- Jennings HS (1901) On the significance of the spiral swimming of organisms. *Am Nat* 35:369–378.
- Jennings HS (1904) The behavior of *Paramecium*. Additional features and general relations. *J Comp Neurol Psychol* 14:441–510.
- Jennings HS (1906) Behavior of the lower organisms. New York: The Columbia University Press, The Macmillan Company.
- Jennings HS, Jamieson C (1902) Studies on reactions to stimuli in unicellular organisms. X. The movements and reactions of pieces of ciliate infusoria. *Biol Bull* 3:225–234.
- Jensen DD (1957) Experiments on “learning” in *paramecia*. *Science* 125:191–192.
- Jensen P (1893) Ueber den Geotropismus niederer Organismen. *Pflüger Arch* 53:428–480.
- Jung I, Powers TR, Valles JM (2014) Evidence for two extremes of ciliary motor response in a single swimming microorganism. *Biophys J* 106:106–113.
- Kandel ER (2009) The biology of memory: a forty-year perspective. *J Neurosci* 29:12748–12756.
- Katz MS, Deterline WA (1958) Apparent learning in the *Paramecium*. *J Comp Physiol Psychol* 51:243–247.
- Keller SR, Wu TY (1977) A porous prolate-spheroidal model for ciliated micro-organisms. *J Fluid Mech* 80:259–278.
- Klauke N, Plattner H (1997) Imaging of Ca²⁺ transients induced in *Paramecium* cells by a polyamine secretagogue. *J Cell Sci* 110:975–983.
- Knoll G, Haacke-Bell B, Plattner H (1991) Local trichocyst exocytosis provides an efficient escape mechanism for *Paramecium* cells. *Eur J Protistol* 27:381–385.
- Kollmann M, Løvdok L, Bartholomé K, Timmer J, Sourjik V (2005) Design principles of a bacterial signalling network. *Nature* 438:504.
- Kralj JM, Hochbaum DR, Douglass AD, Cohen AE (2011) Electrical spiking in *Escherichia coli* probed with a fluorescent voltage-indicating protein. *Science* 333:345–348.
- Krenek S, Berendonk TU, Petzoldt T (2011) Thermal performance curves of *Paramecium caudatum*: a model selection approach. *Eur J Protistol* 47:124–137.
- Kulkarni A, Elices I, Escoubet N, Pontani L-L, Prevost AM, Brette R (2020) A simple device to immobilize protists for electrophysiology and microinjection. *J Exp Biol* 223:jeb219253.
- Kung C, Saimi Y (1985) Ca²⁺ channels of *Paramecium*: a multidisciplinary study. In: Current topics in membranes and transport, genes and membranes: transport proteins and receptors (Bronner F, Kleinzeller A, eds), pp 45–66. San Diego: Academic Press.
- Kunita I, Kuroda S, Ohki K, Nakagaki T (2014) Attempts to retreat from a dead-ended long capillary by backward swimming in *Paramecium*. *Front Microbiol* 5:270.
- Kuriu T, Nakaoka Y, Oosawa Y (1996) Cold-sensitive Ca²⁺ influx in *Paramecium*. *J Membr Biol* 154:163–167.
- Kuriu T, Saitow F, Nakaoka Y, Oosawa Y (1998) Calcium current activated by cooling in *Paramecium*. *J Comp Physiol A Neuroethol Sens Neural Behav Physiol* 183:135–141.
- Kuznicki L (1968) Behavior of *Paramecium* in gravity fields. I. Sinking of immobilized specimens. *Acta Protozool* 6:109–117.
- Lauga E, Powers TR (2009) The hydrodynamics of swimming microorganisms. *Rep Prog Phys* 72:e096601.
- Leick V, Helle J (1983) A quantitative assay for ciliate chemotaxis. *Anal Biochem* 135:466–469.
- Levandowsky M, Cheng T, Kehr A, Kim J, Gardner L, Silvern L, Tsang L, Lai G, Chung C, Prakash E (1984) Chemosensory responses to amino acids and certain amines by the ciliate tetrahymena: a flat capillary assay. *Biol Bull* 167:322–330.
- Li GJ, Ardekani AM (2014) Hydrodynamic interaction of microswimmers near a wall. *Phys Rev E* 90:e013010.
- Lodh S, Yano J, Valentine MS, Van Houten JL (2016) Voltage-gated calcium channels of *Paramecium* cilia. *J Exp Biol* 219:3028–3038.
- Ludloff K (1895) Untersuchungen über den Galvanotropismus. *Pflüger Arch* 59:525–554.
- Machemer H (1969) Regulation der Cilienmetachronie bei der “Fluchtreaktion” von *Paramecium**. *J Protozool* 16:764–771.
- Machemer H (1972) Ciliary activity and the origin of metachrony in *Paramecium*: effects of increased viscosity. *J Exp Biol* 57:239–259.
- Machemer H (1974) Frequency and directional responses of cilia to membrane potential changes in *Paramecium*. *J Comp Physiol* 92:293–316.
- Machemer H (1976) Interactions of membrane potential and cations in regulation of ciliary activity in *Paramecium*. *J Exp Biol* 65:427–448.
- Machemer H (1985) Mechanoresponses in protozoa. In: Sensory perception and transduction in asexual organisms, NATO ASI Series (Colombetti G, Lenci F, Song PS, eds), pp 179–209. New York: Springer.
- Machemer H (1989) Cellular behaviour modulated by ions: electrophysiological implications. *J Protozool* 36:463–487.
- Machemer H (1998) Electrophysiology. In: *Paramecium* (Görtz PDHD, ed), pp 185–215. Berlin/Heidelberg: Springer.

- Machemer H, Eckert R (1973) Electrophysiological control of reversed ciliary beating in *Paramecium*. *J Gen Physiol* 61:572–587.
- Machemer DH, Eckert DR (1975) Ciliary frequency and orientational responses to clamped voltage steps in *Paramecium*. *J Comp Physiol* 104:247–260.
- Machemer H, Ogura A (1979) Ionic conductances of membranes in ciliated and deciliated *Paramecium*. *J Physiol* 296:49–60.
- Machemer H, Machemer-Röhnisch S (1984) Mechanical and electric correlates of mechanoreceptor activation of the ciliated tail in *Paramecium*. *J Comp Physiol* 154:273–278.
- Machemer H, Deitmer JW (1985) Mechanoreception in ciliates. In: *Progress in sensory physiology, progress in sensory physiology* (Autrum H, Ottoson D, Perl ER, Schmidt RF, Shimazu H, Willis WD, eds), pp 81–118. Berlin; Heidelberg: Springer Berlin Heidelberg.
- Machemer H, Machemer-Röhnisch S, Bräucker R, Takahashi K (1991) Gravitaxis in *Paramecium*: theory and isolation of a physiological response to the natural gravity vector. *J Comp Physiol A Neuroethol Sens Neural Behav Physiol* 168:1–12.
- Machemer-Röhnisch S, Machemer H (1984) Receptor current following controlled stimulation of immobile tail cilia in *Paramecium caudatum*. *J Comp Physiol* 154:263–271.
- Marcos, Fu HC, Powers TR, Stocker R (2012) Bacterial rheotaxis. *Proc Natl Acad Sci USA* 109:4780–4785.
- Martinac B, Machemer H (1984) Effects of varied culturing and experimental temperature on electrical membrane properties in *Paramecium*. *J Exp Biol* 108:179–194.
- Martinac B, Saimi Y, Kung C (2008) Ion channels in microbes. *Physiol Rev* 88:1449–1490.
- Masi E, Ciszak M, Santopolo L, Frascella A, Giovannetti L, Marchi E, Viti C, Mancuso S (2015) Electrical spiking in bacterial biofilms. *J R Soc Interface* 12:20141036.
- Maturana HR, Varela FJ (1973) *Autopoiesis and cognition: the realization of the living*, Ed 1. Dordrecht; Boston: D. Reidel Publishing Company.
- McGrath CL, Gout JF, Doak TG, Yanagi A, Lynch M (2014) Insights into three whole-genome duplications gleaned from the *Paramecium caudatum* genome sequence. *Genetics* 197:1417–1428.
- Mendelsohn M (1895) Ueber den Thermotropismus einzelliger Organismen. *Pflüger Arch* 60:1–27.
- Mingee CM (2013) Retention of a brightness discrimination task in *paramecia*, *P. caudatum*. *Int J Comp Psychol* 26:202–212.
- Mingee CM, Armus HL (2009) Unsuccessful reinforcement of a discrete action in *paramecia*, *P. caudatum*. *Psychol Rep* 105:533–538.
- Mogami Y, Baba SA (1998) Super-helix model: a physiological model for gravitaxis of *Paramecium*. *Adv Space Res* 21:1291–1300.
- Moolenaar WH, De Goede J, Verveen AA (1976) Membrane noise in *Paramecium*. *Nature* 260:344–346.
- Nagel U, Machemer H (2000) Physical and physiological components of the gravireponses of wild-type and mutant *Paramecium tetraurelia*. *J Exp Biol* 203:1059–1070.
- Naitoh Y (1984) Mechanosensory transduction in protozoa. In: *Membranes and sensory transduction* (Colombetti G, Lenci F, eds), pp 113–135. Boston: Springer US.
- Naitoh Y, Eckert R (1968a) Electrical properties of *Paramecium caudatum*: modification by bound and free cations. *Z Vergl Physiol* 61:427–452.
- Naitoh Y, Eckert R (1968b) Electrical properties of *Paramecium caudatum*: all-or-none electrogenesis. *Z Vergl Physiol* 61:453–472.
- Naitoh Y, Eckert R (1969) Ionic mechanisms controlling behavioral responses of *Paramecium* to mechanical stimulation. *Science* 164:963–965.
- Naitoh Y, Eckert R (1972) Electrophysiology of ciliate protozoa. *Exp Physiol Biochem* 5:17–31.
- Naitoh Y, Kaneko H (1972) Reactivated triton-extracted models of *Paramecium*: modification of ciliary movement by calcium ions. *Science* 176:523–524.
- Naitoh Y, Eckert R (1973) Sensory mechanisms in *Paramecium*. *J Exp Biol* 59:53–65.
- Naitoh Y, Eckert R, Friedman K (1972) A regenerative calcium response in *Paramecium*. *J Exp Biol* 56:667–681.
- Nakaoka Y, Oosawa F (1977) Temperature-sensitive behavior of *Paramecium caudatum*. *J Protozool* 24:575–580.
- Nakaoka Y, Machemer H (1990) Effects of cyclic nucleotides and intracellular Ca on voltage-activated ciliary beating in *Paramecium*. *J Comp Physiol A Neuroethol Sens Neural Behav Physiol* 166:401–406.
- Nakaoka Y, Iwatsuki K (1992) Hyperpolarization-activated inward current associated with the frequency increase in ciliary beating of *Paramecium*. *J Comp Physiol A Neuroethol Sens Neural Behav Physiol* 170:723–727.
- Nakaoka Y, Tokui H, Gion Y, Inoue S, Oosawa F (1982) Behavioral adaptation of *Paramecium caudatum* to environmental temperature. *Proc Jpn Acad Ser B* 58:213–217.
- Nakaoka Y, Oka T, Serizawa K, Toyotama H, Oosawa F (1983) Acceleration of *Paramecium* swimming velocity is effected by various cations. *Cell Struct Funct* 8:77–84.
- Nakaoka Y, Tanaka H, Oosawa F (1984) Ca²⁺-dependent regulation of beat frequency of cilia in *Paramecium*. *J Cell Sci* 65:223–231.
- Nakaoka Y, Tokioka R, Shinozawa T, Fujita J, Usukura J (1991) Photoreception of *Paramecium* cilia: localization of photosensitivity and binding with anti-frog-rhodopsin IgG. *J Cell Sci* 99:67–72.
- Nakaoka Y, Imaji T, Hara M, Hashimoto N (2009) Spontaneous fluctuation of the resting membrane potential in *Paramecium*: amplification caused by intracellular Ca²⁺. *J Exp Biol* 212:270–276.
- Nakatani I (1968) Chemotactic response of *Paramecium caudatum* (with 8 text-figures). 北海道大學理學部部要 16:553–563.
- Nakazato H, Naitoh Y (1993) Quantitative analysis of chemoaccumulation in specimens of *Paramecium caudatum* in relation to their motile activities. *J Exp Biol* 176:1–10.
- Naremsu N, Quek R, Chiam K-H, Iwade Y (2015) Ciliary metachronal wave propagation on the compliant surface of *Paramecium* cells. *Cytoskeleton* 72:633–646.
- Nishigami Y, Ohmura T, Taniguchi A, Nonaka S, Manabe J, Ishikawa T, Ichikawa M (2018) Influence of cellular shape on sliding behavior of ciliates. *Commun Integr Biol* 11:e1506666.
- Noguchi M, Nakamura Y, Okamoto K-I (1991) Control of ciliary orientation in ciliated sheets from *Paramecium*—differential distribution of sensitivity to cyclic nucleotides. *Cell Motil* 20:38–46.
- Oami K (1996a) Membrane potential responses controlling chemodispersal of *Paramecium caudatum* from quinine. *J Comp Physiol A Neuroethol Sens Neural Behav Physiol* 178:307–316.
- Oami K (1996b) Distribution of chemoreceptors to quinine on the cell surface of *Paramecium caudatum*. *J Comp Physiol A Neuroethol Sens Neural Behav Physiol* 179:345–352.
- Oertel D, Schein SJ, Kung C (1977) Separation of membrane currents using a *Paramecium* mutant. *Nature* 268:120–124.
- Oertel D, Schein SJ, Kung C (1978) A potassium conductance activated by hyperpolarization in *Paramecium*. *J Membr Biol* 43:169–185.
- Ogura A, Machemer H (1980) Distribution of mechanoreceptor channels in the *Paramecium* surface membrane. *J Comp Physiol* 135:233–242.
- Ohmura T, Nishigami Y, Taniguchi A, Nonaka S, Manabe J, Ishikawa T, Ichikawa M (2018) Simple mechanosense and response of cilia motion reveal the intrinsic habits of ciliates. *Proc Natl Acad Sci USA* 115:3231–3236.
- Oka T, Nakaoka Y (1989) Inactivation and activation of inward current during adaptation to potassium ions in *Paramecium caudatum*. *Cell Struct Funct* 14:209–216.
- Oka T, Nakaoka Y, Oosawa F (1986) Changes in membrane potential during adaptation to external potassium ions in *Paramecium caudatum*. *J Exp Biol* 126:111–117.
- Omori T, Ito H, Ishikawa T (2020) Swimming microorganisms acquire optimal efficiency with multiple cilia. *Proc Natl Acad Sci USA* 117:30201–30207.
- Ooya M, Mogami Y, Izumikurotani A, Baba SA (1992) Gravity-induced changes in propulsion of *Paramecium caudatum*: a possible

- role of gravireception in protozoan behaviour. *J Exp Biol* 163:153–167.
- O'Regan JK, Noè A (2001) A sensorimotor account of vision and visual consciousness. *Behav Brain Sci* 24:939–973.
- Osterman N, Vilfan A (2011) Finding the ciliary beating pattern with optimal efficiency. *Proc Natl Acad Sci USA* 108:15727–15732.
- Pallasdies F, Goedeke S, Braun W, Memmesheimer R-M (2019) From single neurons to behavior in the jellyfish *Aurelia aurita*. *Elife* 8:e50084.
- Párducz B (1967) Ciliary movement and coordination in ciliates. *Int Rev Cytol* 21:91–128.
- Parfrey LW, Lahr DJG, Knoll AH, Katz LA (2011) Estimating the timing of early eukaryotic diversification with multigene molecular clocks. *Proc Natl Acad Sci USA* 108:13624–13629.
- Pech LL (1995) Regulation of ciliary motility in *Paramecium* by cAMP and cGMP. *Comp Biochem Physiol Physiol* 111:31–37.
- Pezzulo G, Cisek P (2016) Navigating the affordance landscape: feedback control as a process model of behavior and cognition. *Trends Cogn Sci* 20:414–424.
- Pierce-Shimomura JT, Morse TM, Lockery SR (1999) The fundamental role of pirouettes in *Caenorhabditis elegans* chemotaxis. *J Neurosci* 19:9557–9569.
- Plattner H, Verkhatsky A (2018) The remembrance of the things past: conserved signalling pathways link protozoa to mammalian nervous system. *Cell Calcium* 73:25–39.
- Plattner H, Diehl S, Husser MR, Hentschel J (2006) Sub-second calcium coupling between outside medium and subplasmalemmal stores during overstimulation/depolarisation-induced ciliary beat reversal in *Paramecium* cells. *Cell Calcium* 39:509–516.
- Porter ME, Sale WS (2000) The 9 + 2 axoneme anchors multiple inner arm dyneins and a network of kinases and phosphatases that control motility. *J Cell Biol* 151:37–42.
- Powers WT (1973) *Behavior: the control of perception*. Oxford: Aldine.
- Preston RR (1990) A magnesium current in *Paramecium*. *Science* 250:285–288.
- Preston RR (1998) Transmembrane Mg²⁺ currents and intracellular free Mg²⁺ concentration in *Paramecium tetraurelia*. *J Membrane Biol* 164:11–24.
- Preston RR, Van Houten JL (1987) Localization of the chemoreceptive properties of the surface membrane of *Paramecium tetraurelia*. *J Comp Physiol* 160:537–541.
- Preston RR, Hammond JA (1998) Long-term adaptation of Ca²⁺-dependent behaviour in *Paramecium tetraurelia*. *J Exp Biol* 201:1835–1846.
- Preston RR, Saimi Y, Kung C (1990) Evidence for two K⁺ currents activated upon hyperpolarization of *Paramecium tetraurelia*. *J Membr Biol* 115:41–50.
- Preston RR, Saimi Y, Kung C (1992a) Calcium current activated upon hyperpolarization of *Paramecium tetraurelia*. *J Gen Physiol* 100:233–251.
- Preston RR, Saimi Y, Kung C (1992b) Calcium-dependent inactivation of the calcium current activated upon hyperpolarization of *Paramecium tetraurelia*. *J Gen Physiol* 100:253–268.
- Purcell EM (1977) Life at low Reynolds number. *Am J Phys* 45:3–11.
- Ramoino P, Fronte P, Beltrame F, Diaspro A, Fato M, Raiteri L, Stigliani S, Usai C (2003) Swimming behavior regulation by GABAB receptors in *Paramecium*. *Exp Cell Res* 291:398–405.
- Ramoino P, Scaglione S, Diaspro A, Beltrame F, Fato M, Usai C (2004) GABAA receptor subunits identified in *Paramecium* by immunofluorescence confocal microscopy. *FEMS Microbiol Lett* 238:449–453.
- Ramoino P, Candiani S, Pittaluga AM, Usai C, Gallus L, Ferrando S, Milanese M, Faimali M, Bonanno G (2014) Pharmacological characterization of NMDA-like receptors in the single-celled organism *Paramecium primaurelia*. *J Exp Biol* 217:463–471.
- Reid CR, Latty T, Dussutour A, Beekman M (2012) Slime mold uses an externalized spatial “memory” to navigate in complex environments. *Proc Natl Acad Sci USA* 109:17490–17494.
- Roberts AM (1970) Geotaxis in motile micro-organisms. *J Exp Biol* 53:687–699.
- Roberts AM (2010) The mechanics of gravitaxis in *Paramecium*. *J Exp Biol* 213:4158–4162.
- Roesle E (1903) Die Reaktion einiger Infusorien auf einzelne Induktionsschläge. *Z All Physiol* 2:139–168.
- Saimi Y (1986) Calcium-dependent sodium currents in *Paramecium*: mutational manipulations and effects of hyper- and depolarization. *J Membr Biol* 92:227–236.
- Saimi Y, Kung C (1987) Behavioral genetics of *Paramecium*. *Annu Rev Genet* 21:47–65.
- Saimi Y, Ling KY (1990) Calmodulin activation of calcium-dependent sodium channels in excised membrane patches of *Paramecium*. *Science* 249:1441–1444.
- Saimi Y, Hinrichsen RD, Forte M, Kung C (1983) Mutant analysis shows that the Ca²⁺-induced K⁺ current shuts off one type of excitation in *Paramecium*. *Proc Natl Acad Sci USA* 80:5112–5116.
- Saji M, Oosawa F (1974) Mechanism of photoaccumulation in *Paramecium bursaria*. *J Protozool* 21:556–561.
- Sartori P, Geyer VF, Scholich A, Jülicher F, Howard J (2016) Dynamic curvature regulation accounts for the symmetric and asymmetric beats of *Chlamydomonas flagella*. *Elife* 5:e13258.
- Satir P, Barkalow K, Hamasaki T (1993) The control of ciliary beat frequency. *Trends Cell Biol* 3:409–412.
- Satow Y, Kung C (1977) A regenerative hyperpolarization in *Paramecium*. *J Comp Physiol* 119:99–110.
- Satow Y, Kung C (1979) Voltage sensitive Ca-channels and the transient inward current in *Paramecium tetraurelia*. *J Exp Biol* 78:149–161.
- Satow Y, Kung C (1980) Ca-induced K⁺-outward current in *Paramecium tetraurelia*. *J Exp Biol* 88:293–304.
- Satow Y, Kung C (1976) A mutant of *Paramecium* with increased relative resting potassium permeability. *J Neurobiol* 7:325–338.
- Satow Y, Murphy AD, Kung C (1983) The ionic basis of the depolarizing mechanoreceptor potential of *Paramecium tetraurelia*. *J Exp Biol* 103:253–264.
- Schafer WR (2018) The worm connectome: back to the future. *Trends Neurosci* 41:763–765.
- Schönborn W, Dörfelt H, Foissner W, Krienitz L, Schäfer U (1999) A fossilized microcosmos in triassic amber. *J Eukaryot Microbiol* 46:571–584.
- Schultz JE, Klumpp S, Benz R, Schürhoff-Goeters WJ, Schmid A (1992) Regulation of adenylyl cyclase from *Paramecium* by an intrinsic potassium conductance. *Science* 255:600–603.
- Seung S (2012) *Connectome: how the brain's wiring makes us who we are*. Boston: Houghton Mifflin Harcourt.
- Seymour JR, Amin SA, Raina JB, Stocker R (2017) Zooming in on the phycosphere: the ecological interface for phytoplankton–bacteria relationships. *Nat Microbiol* 2:17065.
- Smith S (1908) The limits of educability in *Paramócium*. *J Comp Neurol Psychol* 18:499–510.
- Sourjik V, Wingreen NS (2012) Responding to chemical gradients: bacterial chemotaxis. *Curr Opin Cell Biol* 24:262–268.
- Takahashi M, Naitoh Y (1978) Behavioural mutants of *Paramecium caudatum* with defective membrane electrogenesis. *Nature* 271:656–659.
- Tamm S (1994) Ca²⁺ channels and signalling in cilia and flagella. *Trends Cell Biol* 4:305–310.
- Taylor AR (2009) A fast Na⁺/Ca²⁺-based action potential in a marine diatom. *PLoS One* 4:e4966.
- Tominaga T, Naitoh Y (1992) Membrane potential responses to thermal stimulation and the control of thermoaccumulation in *Paramecium caudatum*. *J Exp Biol* 164:39–53.
- Tominaga T, Naitoh Y (1994) Comparison between thermoreceptor and mechanoreceptor currents in *Paramecium caudatum*. *J Exp Biol* 189:117–131.
- Tu Y (2013) Quantitative modeling of bacterial chemotaxis: signal amplification and accurate adaptation. *Annu Rev Biophys* 42:337–359.

- Tu Y, Shimizu TS, Berg HC (2008) Modeling the chemotactic response of *Escherichia coli* to time-varying stimuli. *Proc Natl Acad Sci USA* 105:14855–14860.
- Tytell E, Holmes P, Cohen A (2011) Spikes alone do not behavior make: why neuroscience needs biomechanics. *Curr Opin Neurobiol* 21:816–822.
- Valentine M, Yano J, Houten JLV (2008) Chemosensory transduction in *Paramecium*. *Jpn J Protozool* 41:1–7.
- Valentine MS, Van Houten JL (2016) Methods for studying ciliary-mediated chemoresponse in paramecium. *Methods Mol Biol* 1454:149–168.
- Valentine MS, Rajendran A, Yano J, Weeraratne SD, Beisson J, Cohen J, Koll F, Van Houten J (2012) *Paramecium* BBS genes are key to presence of channels in cilia. *Cilia* 1:16.
- Van Houten J (1998) Chemosensory transduction in *Paramecium*. *Eur J Protistol* 34:301–307.
- Van Houten J, Hansma H, Kung C (1975) Two quantitative assays for chemotaxis in *Paramecium*. *J Comp Physiol* 104:211–223.
- Verworn M (1889) *Psycho-physiologische Protisten-Studien: Experimentelle Untersuchungen*. Jena: G. Fischer.
- Walczak CE, Nelson DL (1994) Regulation of dynein-driven motility in cilia and flagella. *Cell Motil Cytoskeleton* 27:101–107.
- Wan KY (2018) Coordination of eukaryotic cilia and flagella. *Essays Biochem* 62:829–838.
- Wan KY, Jékely G (2020) Origins of eukaryotic excitability. *arXiv* 200713388.
- Wang H, Swore JJ, Sharma S, Szymanski JR, Yuste R, Daniel TL, Regnier M, Bosma M, Fairhall AL (2020) From neuron to muscle to movement: a complete biomechanical model of *Hydra* contractile behaviors. *bioRxiv* 2020.12.14.422784.
- Webb B (2001) Can robots make good models of biological behaviour? *Behav Brain Sci* 24:1033–1050.
- Wichterman R (1986) *The biology of paramecium*. New York: Springer US.
- Winet H, Jahn TL (1974) Geotaxis in protozoa I. A propulsion–gravity model for *Tetrahymena* (Ciliata). *J Theo Biol* 46:449–465.
- Wolpert DM, Ghahramani Z (2000) Computational principles of movement neuroscience. *Nat Neurosci* 3 [Suppl]:1212.
- Wood DC (1991) Electrophysiology and photomovement of stentor. In: *Biophysics of photoreceptors and photomovements in microorganisms*, NATO ASI Series (Lenci F, Ghetti F, Colombetti G, Häder DP, Song PS, eds), pp 281–291. New York: Springer US.
- Yang X, Dillon RH, Fauci LJ (2008) An integrative computational model of multiciliary beating. *Bull Math Biol* 70:1192–1215.
- Yano J, Rajendran A, Valentine MS, Saha M, Ballif BA, Van Houten JL (2013) Proteomic analysis of the cilia membrane of *Paramecium tetraurelia*. *J Proteomics* 78:113–122.
- Yano J, Valentine MS, Van Houten JL (2015) Novel insights into the development and function of cilia using the advantages of the *Paramecium* cell and its many cilia. *Cells* 4:297–314.